





1875-1876

1875-1876

1875-1876

1875-1876
1875-1876

AN ANALYSIS
OF
GOTHICK ARCHITECTURE:

ILLUSTRATED BY A SERIES OF UPWARDS OF SEVEN HUNDRED EXAMPLES OF
DOORWAYS, WINDOWS, ETC.

AND
ACCOMPANIED WITH REMARKS
ON THE
SEVERAL DETAILS OF AN ECCLESIASTICAL EDIFICE.

BY
RAPHAEL AND J. ARTHUR BRANDON,
Architects,
AUTHORS OF "PARISH CHURCHES," "OPEN TIMBER ROOFS OF THE MIDDLE AGES, ETC.



New Edition.

VOLUME I.

LONDON :
W. KENT AND CO. (LATE D. BOGUE), 86, FLEET STREET.

MDCCCLVIII.

LONDON:
J. & W. RIDER, PRINTERS,*14, BARTHOLOMEW CLOSE

LIST OF SUBSCRIBERS.

George Abbot, Esq. Barnstaple, Devonshire.

C. B. Allen, Esq. Argyll-street.

George Allen, Esq. Architect, Tooley-street.

T. G. Andrews, Esq. Architect, York.

Arthur Ashpitel, Esq.

J. P. St. Aubyn, Esq. Architect.

Mr. Daniel Bacon, Colchester.

The Rev. H. De Foe Baker, Warden of Browne's Hospital,
Stamford.

G. F. Ballard, Esq. Upper Albany-street.

William Bardwell, Esq. Architect, Queen-street.

James Barr, Esq. Putney.

Charles Barry, Esq. R. A. Architect, Great George-street.

J. M. Belisario, Esq. Clifton-street.

T. Bellamy, Esq. Architect, Charlotte-st. Bedford-square.

G. W. Billings, Esq. Architect, Lower Belgrave-place.

Joseph Biscoe, Esq. Yonge St. Canada.

John Blyth, Esq. Architect, Aldersgate-street.

W. I. Booth, Esq. Architect, Red Lion-square.

The Rev. Charles Boutell, the Rectory, Downham Market.

David Brandon, Esq. Gravesend.

Mr. W. Bremer, Colchester.

Rev. Waldegrave Brewster, Hawarden.

Messrs. Broadbent and Hawley, Stone-masons, Leicester.

E. H. Brown, Esq. Architect, Beaufort-buildings.

R. P. Browne, Esq. Architect, Clement's-lane.

Edward Browning, Esq. Architect, Stamford.

William Burgess, Esq. Architect.

T. T. Bury, Esq. Architect, Golden-square.

The Rev. J. L. Capper, Waltham Abbey.

E. J. Carlos, Esq. Old Jewry.

Sir William Chatterton, Bart. Berkeley-square.

Ewan Christian, Esq. Architect, Bloomsbury-square.

G. Somers Clarke, Esq. Architect, Brixton-road.

Joseph Clarke, Esq. Architect, Lincoln's-inn-fields.

The Venerable Archdeacon Clerke, Oxford.

H. Clutton, Esq. Architect, Whitehall-place.

C. R. Cockerell, Esq. R.A. Architect, Bank of England.

J. K. Colling, Esq. Architect, Barclay-street.

G. Cottam, Esq. Oxford-street.

L. N. Cottingham, Esq. Architect.

J. E. Coxe, Esq. Architect, Hyde Park-st. Bayswater-road.

Leonard S. Coxe, Esq. Brunswick-place, Regent's-park.

Mr. Thomas Crisp, Colchester.

Lewis Cubitt, Esq. Architect, Great Russell-street.

H. Currey, Esq. Architect, Old Palace-yard.

R. L. Curtis, Esq. Stratford.

Francis Darby, Esq.

G. A. Dean, Esq. Architect, Stratford, Essex.

Mr. William Dearn, Colchester.

Monsieur Dedaux, Architect, Alençon.

F. T. Dollman, Esq. Architect, Mornington-place.

Thomas J. Duff, Esq. Architect, Newry, Ireland.

Thomas W. Dunch, Esq. Architect, Stepney-causeway.

C. Dyson, Esq. Surveyor, Stratford-grove, Essex.

C. Eales, Esq. Architect, Langham-place.

George Hay Edwards, Esq. Southampton.

The Rev. Irvin Eller, St. Clement's, Salt Fleetly.

E. W. Elmslie, Esq. Architect.

George Enoch, Esq. Architect, Edward-st. Portman-sq.

The Rev. T. S. Escott, Gedney, Lincolnshire.

B. G. Eyton, Esq. Architect and Surveyor, Grosvenor-street
West, Pimlico.

Benjamin Ferrey, Esq. Architect, Trinity-pl. Charing Cross.

James Field, Esq. Architect, Adelaide-place, London-bridge.

— Forster, Esq. New Ormond-street.

Messrs. Thomas Foster and Son, Architects, Park-street,
Bristol.

Frederick J. Francis, Esq. Architect, Bruton-street.

Mr. William Franklin, Colchester.

The Lord Bishop of Fredericton.

G. R. French, Esq. Architect, Sussex-gardens, Hyde-park.

Thomas Fuller, Esq. Architect, North-crescent, Alfred-place.

G. A. Gagen, Esq. Architect, Stepney-green, Mile End-road.

R. B. Gardiner, Esq. Architect, Tunbridge.

Henry Garling, Esq. Architect, Bedford-row.

LIST OF SUBSCRIBERS.

Mr. W. Gerry, Gilbert-street, Grosvenor-square.
 The Rev. John Edgar Gibson, Bermondsey.
 Henry Goddard, Esq. Architect, Leicester.
 Mr. Goodman, Furnival's Inn.
 Stephen Gomme, Esq. Architect, Regent-street.
 The Government School of Design, Somerset-house.
 Robert Gray, Esq. Brompton-terrace.
 Arthur Green, Esq. Architect, St. Helen's-place.
 John E. Gregan, Esq. Architect, Manchester.

William Gillbee Habershon, Esq. Architect, St. Neot's.
 E. C. Hakewill, Esq. Architect, Craig's-court.
 J. H. Hakewill, Esq. Architect, Craig's-court.
 William Hambley, Esq. Architect, Winchester-buildings.
 George E. Hamilton, Esq. Wolverhampton.
 H. J. Hammon, Esq. Architect, Brooksby-st. Barnsbury-park.
 Charles Hansom, Esq. Architect, Bristol.
 Philip Hardwick, Esq. R.A. Architect, Russell-square.
 L. L. Hartley, Esq. Richmond.
 The Rev. G. L. Harvey, Yate Rectory.
 Mr. H. W. Hayward, Colechester.
 Charles Henman, Esq. Architect, Clifford's Inn.
 Thomas Henning, Esq. Lower Belgrave-place.
 T. L. Henslow, Esq. Clement's Inn.
 J. Hicks, Esq. Architect, Bristol.
 Thomas Hillyer, Esq. Architect, Ryde, Isle of Wight.
 B. H. Hodgson, Esq. Civil Service, Calcutta.
 H. Holland, Esq. Architect, John-street, Adelphi.
 W. S. Hollands, Esq. Architect, Bermondsey-square.
 J. Howell, Esq. Architect, Vincent-square.
 Mr. S. M. Hubert, York-road, Lambeth.

Charles Innes, Esq. Architect, Highbury.
 Robert Innes, Esq. Lloyd's.

H. B. Jarling, Esq. Architect, Bedford-row.
 J. Jennings, Esq. Architect, King-street.
 A. Jenour, Esq. Architect, Adelphi.
 Frederick Johnstone, Esq. Architect, Baker-st. Portman-sq.
 Richard Jones, Esq. Chapel-street, Belgrave-square.

Mr. F. Kemp, Colechester.
 The Rev. E. Kempe, Clifton.
 H. E. Kendall, Jun. Esq. F.S.A. Architect, Brunswick-sq.
 H. Kennedy, Esq. Architect, Bangor.

Richard Lane, Esq. Architect, Manchester.
 A. Lang, Esq. Architect, Buckingham-street.
 Thomas Hayter Lewis, Esq. Architect, Baker-street.
 Frederick Leslie, Esq. Conduit-street.
 — Leslie, Esq. Architect, Aberdeen.
 B. E. Lindo, Esq. Winchester-buildings.

W. H. Lindsey, Esq. Architect, Priory-cottages.
 T. Little, Esq. Architect, Northumberland-place.
 The London Architectural Society.
 George Low, Esq. Architect, Clements-lane.
 Charles Luard, Esq. Upper Wimpole-street.
 Mr. Henry Lufkin, Colechester.
 Frederick Mackenzie, Esq. Hampstead-road.
 George Mackenzie, Esq. Architect, Claremont-row.
 George Mair, Esq. Architect, Charlotte-st. Bedford-square.
 The Rev. W. Mallock, Cheriton Bishop, near Exeter.
 Charles Mannering, Esq. Coleby Hall.
 F. Marrable, Esq. Architect, Lancaster-place.
 A. Mason, Esq. Lime-street.
 James Govey Mason, Esq. Bristol.
 George Mathew, Esq. Trinity-college, Cambridge.
 M. Meredith, Esq. Architect, Bloomfield-street.
 David Mickle, Esq. Architect, Queen-square, Bloomsbury.
 David Mocatta, Esq. Architect, Brunswick-square.
 George Moore, Esq. F.R.S. Architect, Lincoln's-inn-fields.
 — Morriss, Esq. Union-terrace, Peckham.
 John Mullins, Esq. Architect, St. John's Grove, North Brixton.

Edwin Nash, Esq. Architect, Moorgate-street.
 D. C. Nichols, Esq. Architect, London.
 The Marquess of Northampton.

Harry Oliver, Esq. Architect, Hatton-garden.

F. A. Paley, Esq.
 Joseph Parkinson, Esq. Architect, Sackville-street.
 J. Peacock, Esq. Architect, Gt. Russell-street.
 Thomas Percy, Esq. Architect, Alfred-place.
 Thomas W. Plum, Esq. Architect, Camberwell.
 G. Porter, Esq. Architect, Bermondsey.
 J. Porter, Esq. Mansfield-street.
 George Powell, Esq. Ridlington.
 S. Pratt, Esq. Bond-street.

William Railton, Esq. Architect, Carlton-chambers.
 N. T. Randall, Esq. Architect, Harleyford-road.
 Drummond Rawnsley, Esq. Little Hadham.
 Henry Rhodes, Esq. Architect, Margaret-street.
 Harry Ralph Ricardo, Esq. Architect, Camberwell.
 Mr. William Rice, Chester-terrace.
 Edward Richardson, Esq. Sculptor, Melbury-terrace.
 Lawford Richardson, Esq. Blackheath.
 Robert Ritchie, Esq. Architect, Blackheath-hill.
 Edward Roberts, Esq. Architect, Devonshire-place, Edge-ware-road.
 Henry Roberts, Esq. Architect, Suffolk-street, Pall Mall East.

LIST OF SUBSCRIBERS.

The Rev. James Round, Colchester.

Denis M. Samuel, Esq. Sussex-place, Regent's-park.

S. M. Samuel, Esq. Park-crescent, Portland-place.

Jacob Samuda, Esq. Blackwall.

J. D'A. Samuda, Esq. Blackwall.

H. B. Sandall, Esq. Architect, Palace New-road, Lambeth.

R. C. Saunders, Esq. North-crescent, Bedford-square.

G. G. Scott, Esq. Architect, Spring-gardens.

Mr. James Seovell, Colchester.

Mr. William Seovell, Colchester.

A. C. Seymour, Esq. Architect, Bath.

E. Sharpe, Esq. Architect, Lancaster.

E. H. Shellard, Esq. Architect, Manchester.

Sydney Smirke, Esq. Architect, Berkeley-square.

Hugh Smith, Esq. Bedford-row.

Joseph Springbett, Esq. Hermitage-place, St. John-street-road.

H. C. Stewart, Esq. St. John's-wood-grove.

The St. Alban's Architectural Society.

E. Tarn, Esq. Millman-street.

John Taylor, Esq. Architect, Parliament-street.

S. S. Teulon, Esq. Architect, Lansdowne-place.

The Rev. Caddy Thomas, Brandeston, Norwich.

The Rev. Hugh Totty, D.D. Bath.

— Travis, Esq. Architect, Manchester.

G. B. Trench, Esq. Sussex-gardens, Hyde-park.

J. Turner, Esq. Architect, Lower Belgrave-place.

William Vizard, Esq. Spring-gardens.

Lewis Vulliamy, Esq. Architect, Saville-row.

Messrs. Waller, Charles-street.

The Rev. D. C. Whalley, Great Wenham, Suffolk.

Thomas Willement, Esq. London.

Mr. J. Williams.

The Rev. Robert Willis, F.R.S. Jacksonian Professor, Cambridge.

Edward James Wilson, Esq. F.S.A. Lincoln.

Edmund Woodthorpe, Esq. Architect, Jewin-street.

Stephen Wright, Esq. Architect, Somerset-street.

H. I. Wright, Esq. Architect, Park-street, Westminster.

T. H. Wyatt, Esq. Architect, Great Russell-street.

W. Young, Esq. Architect, Tavistock-place, Tavistock-square.



P R E F A C E.



OF the numerous works recently called into existence by the prevalent spirit of inquiry and research into the Ecclesiastical Architecture of the Middle Ages, none has supplied such an analysis of details as is absolutely essential, no less for the complete abstract elucidation of the principles of this great art, than for their correct practical application. The present work has been undertaken with a view to supply this deficiency, by presenting a series of good and pure specimens of the various details which occur in Church Architecture, as they are exemplified in existing Edifices. The examples thus selected commence with the closing style of the Romanesque,* and range throughout the Gothick era, properly so called.

The Authors, desirous to adhere in every respect to their plan of producing a practical rather than an historical work on English Church Architecture, have purposely avoided all notice and illustration of the Architecture of the Anglo-Saxons. Many excellent treatises have been devoted to the investigation of the style of building at this remote period, and much of both curious and valuable information has been thus elicited. Saxon Architecture, however, though abounding in materials for interesting research to the antiquary and historian, is at best but rude and barbarous as a constructive system, and consequently by the architect of the present day it cannot be considered as a guide or authority. And indeed its successor, the Anglo-Norman, has but very few, if any claims to our regard and adoption. That this style

* This term was first adopted by the Rev. W. Gunn, in his "Inquiry on Gothic Architecture." In a note explanatory of this term, Mr. Gunn thus justifies its analogy:—"A modern Roman, of whatever degree, calls himself *Romano*, a distinction he disallows to an *Inhabitant* of his native city, who, though long domiciliated, yet, from dubious origin, foreign extraction or alliance, he stigmatizes by the term *Romanesco*. I consider the architecture under discussion (Norman), in the same point of view," p. 80.

possesses many features in themselves highly meritorious, we readily admit; yet on the one hand, we trace it in all the impress of a lingering barbarism, and on the other, true to its Roman prototype, it is shackled even in its noblest efforts by the characteristic *horizontal* of Classick Architecture. Indeed we do not find Mediæval Architecture to have been absolutely set free from the influence of debased ancient principles, until, with the complete establishment of the pointed arch, the manifold elements of building had undergone an entire, although a gradual renovation. It was then that, in the Early English style, Gothick Architecture attained to its first decided development.

With the same view to their practical usefulness, the examples given in this work have been entirely derived from English Churches. Continental Gothick, beautiful as it is in itself, and influenced by the same spirit with our own, cannot be consistently associated with English details: each possesses peculiarly distinctive features, which it is impossible to blend together without serious injury to both.

It has also been a principal object of the Authors to collect their examples from Parish Churches only; and to this determination they have adhered with very few exceptions. Cathedrals, and the large Abbey and Conventual Churches, have been already amply illustrated, perhaps even to the detriment of the art which it has been the object of such illustrations to advance: for, from the want of proper information upon the subject of architectural details, considered with reference to Edifices of various designs and magnitudes, we see in many Churches of comparatively recent erection, numerous features belonging essentially to our Cathedrals, and contributing in the very highest degree to their appropriate decoration; but which, from the necessarily diminished proportions and general incongruity of effect, appear absolutely ridiculous, when introduced into the architectural composition of the smaller Edifice.

Any remarks, therefore, that occur in the course of the work, as well as the illustrations themselves, must, unless otherwise stated, be understood to have special reference to Parochial Structures.

The illustrative portion of the work will be found to have been divided into two sections: of these the first is devoted solely to a full exposition of the

mason's art in all its various branches ; while the second embraces a similar elucidation of detail in the important accessories of wood-work and metal-work. In the execution of the Plates, no less than in their selection, the strictly practical character of the work has been uniformly kept in view ; without aiming at pictorial beauty, the object has been to ensure the greatest possible fidelity and accuracy of delineation : to accomplish this, the authors have personally visited every Church from which examples have been drawn, and have themselves taken the admeasurements, made the drawings, and engraved them on zinc. Two subjects only form exceptions, the one a floor-cross from St. Patrick's Cathedral, Dublin, which they have drawn from a *rubbing* kindly sent them by J. K. Colling, Esq. ; and the other, the diapers upon the shield of Sir Robert de Vere, Earl of Oxford, A.D. 1221, in the Church of Hatfield Broadoaks, Essex, for a rubbing of which the Authors are indebted to the kindness of the Rev. Charles Boutell : to whom they also have to offer their sincere acknowledgements for much valuable assistance in the arrangement of their letter-press description. Had the plates been executed by more practised zincographers, they would doubtless have exhibited a higher degree of artistick treatment, and greater beauty of finish ; but this, it was feared, might have involved the risk of some slight inaccuracy, and thus have considerably diminished the utility of the examples.

The humble labours of the Authors have been sweetened and rendered dear to them by the sincerest admiration for those noble monuments of piety and skill, our English Churches ; which even now, cruelly mutilated and dishonoured as they often remain, are still foremost among the glories of our land : and should their exertions in any way tend to encourage and enhance sentiments of interest in the matchless Architecture of the Middle Ages, their desire will be most fully accomplished.

INTRODUCTION.



VERY shortly after the commencement of the second thousand years of the Christian era, the Ecclesiastical Architecture of this country, as if preparatory to the accession of a Norman dynasty, became assimilated to the peculiar form of Romanesque then established in the Duchy of Normandy, and at the present day distinguished among ourselves as the Anglo-Norman style. The first principles of this style appear to have been introduced into England by Edward the Confessor, or possibly by Canute, and by them applied to the construction of the numerous Churches erected during their reigns : so that the rapid improvement in Church Architecture which took place under the Norman princes, was in reality the development of a system fairly established before the Conquest. That the Anglo-Norman architects raised their style to the very highest degree of perfection to which it was capable of attaining, is most evidently shown by many of their works which yet remain : still, intrinsically excellent as it became, there was in its very essence that which necessarily involved its suppression. It appears, indeed, true that Architecture shares in the general instability of things terrestrial : for by the working, as it would seem, of some latent yet constraining law, one style, or one distinctive form of a style, no sooner arrives at full maturity, than it is gradually superseded by some other form or style, differing in a greater or less degree, yet still essentially differing. But besides the influence of this inherent principle of change, the Anglo-Norman retained by far too much of ancient classick architecture to admit of its permanent establishment. The low and massive proportions, the ponderous and self-supported walls, the rectangularly recessed arches, the square abaci and plinths, and the strictly superficial character of every decoration,—these all spoke rather of a grander style in a state of debasement, of Roman degenerated to Romanesque, than of a great style rising upward from its foundation ; of the Architecture of the Middle Ages preparing to measure its strength with the Architecture of antiquity. And again, in the Anglo-Norman the essentially aspiring and expansive character of Christian Architecture was wanting ; at the best, there was something Basilican in it,—something not far removed from a Pagan origin, though not itself actually Pagan. Therefore, in reviewing

the Transition Period, which intervened between the final close of the Anglo-Norman and the full establishment of the Anglo-Gothick styles, all regret for the passing style is more than overbalanced by joyous contemplations of superior excellence in its successor. After an Architectural struggle of unusually protracted continuance, during which the elementary features of the new style appeared blended with the established characteristicks of the old, Gothick Architecture assumed a definite form; and at once gave full assurance of its superiority, in the lightness, the elegance, the loftiness, and the spaciousness which distinguished the Early English style:—"a style," observes the author of the *Manual of Gothic Architecture*,* "so transcendently beautiful, so perfect in itself, that it may well be questioned if ever a parallel to it has existed in any age or country, or if the hands that reared or the minds that conceived the choirs of Ely and Lincoln Cathedrals, the Abbeys of Whitby, Westminster, and Rivaux, have not achieved that which, as unsurpassed by former ages, so future generations shall never see equalled again."

As the reign of the third Henry (A.D. 1216—1272) approached its close, certain novelties, both of detail and combination, appeared in the works of Gothick Architects. In place of distinct lancets, isolated by strips of the main wall in which they were pierced, and yet combined by continuous dripstones and hoodmolds, windows of large dimensions and divided into several lights by mullions, were introduced; and with the mullions came tracery-bars, filling the window-heads with various rich geometrical figures:—the alternation of bold projections and deep hollows in the mouldings gave way to a system of grouping, richer and far more beautifully blended:—shafts ceased to stand detached, or banded into clusters, and became instead firmly compacted into a mass; the bands, no longer of any use, real or apparent, being suppressed:—foliage, ever a favourite Gothick enrichment, appeared more closely studied from the natural tree or plant; and instead of waving trefoils, expanding from clustered and upward-tending stalks, the several leaves were disposed in a wreath-like form, and made to encircle the member which they adorned:—more abundant and diversified decoration also, began to overspread the several component members of a Gothick edifice, imparting a finished richness to the whole.

Thus it was that the Early English gradually merged into the Decorated,—that most admirable style, which has identified with the Edwardian era (abounding as it does in matters of high historick interest) the perfection of Anglo-Gothick art. As this style advanced, its several peculiarities assumed a very clearly defined distinctness of character; while, at the same time, the geometrical precision of its earliest form yielded to a predominance of lines, flowing with graceful undulations.

A tendency to direct verticality, placing itself in, perhaps, violent contrast with the

* *A Manual of Gothick Architecture*, page 230, by F. A. Paley, Esq., M.A. Van Voorst.

Romanesque horizontalism of the Anglo-Norman, had been in the Early English Gothick the special characteristic of that beautiful style. In the Decorated Gothick, the principal lines of the composition verged pyramidically, rather than vertically or horizontally. And, to complete the series of changes in this fundamental principle, a third distinct period of Anglo-Gothick was distinguished by the prevalence of perpendicular lines, crossed at right angles by others of scarcely less importance than themselves. This last gorgeous style, from the position of its leading lines denominated the Perpendicular Gothick, gradually supplanted the Decorated; as the mature, yet ever chaste and harmonious richness of the Decorated had itself succeeded to a supremacy before enjoyed by the more youthful grace and elegance of the Early English. For a while the new style was content to retain much that was characteristic of its predecessor, in combination with what was more especially its own; and of this, the first (or, historically speaking, the Lancastrian) period of the Perpendicular Gothick, although certainly wanting in the majestic beauty of the pure Decorated, it would be difficult to speak in terms of too high admiration. With the depressed arch of the Tudors, however, came that multiplicity, profusion, and minuteness of panelling, and other ornamental detail, which but too clearly indicated a decadence in Architectonick taste. A single retrograde movement in Architecture is almost always a fatal symptom. Debasement, once admitted, speedily pervades the entire system; and then a period of utter degradation will intervene, before the art can again revive, animated by its former exalted spirit, and capable of aspiring to even nobler achievements.

It has been thus with the Church Architecture of the Middle Ages: magnificent even in decline, it spread over its last great works those elaborately fretted vaults of fan-tracery, as monumental canopies, not unworthy of Gothick art: and then speedily came on the long and dreary age of Architectural debasement.

Taking thus a retrospective view of the history of our Ecclesiastical Edifices, there is much reason for associating with the past, both present congratulation and future hope: for it is truly satisfactory to observe the existing recognition of the superior merit of Mediæval Architecture, *as Church Architecture*, and the prevalent anxiety to obtain correct views both of its principles and of their practical application; and from the actual existence of such a state of feeling it is not unreasonable to anticipate that complete revival of the original Gothick spirit, which may even lead to an Architectural perfection hitherto unknown. But before advance can become practicable, it is indispensable that there be a recovery from retrogression. The first thing to be attained is the mastery of Gothick Architecture, as it *has been* practised. It is accordingly the object of these volumes, by conveying a clear and full exposition of the various details of Church Architecture as they *exist* in our Churches, to contribute, in however humble a degree, toward the attainment of this all-important pre-

liminary step. And here it may be remarked, that undue importance must not be attached to the terms Early, Decorated, and Perpendicular Gothick, as though they denoted so many *distinct styles* in Church Architecture.* For convenience in studying, and also with a view to simplify the process of classifying details, these terms have been invented and assigned, as distinctive titles, to certain Architectural forms or periods : the forms and periods themselves, however, are really but modifications and progressive eras of one and the same style ; and it is most important that in this light they should be regarded. As it has been already observed, “the great principles and essential characteristicks of Gothick Architecture remained unchanged, from the first establishment to the final suppression of the style : and hence, though the several conditions of Gothick Architecture have led to its subdivision into styles, each distinguished by a peculiar name ; still, these minor styles must, in the first instance, be regarded as mere subdivisions, or rather as the more prominent transition stages of the one great style, the Gothick.”† Accordingly, notwithstanding that dates have been assigned to these several subdivisions of Gothick Architecture, it is impossible to fix with absolute and peremptory certainty where one stage of the art left off, and where another began. There can be little doubt but that Early English was still in use in some parts of the kingdom (unwilling to depart, as it were, from the scene of its many glorious triumphs) at the very same time that, in other localities, complete Decorated was struggling into existence ; and in like manner, Decorated may be observed to have still lingered here and there for a considerable period subsequent to the time that is generally considered to mark the establishment of Perpendicular. The usually received dates, therefore, of the commencement and close of the Early English, Decorated, and Perpendicular Gothick, in strict reality serve only to indicate those minor stages of transition which intervened between the several more important periods of Anglo-Gothick Architecture ; and in this capacity they are very useful : their utility is greatly increased also, from the circumstance of their ranging with the reigns of successive sovereigns ; for the association of Architecture with history is always most desirable.

In pursuing the study of Mediæval Architecture, it is absolutely necessary to pass on from written and illustrated treatises to original examples themselves. Gothick Art can

* This nomenclature, introduced by the late Mr. Rickman, has been retained by the Authors, as being in itself sufficiently well adapted to its purpose ; while at the same time it possesses the very important advantage of being generally recognized and understood. And, in like manner, where words already exist which clearly explain the different details of Architecture, they have uniformly been adopted ; but where such terms are wanting, free use has been made of the nomenclature of the Middle Ages revived by Professor Willis.

† Lectures upon English Church Architecture, delivered before the St. Alban's Architectural Society, by the Rev. C. Boutell, M.A., Secretary. May, 1846.

neither be so completely described, nor so illustrated by the pencil, as to convey any adequate conceptions of its reality. It may, therefore, be held as an axiom, that personal inspection of the old churches of England is the *only mean*, by which it can be possible now, either to appreciate the genius of our Mediæval architects, or to sympathize with the spirit which animated them. But in carefully studying early remains, it is possible that even experienced observers may sometimes be misled by a practice, the very existence of which can scarcely be considered to have received a general recognition: the practice, that is to say, of occasionally assimilating work in a later style to some already existing portion of an incomplete general design.

This is a remarkable and highly important circumstance; lying, as it does, at the very basis of authoritative rules for restoration of original edifices by ourselves. And indeed, it forms a strongly marked exception to the usual practice; for it was a general rule with the builders of the Middle Ages never to fall back upon a past era of their art, even when engaged in completing structures of a bygone age. Influenced by a spirit, which in these times it is scarcely possible yet to understand, their sole aim was advancement: one "Master" was ever anxious to surpass another; and each sought, in any fresh design, to improve upon his own previous works. It would seem that when engaged in *repairing*, or making *additions* to their churches, the style then prevailing was invariably and boldly adopted: the architects of those days trusted in the beautiful harmony which breathes throughout their great art, and which they well knew must necessarily exist the same at any period of it. But when they had to *complete* a design, left from the first imperfect, they appear to have been induced, in some instances, to mold their work in such a manner as to maintain, *in the general outline*, some degree of uniformity throughout the whole.

The grand and venerable Abbey Church of St. Alban preserves examples, no less remarkable for diversity than excellence, of the proceedings of the "Masters" of old. The Nave, including the triforia and clearstory, was originally Anglo-Norman; plain and massive in the extreme, yet strikingly majestick in its austere simplicity. It would appear that when, after a lapse of time, the early English Gothick was fairly established, it was determined to alter the Nave to that style, and thereby improve it. The work of renovation accordingly commenced, began at the west, and the design extended to the first four arches on the north side, and the three corresponding ones on the south. We must imagine that for some reason the works were suspended, and that an interval of several years elapsed before they were again resumed: for when once more proceeded with, the style had considerably progressed, and Early English Gothick was shortly to give way to Decorated. Two more of the Anglo-Norman arches on the south side were rebuilt at this period, their general design being the same, the strings, &c., corresponding with the earlier work, while a partial difference is

observable in the moldings and other ornamental details. Again were the works discontinued; nor was any further effort attempted, with a view to the reconstruction of the Church, until the Decorated Gothick had attained to almost the very highest degree of its beauty and perfection. And here begins, correctly speaking, the work of assimilation. Since the commencement of these improvements, Gothick Architecture had gradually undergone a remarkable change: so that it is very certain that, had not the architect been desirous of assimilating his work to that of his predecessors, he would have adopted a design very different from that which has actually been carried into effect. As it is, the general character of the Early English pier-arches is here preserved, though the moldings of the arch-heads, and the capitals of the piers, are pure Decorated. In the south triforium also, the arrangement of both the arches and sub-arches of the arcade corresponds with the similar members in the earlier work; shafts (though no longer detached) are placed in the jambs, and strings are continued above and below the arcade, in which the long trails of tooth-ornament are superseded by a series of the square flower of four leaves. And again, the walls of the clearstory (quite at variance with the practice of the time) are pierced with lancet windows, in evident continuation of the original design: the proportions of these windows are precisely similar to those in the adjacent Early English portion of the Church, but their moldings are beautiful and pure Decorated. The corbel table also, beneath the parapet on the exterior, is continued: but in the later portion of it, the Early English noteh-heads are seen to have given way to a series of male and female heads (valuable specimens of the head-dresses of the period) and lions' heads, peculiarly a Decorated ornament.

In Westminster Abbey Church this same curious process appears also exemplified, and that in a manner still more remarkable, in the Nave-piers and arches, triforia and vaulting. The eastern part of the Nave and Aisles was rebuilt between the years 1269 and 1307; and the western portion was continued at intervals, between the years 1340 and 1483.* The Early English character, however, has been so well preserved throughout, that in many cases it requires a close inspection, and that by an experienced eye, before it is possible to detect and authenticate the presence of Perpendicular work. Thus, the windows in the Aisles erected by Henry V. are very decidedly of Early Decorated character: and it might, indeed, be difficult to assign any reason, from the aspect of the work itself, which would militate against their being classified as such, did not the customary octagonal and molded cap of the Perpendicular period occupy the place of the corresponding circular and foliated members which, had the windows really been erected some hundred years earlier, would assuredly have surmounted the bowtels placed in their jambs. An equally characteristic distinction is also observable in the plans of the Nave-piers of the two eras: in the early

* Neale's History of Westminster Abbey.

work, four shafts stand clearly detached from the main body of the pier; but subsequently the pier was worked with eight shafts, all equally attached to the central mass. This last,

PERPENDICULAR NAVE PIER.



EARLY ENGLISH NAVE PIER.

though in reality but a trifling deviation from the original plan, is nevertheless indicative of the altered fashion of the day, in which detached shafts, once such a favourite feature, were entirely discarded.

In the Nave of Westminster Abbey, as at St. Alban's, in the midst of this partial amalgamation of styles, one most important member appears to have invariably rejected the slightest symptom of compromise, and maintained its characteristic identity: for, in the treatment of their *Moldings*, we find that the architects of the fifth and sixth Henrys have put aside all attempt at assimilation, and pursued with scrupulous strictness the molding system of their own times.* It is, indeed, truly worthy of remark how capricious these architects seem to have been in their adaptation,—jealous, apparently, of returning to what was then felt to be an inferior style, yet at the same time anxious to preserve and be guided by the conceptions of the original author of the general design. It must be noted that, when introducing, for the general purpose of assimilation, a member altogether foreign to their own style, the architects of the Perpendicular period disdained to copy exactly the model: it was the original *idea*, and that *idea alone*, that they cared to carry out; thus, in the piers, they worked the bands of the thirteenth century with the


BAND TO NAVE PIERS.
PERPENDICULAR.BAND TO NAVE PIERS.
EARLY ENGLISH.

moldings peculiar to the fifteenth. The accompanying cuts, both drawn to the same scale, show how fearlessly they departed not only from the outline, but also from the size of the original. And thus also in the triforia, the Early


English design is equally apparent in the former and latter portions of the work; but the moldings in these respective portions differ essentially, each being true to the style of its own period. And again, although the groining is tolerably in keeping throughout; in the Aisles and in the later portion of the vaulting, the original spring and

* It may not be out of place here to remark, that the architect in chief to our King Henry V., and the probable author of the assimilations referred to in the text, was Alexander de Berneval, the builder of the later portion of the Church of St. Ouen, at Rouen; in which edifice is still preserved an Incised Slab of elaborate workmanship, the memorial of his predecessor in that great and splendid work, as well as of himself. The effigies depicted in this interesting monument are figured in the Rev. Charles Boutell's *Treatise upon Monumental Brasses and Slabs*; and the entire tomb is represented by Willemin in his *Monuments Inédits*, and also in the description of the Church of St. Ouen by Gilbert.

height of the ridge-rib have been preserved, while to the elegant acutely pointed lancet of the earlier groining, an obtusely pointed arch has been preferred ; which consequently it has been necessary to stilt.




EARLY ENGLISH ARCADE, WESTMINSTER ABBEY CHURCH.



PERPENDICULAR ARCADE, WESTMINSTER ABBEY CHURCH.

In the arcading also, under the windows, we find another striking illustration of the process we are describing. In the Early English portion of the Church, this arcading was made such a prominent feature, that it was not deemed advisable to omit it in the Perpendicular work : accordingly we find it has been continued quite round the Church ; and although this mode of decoration had long since been disused, and supplanted by the new system of panelling, still in this instance, in its main features it has been revived, and made closely to assimilate to the earlier portion. On examining the moldings, however, we again perceive how rigidly the distinctive peculiarities of the Perpendicular



style have been adhered to. This is especially to be remarked in the two capitals of which we append cuts : the one a beautifully molded specimen of Early English work, the other an equally good and pure Perpendicular example. The stilted and octagonal base of the

Perpendicular shaft contrasts very forcibly with the low and unpretending Early English base, each indicative of the prevailing spirit in the Architecture of its respective age.

One more notable instance of assimilation may be mentioned: we refer to the Church of Fotheringhay, Northamptonshire. The choir of this Church is supposed to have been built by Edmund of Langley, fifth son of Edward III.; and in 1435 (13th of Henry VI.), Richard Duke of York, his son's nephew, signed by commission a contract with William Horwood, freemason of Fotheringhay, for the rebuilding of the Parish Church, on a scale and in a style exactly corresponding to those of the choir.* This contract, which is still preserved, states that the said William Horwood "graunts and undertakes to mak up a new body of a Kirk joyning to the quire of the College of Fodringhey, of the same hight and brede that the said quire is of," and that in "eche Isle shall be wyndows of fre-stone, accordyng in all poynts unto the wyndows of the said quire, sawf they shal no bowtels haf at all;" and also that "aither of the said Isles shal have six mighty botrasse of fre-stone, clen-hewyn; and every botrasse fynisht with a fynial, according in all points to the fynials of the said qwere, save only that the botrasse of the body shal be more large, more strong and mighty than the botrasse of the said qwere." Now here we have a document which expressly states that in building the new body of the Church, the Decorated choir already existing is to form the guide and be exactly copied; and yet William Horwood, we must imagine, was so entirely imbued with the Architectural spirit of his day, that even with these positive injunctions before him, he still let the Perpendicular architect be visible in almost every portion of his work. Truly, that our ancient builders should not merely have limited their practice to one style, but actually to *one* period of that style, is remarkable even among the many extraordinary facts connected with the Architecture of the Middle Ages: such being the case, how can we wonder at the astonishing perfection at which they arrived. It is in the piers that we may observe more particularly the assimilation to those of the choir; as in Westminster Abbey Church, with a plan of an earlier period they combine an arrangement essentially Perpendicular: such is the stilted base, and octagonal plinth and capital, with the intermediate continuous moldings, so common about this period. Indeed, when we remember that the then existing choir had two aisles, we can easily understand that if uniformity of design was sought after, it would be so more especially in the piers and arches, as they form in a Parish Church the most striking internal features. The arches in the nave are pointed, and of good proportion, and were probably made conformable with those already existing in the choir.

From these examples, therefore, it is clearly evident that in reconstructing certain portions of the fabrick of the larger Churches, it was an occasional practice with the Mediæval

* Memoirs of Gothick Churches, published by the Oxford Society.

architects to assimilate new work to old, so far as would tend to carry out the general uniformity of an original design ; and it is highly probable that further researches will show this practice to have been far more extensively adopted than at present is imagined. Whether it was also followed in small village Churches, and if so to what extent, are questions deserving a close and searching investigation.* Possibly many features which occasionally present themselves, and which it is difficult to reconcile with the style in which they occur, may result from some such an arrangement. Be this as it may, one thing appears sure and invariable amidst whatever of uncertainty may arise from this practice of assimilation ; and that is, that the assimilating process never extends to the *moldings*. To however great an extent the earlier portion of an Edifice may have been subsequently copied,

these important members were always worked in strict conformity with the ordinary system prevalent at the time of their construction ; and thus they will be found guides of the greatest possible authority, as well for detecting the application of this principle of assimilation, as for determining the date of those Structures, or parts of Structures, which maintain throughout an Architectural consistency. Such, at least, is the conclusion fairly deducible from all the instances, which the authors of these volumes have examined.

Before adverting to their analysis of more strictly Architectural details, the Authors here remark, that monumental brasses may frequently be studied by the architect with satisfactory and beneficial results. The arrange-

ment of the canopies in these interesting memorials is almost invariably elegant and effective ; while, in some examples, they display designs of most elaborate magnificence. The annexed illustration is from the brass, in Westminster Abbey Church, of Alianor de Bohun, Duchess of Gloucester, who died in 1399.

* Mr. Paley, in his manual (p. 214), mentions that " now and then the arches on one side of a nave were rebuilt after the model of the other side ; as at Little Casterton Church, Rutland, where there are semi-circular arches of the fourteenth century, evidently suited to others of the twelfth."



AN
ANALYSIS
OF
GOTHICK ARCHITECTURE.

SECTION I.—OF MASONRY.

1. WINDOWS.



TRACERIED window may be justly regarded as a peculiarly distinctive characteristic of Gothick Architecture—its own grand conception, and most beautiful enrichment.

Well aware of its remarkable suitableness for the display of both artistic and constructive skill, the Mediæval architects delighted to exemplify in this one member, in preference as it would seem to all others, the versatility and the power of their great art. Hence the astonishing diversity in their tracery, its almost invariable grace and elegance, its just harmony of proportion, and imposing richness of effect. It is, however, most certain, that Gothick windows are far from being *specimens only* of Mediæval genius, most admirable as these specimens are: for, upon a critical examination, it becomes evident that they are regulated by certain general principles of design, as well as of composition; and consequently, the apparently capricious ramifications and undulations of the stonework, are in reality no other than variously modified applications of the same fundamental laws.

In now sketching out the origin of tracery in the heads of windows, its gradual development and successive changes, we shall endeavour to illustrate the several more prominently distinctive forms which at different periods it assumed, previously to entering upon an examination of the rules by which its construction may be considered to have been governed.

Possessing several important features, and being also characteristick of certain periods, windows altogether devoid of tracery are the first to present themselves to our notice. In the early Norman Edifices, and particularly in the small village Churches, the openings for the windows were small and remarkably narrow,—indeed but little more than plain, round-headed slits, pierced at as great a height as possible above the ground, in the massive walls. Examples occur in Southease Church, and Steyning Church, Sussex,

TANGMERE CHURCH,
SUSSEX.



Nately Church, Hampshire, and Stow Church, Lincolnshire; in which the entire window openings are between two and three feet high, and in width do not exceed a few inches. These windows have a considerable internal splay, but externally their glazing is set almost flush with the wall-face. Glass, however, being at that time an object of considerable scarcity in England, many of these early windows do not appear to have been constructed with a view to their being glazed; as may be seen at Waltham Abbey Church, Essex, and Darenth Church, Kent, where evidently no provision was originally made for fixing panels of glass. A shutter, probably, was designed to close upon the rebate, which sometimes may be seen worked externally in the masonry; as at Southease Church, Sussex.* These windows merely resulted from absolute necessity; and, accordingly, but slight attempts were made to render them subservient to decorative purposes. Many examples are absolutely devoid of all ornament whatsoever. In Nately Church, the east window of the apse is perfectly plain on the outside, without even a dripstone; and internally a very slightly indented saw-tooth molding appears over the arch. The very early round-headed triplet at the east end of Darenth Church exhibits a few rude and imperfect attempts at zig-zag and billet work about the heads of the lights on the exterior (Section 1, Norman, Plate 2); over one light a dripstone may be noticed, but its occurrence here would seem to be the result rather of accident than of design, as the two other lights are without it. These lights are slightly splayed externally, and in the interior their splay is very wide.

The windows in the south aisle of Waltham Abbey Church (Section 1, Norman, Plate 3), though still very early, exhibit a considerable advance in decoration; and in their construction also, a new and important feature presents itself. The window-opening is no longer flush with the outer wall, or withdrawn from it by a slight external splay: here the opening is regularly recessed, and ornamented with jamb-shafts, having bases and capitals, which carry an arch molded with the chevron: a dripstone worked with

* In Clymping Church, Sussex, all the windows in the Chancel, including the east triplet, are rebated internally, and retain the hooks on which the shutters hung. A plan and two views of this Church are given in the "Parish Churches," Vol. II. page 75.


billets is also appended, and this member is continued from window to window by horizontal returns similarly ornamented. These windows are themselves greatly increased in size, and particularly in width as proportionate to their height. Beneath them runs a string, which in the interior is simply molded, but externally is enriched with the saw-tooth.

As the style advanced, the windows increased in both size and richness: the arches were recessed in two or three orders, additional shafts were added, and a profusion of the most elaborate carving ornamented the heads of the lights, in some cases extending to the jamb-shafts and completely covering the innermost order of the masonry. In a window in Stourbridge Chapel, Cambridgeshire (Appendix, Plate 1), the surface of the arch is richly diapered. Iffley Church, Oxfordshire, presents some fine specimens of recessed windows with jamb-shafts; and here the chevron is continued from the arch-head down the jamb masonry on either side. Amongst many others, the Churches of Castle Rising, Norfolk, and Beaudesert, Warwickshire, may be specified as containing some rich and valuable examples of windows of this style. Other admirable specimens will also be found in that most interesting edifice, the Church of St. Cross, near Winchester.

In the clearstory it was a common practice to construct windows having larger openings than those of the aisles, as in Steyning Church, Sussex; where the aisle-lights measure one foot only from jamb to jamb—while in the clearstory the same admeasurement amounts to about 2 ft. 9 in. Internally, these clearstory windows (themselves consisting each of a single light) commonly opened into an arcade of three arches—the centre one being stilted. This arrangement displays a passage pierced in the thickness of the walls, which traverses in front of the clearstory windows, and forms an upper triforium. It occurs in Waltham Abbey Church (Appendix, Plate 1), in the Cathedrals of Oxford, Winchester, and Norwich, and elsewhere. This same feature was continued throughout the transition or Semi-Norman period: thus, at Romsey Abbey Church a precisely similar arrangement appears, with pointed in place of semi-circular headed arches.

Triplets, although occasionally introduced, are not characteristick of Norman work: their most usual, as well as most beautiful, position would be at the eastern end of the Building; and as the common termination of a Norman Church towards the east was apsidal, their rare occurrence is without difficulty accounted for. Circular windows are not unusual; as, indeed, appears but natural in a style expressly distinguished by its rounded arches. In the earlier period they are mere openings, simply moulded, or perhaps ornamented with the chevron and other equally characteristick carving. A series of such circular windows constitute the clearstory lights to the nave of Southwell Minster: and again, in Waltham Abbey Church, the original arrangement appears to have been the

same ; although at the present time, in consequence of subsequent alterations, it is difficult to determine whether the existing remains were once actual openings, or merely sunk panels. In the west front of Ifley Church, a Perpendicular window has been inserted : in this same position the remains of a circular window of considerable size may, notwithstanding, be distinctly traced ; and again, part of a similar window yet remains in the west front of St. Botolph's Priory Church, Colchester. A small but perfect example, simply ornamented with a band of nail-head, occupies the eastern gable of the Church of St. Cross ; and in Chichester Cathedral and New Shoreham Church are other good examples, though both partake of a transitional character.



At a late period of the Anglo-Norman style, it was usual to divide the openings of circular windows with small shafts, radiating from a common centre. Good specimens of this usage occur in the Churches of Barfreton and Patricbourne, both in Kent.*

From the time of its first introduction until the final close of the Anglo-Norman style, the pointed arch differed from the semi-circular headed arch merely in form—the general characteristics, details, and ornamental accessories of the two arches remaining the same. It was also a common practice, anterior to the Gothick period, to introduce the two forms of arch in close connection the one with the other, in the same Building, or part of a Building. Thus, in Chichester Cathedral three pointed lancets appear arranged under a single large semi-circular arch. In the triplet at the east end of Castle Hedingham Church, Essex, the arches externally are pointed, while internally their heads are rounded : and again in Barfreton Church, a pointed window is placed side by side with one that is rounded, and the two are connected by a string continued between their dripstones. Semi-circular headed and pointed windows are also inserted indiscriminately in the clearstory of Oxford Cathedral : in all other respects, however, the details of these windows are precisely identical, and essentially Anglo-Norman.

Forced into existence by the exigencies of construction,† a considerable space of time elapsed before the peculiar faculties and beauties of the pointed arch were duly appreciated or even discerned : and consequently, we find it to have been in frequent use, merely with a view to produce an agreeable variation from the more general rounded form. The

* It is highly remarkable that these windows, thus divided, and bearing so close an approximation to tracery, do not appear to have originated the idea of a tracery window-head. The circular window in St. James's Church, Bristol, is a curious instance of a near, but still purely accidental, approach to a complete piece of tracery.

† There can be little doubt but that it was in vaulting that the pointed arch was first introduced as a necessary constructive form.

pointed arch thus used may be distinguished as the pointed Norman arch, and this period may also be correctly indicated by the term Semi-Norman: the period, that is, intervening between strict Norman and pure Gothic—in which the grand feature of the coming style appeared in association with the general characteristics of that already in its decline.

Fine specimens of the transitional character of this Semi-Norman period exist in the ruined Churches of Buildwas Abbey, Salop; Fountains Abbey, Yorkshire; and Croyland Abbey, Lincolnshire; in the Chapel, also in ruins, of St. Joseph, at Glastonbury; in the Church of the Hospital of St. Cross, near Winchester; and in the conventual Churches of Malmesbury and Romsey. From the circumstance, however, of the exact period of its construction having been recorded by a cotemporary writer, as well as from its intrinsic merit, the eastern part of the choir of Canterbury Cathedral justly claims a pre-eminence in value and interest over all other remains of this period. Here, in the clearstory windows, a remarkable deviation from both the pointed and semi-circular form is observable in the head of the window-arches: the actual openings of these windows have trefoiled heads, each one circumscribed by a semi-circular arch.* But this new form, notwithstanding its close approximation to the heads of the lights in pure Gothic windows, clearly had no real influence in the formation of tracery: its introduction, whether fortuitous, or resulting from design, produced nothing more than another form of window-arch, and led directly to no more important results.†

In the smaller Semi-Norman Churches, the windows appear to have frequently been pointed, but in other respects constructed and ornamented after the Norman style. Several good examples of this arrangement remain in the Chancel of Bloxham Church, Oxfordshire; and at the east end of the Chancel of Barnwood Church, Gloucestershire, is a single-light window (from its great width scarcely to be called a lancet) with plain molded jambs, a pointed arch, and dripstone ornamented with chevron-work.‡ It appears unnecessary to refer to other examples of these transition windows; we therefore here recapitulate the more prominent features of the windows of the Anglo-Norman style:—

(1.) They were small, each consisting of a single light, semi-circular in the head, and placed as highly as possible above the ground.

(2.) In the earlier examples the splay was entirely internal, and in many cases no

* The trefoil arch is also observable in the heads of doorways of this period. See subsequent article upon Doorways.

† Professor Willis, in his admirable History of Canterbury Cathedral, fixes the date of these windows between A.D. 1175 and 1178; William de Sens, architect.

‡ See "Parish Churches," Vol. II. p. 71.

preparation for glazing appears to have been made : later in the style the windows began to be recessed, jamb-shafts with quaintly carved capitals were introduced as the supporters of richly ornamented arch-moldings, and the openings were considerably elongated.

(3.) No decided indications of tracery had yet appeared : the wheel-windows of even the Semi-Norman period, though possessing what might have been regarded as the germ of tracery, were discontinued when the Early English Gothick became positively established.

On the first establishment of the Gothick style, little essential difference, beyond the invariable adoption of the pointed arch, was apparent in the design and proportions of the windows ; but as the style advanced, the development of Gothick details and accessories in the windows gradually increased : the openings of the lights became, in most cases, narrower in proportion to their height : a new and peculiarly characteristick principle of construction was introduced in the heads of window-arches ; and, after a while, the juxta-position of several distinct windows brought on the general use of mullions and tracery.

At its first introduction, and throughout the continuance of the Semi-Norman period, the pointed arch was very obtuse, rarely becoming equilateral, and perhaps in no single instance acutely pointed. In the Early English Gothick, on the contrary, the equilateral is the usual form of the window-arch ; while in some cases, and more particularly in the Cathedrals and larger Churches, we find the windows most acutely pointed, as at Lincoln and Southwell Minsters. The single-light Early English lancet, in general use during the first Gothick period, was of the simplest arrangement ; its very simplicity constituting its peculiar charm. In these windows the glass was generally brought within three or four inches of the outside face of the wall. (See plans, Section I. Early English, Plates 1 and 4.) In the interior the openings were widely splayed ; and consequently, in walls of great thickness, this splay caused the width of the jambs to be, in most cases, four or five times the width of the light. Now, if the arch of the window had been allowed to widen inside with the jambs, besides the unsightly appearance which would have been produced, it would have necessitated a much greater height in the walls of the Church than was considered desirable by the Early English architects ; and hence arose a peculiar treatment



of the interior of windows, the general arrangement of which consisted in having totally distinct arches inside and out : the outer adapting itself to the peculiar character of the window, but the inner being almost invariably a segmental pointed or drop-arch ; the point of which, in many examples, was considerably below that of the window itself, as in the south aisle of St. Alban's Abbey Church. It will be observed, in this mode of construction, that the head of the lancet is cut out of a mere slab a few inches in thickness, which is carried up internally till it meets the soffit of the

drop-arch. (See Section I. Early English, Plate 11.) The effect also of this treatment of their lancets was to throw the light *down* into the Church, and leave the valley of their high-pitched roofs in a state of semi-obscurity, an object they so evidently sought for in their interiors. So characteristick was this arrangement considered, and also so peculiarly effective in itself, that shortly after its introduction it was generally adopted even in windows so placed as not to require its constructive advantages: thus, in gable-triplets, the combined windows were very commonly finished in the interior with drop-arches (see Section I. Early English, Plate 15); and, again, the same arrangement appears in the tower of Brockworth Church, Gloucestershire (Section I. Early English, Plate 11), where the interior arch, though segmental, is actually concentrick with the arch of the light. This last-named circumstance is, indeed, of by no means rare occurrence in those positions, in which the drop-arch was introduced rather as an essentially characteristick feature than a necessary constructive application. As a matter of construction, this drop-arch is by far more secure than an arch sloping so considerably as would have been requisite had the interior and exterior arches been concentrick. We may here observe, that this arrangement, variously modified, continued to be in use in the construction of windows throughout the Gothick style.* (See Section 1, Decorated, Plate 2.)

In some early examples we meet with a simple segmental arch inside, connected with the lancet-head by rough and irregular masonry, without any effort of design or systematick construction.

The proportions of Early English lancets vary to a remarkable degree; the lights being, in height, in some instances, as much as eleven times their width, as in the Churches at Oundle and Clymping;



TANGMERE CHURCH, SUSSEX.



MANTON CHURCH,
RUTLANDSHIRE.

or ten times, as at Shorne Church (see Section I. Early English, Plates 1, 4, 7); while, in other examples, as at Brockworth and Great Casterton, the height of the lancets does not exceed five times their width. Eight, or perhaps nine times their width may be regarded as a fair average for the height of these lancet-windows when in their greatest perfection.


The instances are rare in which we find a Church still retaining the original arrangement of its lancet-windows; but in such cases we may generally remark, that in the gables and in the north and south walls of the Chancel they are of more slender proportions than in the other parts of the Edifice.

The reason for this is obvious: were the narrow proportions of the Chancel lancet

* A contrivance of this kind was not necessary in the Anglo-Norman Churches, the windows being almost invariably of much less height, and the walls in some instances comparatively higher. Where there was sufficient height, even in the Early English period, in some examples the exterior and interior arches of the windows were concentrick, as in the North Transept of York Cathedral.

preserved in those placed in the less elevated walls of the aisles, the light thus obtained would be altogether insufficient; and hence appears to arise the general rule, that the width of Early English lancets varies *inversely* in proportion to their height.* Early English lancet-windows occur either singly, or in groups of two, three, five, and seven; but combinations of four and six lancets are rarely to be found. Repton Church, Derbyshire, furnishes an example of this latter arrangement: of the former, the east end of the Chapel of St. Mary's Hospital, Leicester, affords an instance. A single lancet is very rarely placed at the east end of a Chancel; nor is a similar window much less uncommon in a western elevation. The eastern gable of the Chancel at Llanabar, Merionethshire, is pierced with a single lancet: and at Little Casterton Church, Rutland, and Tangmere Church, Sussex, are single lancets to the west.† Single lancets also appear in western towers, in the Churches of Stanwick, Ringstead, and Etton, in Northamptonshire.‡ The usual position of single lancets is in the north and south walls of Chancels and Naves, and in the east and west extremities of aisles.

In a small country Church, the arrangement of two single lancets, tall and narrow, is productive of the most beautiful effect. This arrangement is sometimes seen to the east of a Chancel, as at Great Casterton Church, Rutlandshire, and Tangmere§ and Portlade



SOUTH NEWTON CHURCH, WILTS.

Churches, Sussex; and commonly to the west, as at Barnwell, Cambridgeshire. Couplets of lancets occur in the aisles of Churches more frequently than in any other position, as at Little Wenham Church, Suffolk, and Stoke Pogis Church, Bucks (Section I. Early English, Plate 1), and Hythe Church, Kent: this probably results from the same desire to obtain light, which caused the single lancets in aisles to have a greater proportionate width than in other positions. A lancet couplet also is commonly found in the side walls of Chancels, as in the Churches of Great Wenham, Suffolk, and Hartley, Kent (Appendix, Plate 2).

The triplet, at once the most characteristick and the most beautiful arrangement of

* The beautiful little Church of St. Michael's, Long Stanton, Cambridgeshire, retains the Chancel lancets in nearly their original state; but in the aisles the original windows have been altogether destroyed. Clymping Church, Sussex, may also be specified as containing most valuable examples of Early English lancet-windows. Parish Churches, Vol. I. page 75.

† See Parish Churches, Vol. I. p. 1.

‡ Single western lancets sometimes may be seen in Semi-Norman Edifices, as at Manton Church, Rutland; and in a Church of a similar character at Barnwood, Gloucestershire, is a single eastern lancet.


§ See Parish Churches, Vol. II. p. 34. See also Section I. Early English, Plate 13.

lancet-windows, generally appears to the east in the gable of the Chancel, and this may be safely considered as its original position. Here its impressive symbolism is most appropriate, and also in most exact accordance with the spirit of the Early Gothick age. Instances, however, occur, which authorize the introduction of the triplet into every possible position in the walls of a Church, without in any degree infringing the general rule of its peculiar applicability for the eastern extremity of the Chancel. Lancet-triplets exist in the west front of the Church, at Werrington, Northamptonshire (a small picturesque Edifice, having a double bell-gable over the Chancel-arch, but without any west door); at the west end of the aisle, at Tinwell Church, Rutlandshire (Section I. Early English, Plate 20); and at Warnington Church, Northamptonshire, it appears at the east end of the aisle, and is also four times repeated in the south wall of the south aisle. At Great Casterton, Rutlandshire, the side of the Chancel contains a triplet; and at Stanton Harcourt, Oxon, two triplets are pierced in either side of the Chancel. In the Cathedrals and larger Churches, triplets were placed to the north and south in the transepts, and also in a continued series in the clearstory; frequently two, and sometimes even three, were placed successively one above the other in gable walls, as at Whitby. In triplets it was customary to mark with greater importance the central light, by giving to it additional height, and in most cases increased width also; this modification may be satisfactorily deduced from the form of the gable, in which, as we have already remarked, the triplets of lancets without doubt were originally placed. (Section I. Early English, Plates 1, 4, 7, 9, 12, 15, and 20.) Where, on the exterior wall, lancet-triplets are surmounted by dripstones, each lancet has its own distinct dripstone; though, in most cases, the three dripstones are united by short strings traversing between the lights. These strings are generally placed at the springing of the arches of the two outer lancets; and consequently either the dripstone of the central light is stilted, as St. Bartholomew's Hospital, Kent (Section I. Early English, Plate 15); or in some instances, as at Stanton Harcourt, Oxon, the connecting string is interrupted by perpendicular returns, and again continued horizontally to join the central dripstone at the springing of its own window-arch. In some examples the three windows of a lancet-triplet are placed within a dripstone forming a single arch; and thus, though essentially and really distinct from it, they bear a strong general resemblance to a single three-light window. The glass, in these combinations of lancet-windows, is usually placed near the outer face of the wall, in the same manner as in single lancets, and internally the three windows are widely splayed: in this last respect, no less than when placed under a single dripstone, they produce a general effect closely approximating to a single window of three lights. This effect is, in the greater number of instances, considerably enhanced by the narrow fillets of the wall, which intervene between the splays

of the windows, being faced with bold shafts, from which rise the combined hood-molds. In both single lancets and triplets, and also in other combinations of this beautiful window, the tooth-ornament is frequently introduced in long trails, in the molding of the window-arch, or of the hood-mold: fine examples of this characteristick enrichment occur in the south aisle of St. Alban's Abbey Church.*

In Cathedral and other very large Churches, four or more lancet-windows of the same height and width, were occasionally introduced in combination. In the less important Buildings, and, also, in many instances in the larger ones, the lancets in combination are of an uneven number, and are generally arranged after the same system as the triplet,—the central window, that is, having both the greatest width and height, and the exterior window on either side the group being smaller than the inner pair. In these combinations of lancets, exceeding three in number, the several windows are commonly surmounted by a single dripstone, as in the Churches at Etton and Oundle, Northamptonshire (Section I. Early English, Plate 7), where five lancets form the group. Seven lancets similarly arranged but rarely occur: examples, however, exist in the Churches of Blakeney, Norfolk, and Oakham, Surrey.

In place of the customary simple arch-head, in some examples of lancet-windows the head of the light is *foiled*; at Great Wenham Church, Suffolk, the eastern end of the Chancel is pierced by a triplet of this character. (Section I. Early English, Plate 1.) This form of window-arch was in common use at an early period; and in this, with its first modification, a *foliated* lancet (see in the same Section, pl. 4, the example from Hangleton Church), we see the germ of cusping, properly so called.† At Winnal Magdalen Church, near Winchester (Appendix, pl. 2), the lancets display early and rude specimens of foliation or cusping, in its primitive condition. To this style of cusping the distinctive title of soffit-




cusping has been applied, from the circumstance of the cusps springing from the soffit of the arch, and not, as subsequently was the invariable practice, from the chamfer or slope of the arch-side. This soffit-cusping may be regarded as a sure indication of early work; and in most instances it is characteristick of a transition from Early to Decorated Gothick.

In early cusped circles, a similar distinctive peculiarity is observable in the cusping: here the foils are produced from the inner curve, without rising at all into the chamfer, and thus no eyes whatever are formed; or the foils themselves are chamfered, but the eyes are

* The tooth-ornament also appears on the exterior in some lancet-windows, as in the triplet in Tinwell Church, Rutlandshire (see Section I. Early English, Plate 20); and in Warmington Church, Northants.

† Professor Willis derives the idea of a *foliated* arch from a compound archway, of which the first order is a simple, and the second a *foiled* arch.

imperfect ; their chamfer being restricted to their outer curves (B). Another marked peculiarity in early foils is that, in place of being segments of intersecting curves, they are formed from a series of distinct circles, which all cut a larger circle inscribed within them. Tracery, in the cusping of which any of these peculiarities occur, is invariably of an early, when not actually of a transitional period. The two windows in Meopham Church, Kent (Section 1, Early English, Plates 10, 11), and also the windows of Evington Church, Leicestershire, illustrate this early cusping.*



From the combination and cusping of distinct lancets, a single window divided by mullions and tracery derives its origin. It is no less remarkable than interesting to trace, as we are enabled to trace in existing examples, the gradual development of this grand Gothick conception. Thus, as in Glapthorne Church, Northamptonshire, two lancets were in the first instance placed side by side in a closer proximity than heretofore was customary, and the spandrel between their heads was pierced by a simple oval-shaped opening ; a second window in the same Church exhibits the lancets more acutely pointed,



with an opening of a lozenge shape in place of the previous oval, and the whole enclosed within a common dripstone ; and in a third window a more decided advance is apparent ; for in this composition, while the lancets remain the same, the oval has been superseded by a circle with soffit-cusping forming a quatrefoil, and the plain space in No. 1 has been converted into sunken spandrels. These three windows occur in the south side of the Chancel of this interesting Church : and they exemplify, in a manner perhaps unparalleled in any one similar Structure, the idea of tracery being conceived in the artist's mind, and gradually worked out in three successive designs. The window in Belgrave Church, Leicestershire, is another good specimen of this period (Appendix, Plate 3) : it is somewhat richer in moldings, but does not exhibit any advance-

* In Arreton Church, Isle of Wight, is a window with this description of cusping, where a stone ring connects and intersects the foils (Sharp's Decorated Windows), thus illustrating in construction the formation of the foliations.

ment in design. The windows in Houghton Church, Durham, are of precisely the same character, with a very peculiar arrangement of dripstone.*

The idea of several distinct lights with minor compartments of an ornamental character, constituting a single window, was no sooner fairly recognised, than examples of its practical application rapidly increased in both number and variety. The peculiar aptitude for modification and variety which distinguished a window divided by mullions and tracery, appears from the very first to have convinced the Gothick Architects that in this member the essentially pliant character of Gothick Architecture might be most signally displayed. Hence the almost countless multiplicity of designs and modifications of each design, which were so speedily produced in the windows erected after the first introduction of tracery.

A two-light window with a quatrefoiled circle at the head of the lights was, as we have seen, the first decided step towards the adoption of regular tracery. It was a natural and easy advance to place two such windows in combination, and to pierce with a larger circle the space enclosed by a dripstone forming a single arch above



ALDWINKLE CHURCH, NORTHAMPTONSHIRE.

them both: here appears, therefore, a four-light window with its geometrical tracery. Then one of the lights would, no less naturally, in some instances be suppressed; while under circumstances of a contrary nature, a fifth or even a sixth light might be introduced; and in each of these cases some alteration in the tracery must necessarily ensue: and again, every such alteration would lead to the intro-

duction of fresh variety, and thus illustrate the facility with which window-tracery admits of change, even whilst fettered by geometrick forms, without diminution either of beauty or of consistency.† In the first instance, in these early windows, the cusping was for the most part restricted to the geometrical tracery, the heads of the lights remaining plain; but after a while a similar enrichment was introduced at the heads of the lights, to the great improvement of the entire composition: examples, however, remain, which show that, even

* Billing's Durham.

† Etton Church, Northants (Parish Churches, Vol. I. p. 13), a pure Early English Structure, affords some excellent specimens of early tracery. The windows in the aisles consist of two lancet lights, surmounted by a plain circle, and all inclosed within a common dripstone: those in the Chancel are of the same design, but a trefoil of soffit-cusping enriches the circle. At Oundle the addition of a third light, and two head circles to a similar composition, produces a three-light window. In St. Alban's Abbey Church, a very fine three-light window is the result of the same arrangement.

in large windows of many lights, cusping was occasionally omitted altogether.* The circle, the original form of tracery, itself trefoiled and quatrefoiled, was soon modified by distinct quatrefoils and trefoils; and in many instances a reversed trefoil became the central figure of the tracery in two-light windows, and sometimes, as at St. Alban's, in three-light windows. In trefoiled circles also, the trefoil formed by the cusping is frequently reversed, as at Meopham Church (Sect. 1, Early English, Plate 10). The trefoil appears to have been a favourite arrangement of early cusping: two beautiful examples of its introduction into single lancets, with the view to impart to them a traceried character, are given at Section 1, Early English, Plate 8, from the Chancel of Raydon Church, Suffolk. In Plate 13 of the same Section is engraved a singularly beautiful two-light window, also from that Church.

During the progress of the development of window tracery, a change gradually becomes apparent in Gothick Architecture itself; and the observer is led to discover that the first great period of the style has merged into its successor. In thus passing on from Early English to Decorated Gothick, the only sure criterion for deciding upon the windows of either, lies in the moldings combined with the cusping. It being a necessary result that the works executed during a transition period should lose, in a greater or a lesser degree, the *general* characteristics of an established style,—such works must be either regarded (as in strict reality they are) as transitional specimens; or their assignment to one or other of the successive periods between which they appear, must depend altogether upon peculiarities in matters of *detail*. Thus, the general design of two windows of geometrical tracery, may be precisely identical: and yet, if the idea of transition windows be rejected, the one may be correctly assigned to Early English, and the other with no less accuracy to Decorated Gothick; because of the moldings being essentially different, or because in the one there may appear soffit-cusping, while in the other the cusping may expand from the chamfer of the window-arch. For example, the windows in Stoke Albany Church (Section I. Early English, Plate 17), in their general aspect might be reckoned pure Decorated; their soffit-cusping, however, more correctly classifies them with the Early English period. And so also in the clearstory over the choir of the Abbey Church of St. Alban, the composition is altogether Early English, but the moldings partake more of a Decorated than of an Early English character.† In this transition period it was customary to construct many windows of more than two lights, having

* See, in Sharpe's Windows, an example from Grantham Church.

† It is, perhaps, impossible to consider these windows otherwise than as *transitional*, from the want of any decided peculiarity of style.

no other tracery than would be produced by the intersection of the mullions in the window-head: a practice which was in some instances continued considerably later, and forms the basis of a numerous class of Decorated windows. In some examples of this arrangement the intersections are cusped, but very frequently they are entirely plain, and consequently produce a meagre and unsatisfactory appearance. Very different, however, is the result, when the intersections of the mullions are filled in with quatrefoils, trefoils, and other enriched forms of tracery: in these cases the general effect is singularly beautiful and elegant, as is shown by the examples from the Churches at Southfleet and Herne, in Kent, and at Trumpington, Cambridgeshire (Section I. Decorated, Plates 20, 29).



But, before entering upon the direct consideration of Decorated Gothick windows, one peculiar kind of tracery, common to the close of the Early English and the commencement of the Decorated periods, demands to be particularly noticed: we refer to that in which, contrary to the usual practice, the general design is indicated by *foliations*, and not by foliated geometrical figures. This arrangement may be distinctly referred to the trefoiled arches, adopted by the early Gothick Architects from their Anglo-Norman predecessors, and is exemplified in the east triplet at Great Wenham Church, Suffolk (see Section I. Early English, Plate 1). The windows in the south aisle of Northfleet Church, Kent, are instances of considerable merit (Section I. Decorated, Plate 1): other examples occur in the Abbey Church of St. Alban (Appendix, Plate 4), and in Wooton Church, Northants.* As Gothick Architecture advanced, this *foiled* tracery was almost abandoned, appearing only in occasional specimens, and then perhaps resulting rather from accident than design:† a fine late example may be mentioned as existing in a Perpendicular window in Churchdown Church, Gloucestershire.



Neither may we here omit to notice the remarkable evidences which yet remain in windows undoubtedly constructed during this transition period, of the manifold *experiments* which were tried and rejected before the perfect Decorated window was produced. Thus, at Rickenhall Church, Suffolk,‡ the east window of the south aisle, which is

* This window is figured at page 125 of Paley's Manual of Gothick Architecture.

† The windows in the Lady Chapel at St. Alban's (Appendix, Plate 4) show the two kinds of tracery combined in the same design.

‡ Parish Churches, page 45.

decidedly of the same date with the other windows (temp. Edward I.), exhibits almost every peculiarity of Perpendicular tracery: the main lights are cinquefoiled, and the widow-head comprises batement-lights, super-mullions, &c.; all features directly at variance with the general custom of the time. At Evington Church, Leicestershire, in the north aisle are two windows still more curious: of these, the western window (Fig 1) might be regarded as a fine specimen of flowing tracery, were it not for its soffit-cusping; the invariable test of early work: the ornaments, also, with which it is richly studded, are a mixture of the Decorated ball-flower, with the dog-tooth and masks of the Early English period. The composition of the east window is even more remarkable, and indeed contradictory (Fig 2): it consists in its general design of a series of equilateral-headed arches springing from small shafts with delicately carved foliated caps of pure Decorated character, and the upper part of the tracery is divided by super-mullions and transoms into two octo-foliated squares and a row of tre-foliated batement-lights. Thus, in these two windows, evidently both of the same date, are displayed peculiarities characteristick of the three great periods of Gothick Architecture: the Early English soffit-cusp, the Decorated foliated cap, and the Perpendicular super-mullion and tracery-transom. Such phenomena afford ample scope for conjecture: shall we say that William of Wykeham first introduced Perpendicular tracery, when we find every one of its essentials in a window of the time of Edward I.? Shall we not rather conclude, that in their endeavours to arrive at perfection in tracery, the early builders, in the course of their experiments, actually invented Perpendicular tracery, proceeded to a partial development of its peculiarities, and finally rejected it as unworthy?


With the decided establishment of the principle of window-tracery it became a recognised constructive arrangement to recess the mullions from the face of the wall in which the window-arch was pierced; and the



EVINGTON CHURCH, LEICESTERSHIRE. FIG. 1.



EVINGTON CHURCH, LEICESTERSHIRE. FIG. 2.



CAPITAL FROM EAST WINDOW.

fine effect thus produced was, as the art advanced, speedily enhanced by the introduction of distinct orders of mullions, and by recessing certain portions of the tracery from the face of the primary mullions and their corresponding tracery-bars. The distinct planes of tracery and mullions thus produced, constitute one of the most beautiful features in Gothick windows: four of these planes are well exemplified in the window from Herne Church, figured at Plate 20, of Section I. Decorated: here are, first, the wall-plane; second, the mullion and tracery-bar plane;* third, the tracery-plane, and fourth, the plane of the *eyes* of the cusping.† This last plane sometimes coincides with the plane of the tracery; and again, in some examples there are primary and secondary planes of both mullions and tracery-bars: all these modifications appear in the beautiful window of the north aisle of Sleaford Church, Lincolnshire‡ (Section I. Decorated, Plate 26).

Decorated window-tracery has been generally divided into two chief varieties, Geometrical and Flowing: the former so called, from strictly consisting, as its name implies, of geometrical figures, such as circles, curvilinear triangles, lozenges, trefoils, quatrefoils, &c.; while in flowing tracery these figures, though still existing, are gracefully blended together in one design. Of these two varieties, the geometrical is the earlier; though it appears to have been retained in use subsequently to the introduction of flowing tracery, and in many instances both forms were used indifferently in windows of the same Edifice, and these erected at the same period. Indeed, the two varieties of tracery are not unfrequently exemplified in the same composition: for tracery, like almost every other feature of Gothick Architecture, passed through its changes with such extremely gradual progress, that in many cases it is absolutely impossible to carry out any complete rule of classification.

In its most perfect state, geometrical tracery invariably exhibits some large figure of distinct and decided character, which occupies the entire upper part of the window-head: this figure is generally either a circle, itself foliated and cusped, or subdivided by smaller geometrical figures, in most cases similarly enriched; or it is formed by tracery-bars diverging from the head of the central light, in such a manner as to resemble the upper portion of the window-arch *inverted*, and containing ornamental work of the same

* *Tracery-Bars* are those portions of the masonry of a window-head, which mark out the principal figures of the design: from these, the minor and more strictly decorative parts of the stonework may be distinguished under the title of *Form-pieces*. See Willis's Nomenclature.



A.A. the eyes of a quatrefoil.

† For want of a better, the term *eye* has been adopted by the authors, to indicate the small triangular space, whether pierced or not, which intervenes between a cusp and the curve that circumscribes it.

‡ We occasionally, however, meet with instances where, probably from the great scarcity of freestone, the mullions have been brought flush with the outer wall.

character as the large circles.* In some other designs three circles or three curvilinear triangles (Section I. Decorated, Plate 2) of *equal size*, are introduced, and variously enriched and modified. And



COTTINGHAM CHURCH, NORTHAMPTONSHIRE.

again, in other windows the geometrical forms are subordinate to intersecting curves (Sect. I. Decorated, Pl. 20);



SAWBRIDGEWORTH CHURCH, HERTS.

or the entire tracery consists simply of one geometrical figure (Section I. Decorated, Plate 8).

To enter into a full description of even the chief of the manifold variety of designs which appear in the windows of the Decorated period, would greatly exceed the limits of this work: and this is especially the case in windows of flowing tracery, which comprise almost every possible modification of almost every possible design. It must suffice to refer, in general terms, to the more distinctive peculiarities in tracery; leaving it to the illustrations to explain the details of upwards of one hundred specimens.



SOUTHFLEET, KENT.



RINGSTEAD CHURCH, NORTHAMPTONSHIRE.

selected from all the principal varieties which are profusely scattered over the country.

In two-light windows, the Early English arrangement, frequently varied and enriched, was for a long time continued; as in the beautiful specimens from the Churches at



HOLTON ST. MARY'S, SUFFOLK.

Northfleet and Roydon, figured in Plate 5, of Section I. Decorated. In other two-light windows in which the tracery-bars diverge from the mullion, describing curves similar to those of the window-arch, the heads of the two lancets thus formed are filled with various tracery (Section I. Decorated, Plate 3). Others, again, are of a character so very peculiar, as to form an absolutely distinct class from any we have yet noticed. They occur in the purest period

* See, in Sharpe's Windows, specimens from the Churches of Rudston, York; Billingborough, Lincoln; Howden, York; Exeter Cathedral; Fishtoft, Lincoln; Trent, Somerset; Wellingborough, Northants; Ripon Cathedral, &c. Also Appendix, Plate 3.

of the Decorated era, and are characterised by a remarkable *angularity* and *abruptness* of outline: such are the windows in the Chancels of Chartham Church, Kent (Section I.



ST. ALBAN'S ABBEY CHURCH.

Decorated, Plate 22), Belgrave Church, Leicestershire, and Lyddington Church, Berks (Appendix, Plate 4). "The tracery is different in each of these examples, but they agree in being dissimilar from all other Decorated windows of the same date."* In other examples the heads of two-light windows are filled with flowing tracery:—so endless,

indeed, are the varieties in this species of decoration, that we are as much astonished at the great effort of imagination which could, in a comparatively short space of time, produce such numerous designs, as we are gratified with the exceeding beauty and appropriateness of the designs themselves.



SOUTHFLEET CHURCH, KENT.

Larger windows of three, four, and a still greater number of lights, were produced by repeating, with certain modifications, the same designs as were introduced in a simple state into two-light windows. In many of these large windows a fine effect is produced by the primary mullions and tracery-bars being very richly molded: in some examples, as at Bottisham Church, Cambridgeshire (Section I. Decorated, Plate 27), the rich moldings of the mullions are

continued throughout the entire composition. The mullions also, in many instances, have shafts, with bases and capitals characteristically molded and encircled. In some specimens,



SAWBRIDGEWORTH CHURCH, HERTS.

also, the ball-flower is introduced with admirable effect, studying the hollows of both mullions and tracery in rich profusion (Section I. Decorated, Plate 38).† Specimens of some of the most beautiful forms assumed by flowing tracery, are given in Section I. Decorated, Plates 6, 7, 11, 12, 18, 26, 29. To these may be added, as ranking amongst the finest windows of the same class in England, the east window in Carlisle, and the west window in York Cathedrals.‡



* Remarks on the Principles of Gothick Architecture, as applied to ordinary Parish Churches; by the Rev. J. L. Petit.

See also Bloxam's Gothick Architecture, Ed. 8, p. 217; and Sharpe's Decorated Windows, where is a plate representing one of the windows in the north aisle of the ruined Abbey Church of Whitby, which contains tracery somewhat of the same character with that of Chartham.

† See Parish Churches, Vol. I. p. 67; also Sharpe's Windows, part 6, window from Leominster Church, Herefordshire; and Britton's Gloucester Cathedral.

‡ See Sharpe's Windows.

A class of windows are occasionally met with in the more magnificent of our Churches, of which the rich and elaborate design fails to entirely satisfy the eye, owing to the inelegant arrangement of the tracery-bars. We refer to such windows as those in the north transept of Sleaford Church, in the south transept and east of Chancel of Heckington Church, in Selby Abbey Church,* and in the Chancel of Redgrave Church, Suffolk. The diagram A represents the primary curves of the east window of seven lights in Heckington Church, where we may notice that two intersecting and irregularly shaped ogees form the principal feature in the design, and by their awkward combination detract from the merits of an otherwise beautiful production. In a *nine*-light window, on the contrary, as shown in diagram B, this arrangement might be well carried out and create a very fine effect; for here the main lines throughout the composition would be equally balanced.



Amidst all the surpassing beauty of Decorated tracery, anomalies sometimes present themselves to our notice, for which, while it is difficult to assign any reason, it would be still more difficult to find admirers. For example, in the fine conventual Church at Dorchester, Oxfordshire, is that curious and contradictory composition known as the Jesse-window, in which the real use of tracery, and consequently its beauty, are together lost sight of; and where the mullions, branching out into various shapes, are made to represent the tree of Jesse.† Again, scarcely less reprehensible is the introduction into window-tracery of canopies and pinnacles, however beautiful in themselves, and however richly they may be decorated. These members are designed to form an external protection, and at the same time in their proper position to enhance the beauty of window-tracery, but not to be interspersed amidst the tracery itself. Examples of this arrangement occur in the otherwise fine east windows of Merton College Chapel, Oxon;‡ St. Alban's Abbey Church; Barnack Church, Northants; and in the west window of Henry the Seventh's Chapel, Westminster.

One other kind of tracery, very common in windows of every variety of dimension throughout the Decorated period, we must not omit to notice before passing on to that great change, which has given its title to the last of the three periods of English Gothick Architecture: we refer to the *net-tracery*, so named from its resemblance to the meshes of a net. This, when double-cusped, as in the cloisters of Westminster Abbey,

* Sharpe's Decorated Windows.

† See Addington's Dorchester Church.


‡ See Britton's Antiquities, Vol. V.

is productive of great richness of effect: though at the same time, and particularly in windows comprising more than three lights, it almost invariably presents rather the appearance of *diaper cut to the shape of the window-arch*, than of tracery specially designed to fill the head of the arch within which it is contained. This appearance results, in part, from the want of variety in the several subdivisions of the design, but more particularly from those portions of the tracery which come in contact with the curves of the window-arch being cut off abruptly, instead of curving upwards to adapt themselves to their situation.



WHEATHAMPSTEAD CHURCH, HERTS.

It also appears requisite here to refer to one other peculiar species of flowing tracery



FROM A DEDICATED CHURCH AT ROUEN.

common in continental Gothick Buildings, but very rarely indeed to be found in this country. From the flame-like undulations of its tracery-bars and form-pieces, this tracery has been distinguished as Flamboyant.



SECTION OF JAMB AND SILL.

In England this term Flamboyant is restricted to form or design in tracery; but on the Continent the same expression denotes not a peculiar style of window-tracery alone, but the entire range of Gothick Architecture at a period commencing with the decline of Decorated Gothick in England. The term, however, can hardly be correctly applied to English windows, inasmuch that however flamelike* their tracery may be, they are still to be referred to the purest period of Gothick Art, if we have recourse to that unfailing test, the moldings: whereas in the real Flamboyant of the Continent (of which we append an illustration from a desecrated Church at Rouen) the moldings show at once the debasement that has taken place. Mullions finishing with an arris are perhaps never met with in Decorated work, though they harmonize well with the general angularity of the Flamboyant.

* That we should meet with many Decorated windows in our own country having flowing tracery, closely resembling Flamboyant, is in no ways remarkable, if we consider this last-named style in the light of a debased Gothick, in which flowing tracery alone was preserved tolerably pure amidst the general debasement of all its other parts. Indeed, tracery itself soon shared in the total wreck of good taste, which took place earlier on the Continent than with us: losing all consistency in construction, it became distorted and unsightly.

Towards the close of the reign of King Edward the Third the outline of window-tracery began to show a tendency to adapt itself to the vertical bearing of the mullions, instead of branching off from them in flowing undulations. This, the death-blow to flowing tracery, and with it to Decorated Gothick, gave rise to a new variety, at present known, in common with the period of Gothick Architecture during which it prevailed, as Perpendicular. Here, however, as in the previous changes, the alteration was very gradual; consisting at first, rather of the introduction here and there of a perpendicular member into compositions in other respects strictly flowing in their character, than of any decided verticality in entire designs. Thus in the east windows of the Churches of Houghton-le-Spring, Durham; St. Mary, Stratford, Suffolk; Charlton-on-Otmoor, Oxford, and in the south aisle of Tunstead, Norfolk, a perpendicular tendency is apparent in parts of the tracery (Section I. Decorated, Plate 9). The north and south windows in the Chancel of Wheat-hampstead, Herts, also, are curious examples of the gradually progressive influence of the vertical principle. In the Church at King's Sutton, Northants, is another window of transition tracery. The earliest examples in which the leading principle of the new style of tracery is completely carried out are, probably, those of William of Wykeham, in the nave of Winchester Cathedral, and the corresponding windows in the Church of St. Nicholas at Lynn, Norfolk; here the mullions rise through the window-head into the curves of the arch. This continuation of the vertical bearing of the mullions is the basis of all Perpendicular tracery: and though, as the Perpendicular period advanced, the application of this fundamental principle was carried to such an excess as to degrade tracery into mere panelling, and almost to destroy the characteristick qualities of the mullions themselves, still for a while it must be admitted that Perpendicular windows possessed features of great interest and beauty. In these earlier specimens of this style, the window-head is generally divided by tracery-bars rising direct from the mullions into the arch, and also by other similar members branching off from the same mullions and describing curves corresponding with those of the main arch. The principal compartments thus formed are again subdivided by form-pieces, variously arranged and modified, but for the most part having a vertical tendency. These members, from their bearing and position denominated *super-mullions*, generally rise alternately from the heads of the main lights, and from the actual mullions; and thus they divide the head of the window into double the number of lights contained in the lower part. (Section I. Perpendicular, Plates 5, 13, 16, 18, 23, &c.) The heads of the main lights are almost invariably *cinquefoiled*; whereas in the Decorated period the *trefoiled* heading of the lights was so prevalent



TUNSTEAD CHURCH, NORFOLK.

as to constitute a characteristick of the style. Above each exterior light, or of those main subdivisions which are formed by tracery-bars following the curves of the window-arch, a compartment of tracery is produced by a minor tracery-bar following the same curve, while an inverted arch, foliated, is placed within the space thus formed. This is a no less beautiful than peculiar feature of the finest Perpendicular tracery: it prevails in William of Wykeham's work in Winchester Cathedral, and is also exemplified in the beautiful windows in the south transept of Beverley Minster,* in the north transept of Merton College Chapel, Oxford;† in Ashborne Church, Derbyshire;‡ Headcorn Church, Kent; and St. Mary's Church, Oxford.§

The transom, which had been occasionally used during the Decorated Gothick period, and then generally consisting of a simple horizontal mullion, crossing the lights at right



ASHBY ST. LEGGER'S CHURCH, NORTHAMPTONSHIRE.

angles, speedily became a regular component of Perpendicular windows: this member dividing the lights into an upper and lower series; and the heads of the lights in either series being similarly foliated. Instances are frequently met with in which the transoms are embattled, as in the Church of St. Mary Magdalen, Wiggenshall, Norfolk: this Church also exemplifies the use of an embattled transom in the tracery. For another specimen of an embattled tracery-transom, see Section I. Perpendicular, Plate 18. A rich, though perhaps a scarcely legitimate, effect was sometimes produced by cusping the lights of the upper series

at the foot as well as at the head, and uniting them with those of the lower series, without any intervening transom-bar. A modification of this arrangement appears to have produced the panelled windows at the west of Winchester Cathedral, and Westminster Abbey Church.

Perpendicular tracery continued to degenerate in character from an early period after its first introduction, until its utmost effort appears to have been the production of the largest possible window containing, in lieu of tracery rightly so named, the greatest number possible of small pierced panels. Nothing can be more monotonous, or more devoid of all beauty or effectiveness, than this glazed panelling.

* See Britton's *Antiquities*, Vol. V.

† See Ingram's *Memorials of Oxford*, and Bloxam's *Gothick Architecture*.

‡ See Bloxam's *Gothick Architecture*.


§ See Oxford Glossary, Vol. II.

With the progress of the Perpendicular period, a remarkable change took place in the form of the window-arch: and indeed long before other parts of Perpendicular structures felt its destructive influence, the four-centred arch was in general use in the formation of windows.* In the tracery of windows constructed with the four-centred arch, if any degree of richness was attempted, it became a general practice to carry it considerably below the springing of the arch. Possibly from this arrangement, the idea of *traceried*-transoms might have been derived.†

In this period many windows were constructed of such ample size, as entirely to fill the end of that portion of the Edifice in which they were placed; as at Winchester, York, St. Alban's, &c. This vast extent of window was produced (in accordance with the laws of Gothick Architecture) not so much by increasing the size of the lights, as by adding to their number: thus the west window of Henry the Seventh's Chapel contains fifteen lights, and those at Winchester, St. Alban's, and York, each nine lights.




BLACKNEY CHURCH, NORFOLK.



FARNISH CHURCH, BEDFORDSHIRE.

Nearly every possible variety of arch appears to have been used in the construction of window-heads. As we have already seen, the pointed arch was the almost invariable shape adopted in the Early English lancets; occasionally, however, as in Thanington Church, Kent (Appendix, Plate 2), we meet with square-headed trefoiled lancets. The accompanying illustration is the north lychnoscopic‡ window from Westhamptnet Church, Sussex. The one from Thanington Church occurs in the north side of the tower.

WESTHAMPTNET
CHURCH, SUSSEX.

* We occasionally meet with Decorated windows with four-centred arches, as in Deopham Church, Norfolk.

† This arrangement is not uncommon in Decorated windows, though by no means so frequent as in those erected during the closing years of the Perpendicular period. See Section I. Decorated, Plate 13; also the beautiful window figured by Sharpe, from Billingborough, Lincoln. Other specimens occur at Herne, Kent, and Evington, Leicestershire.

‡ The term lychnoscope has been applied to a very peculiar window, to be found in Gothick Churches of all the different periods: most frequently it is placed at the south-west or north-west of the Chancel, and the sill is generally brought much nearer the ground than in any of the other windows. Temple Balsall Church affords an example of one to the south-west (Parish Churches, Vol. I. p. 15). It is still more frequent that both the north-west and south-west windows are of this description, as in the Churches of Westhamptnet, Raydon

At the close of the Early English, and throughout the Decorated Gothic period, the window-arch in most frequent use was the equilateral; and this is always the most beautiful form. Other window-arches which occurred during the Decorated period, were the



BRANDON CHURCH, NORFOLK.

acutely-pointed, the obtusely-pointed, the ogee, the segmental-pointed, and the segmental-circular. The ogee arch is not of frequent occurrence, nor is it often productive of a good effect: the segmental-circular is very rare. The square-headed arch was very generally



SOUTHFLEET CHURCH, KENT.

in use at this period: all the windows to the south aisle of Leckampton Church are of this description (Parish Churches, Vol. II. page 65). The tracery in these windows is sometimes



BICKER CHURCH, LINCOLNSHIRE.

very good and rich, as in Harbledown Church, Kent (Appendix, Plate 6), and Roydon Church, Essex (Sect. I. Decorated, Plate 13). Triangular-headed windows are occasionally to be met with, but they are defective both in grace of outline and soundness of construction. The example from Keymer



KEYMER CHURCH, SUSSEX.


Church, Sussex, is another curious instance of the never-ceasing search after improvement, in its course naturally producing some such extraordinary designs as the present, which is not instanced as a fit example for imitation. It may be considered as a link between the several successive changes in Gothic Architecture,—comparing it with the square-headed window from Southfleet, we can clearly identify it as a modification of the

(Sect. I. E.E. Plate 8), and Clymping (Parish Churches, Vol. II. p. 75). Very rarely are windows in other parts of the Church thus treated. Aldwinkle Church, Northamptonshire (Parish Churches, Vol. I. p. 51), may perhaps furnish an example of one at the west of the south aisle. Sometimes a separate opening in the wall was expressly provided, as in Crick Church, Northamptonshire, where we find a quatrefoiled circle; or in Bishop's Lydeard Church, Somersetshire (Parish Churches, Vol. II. p. 63), where the wall of the south Chapel, which apparently was subsequently added, is splayed so as not to block up the lychnoscope.

The real use of these curious openings in the walls of the Chancel (for, as we have seen, they are almost exclusively to be found in this part of the Church) is still a "vexata quæstio" among Ecclesiologists: of the various uses to which they have been supposed to have been devoted, such as confessionals, openings to watch the Easter Sepulchre, lepers, windows, &c., none seem to adapt themselves entirely to the different peculiarities of the case: at any rate we feel that no apology is necessary for not entering into a discussion which, though highly interesting, is no ways in accordance with the nature and objects of the present work. We would refer to some very instructive notices of this subject in the "Ecclesiologist," Vol. V. p. 164 and 187; Vol. VI. p. 40; and Vol. VII. p. 65.

former, by the omission of the two spandrels. Triangular windows were comparatively rare, except in clearstories : the example from Cottingham Church, Northamptonshire, occurs at the west end of the south aisle.

All these arches were continued, with the exception perhaps of the acutely-pointed and the ogee, in the Perpendicular era, with the important addition also of the four-centred arch. In very late windows, of this last named style, a label* sometimes took the place of a pointed dripstone or hood-mold ; and in this case, the spandrels, as at Monksilver Church, Somersetshire, were occasionally pierced and glazed. Square-headed windows were in constant use in the Perpendicular, as well as in the preceding periods : of these several specimens are appended. Circular windows also occasionally appear, but this beautiful form is by no means common in Gothick Edifices in this country.



COTTINGHAM CHURCH, NORTHANTS.


CLEARSTORY WINDOWS,

Which are almost essential features in Perpendicular Edifices, were of comparatively rare occurrence at an earlier period. The Anglo-Normans used them much more frequently than did the architects of either the Early English or the Decorated eras : thus, at Steyning Church, Sussex, we observe Anglo-Norman clearstory windows placed singly ; while they form arcades at St. Margaret at Cliffe, Kent, and St. Peter's, Northampton. At Southwell, as has already been remarked, the clearstory windows are circular. In early English Churches the clearstory but rarely formed a part of the design, except in the Cathedrals and other large Structures. Salisbury, Ely, Lincoln, and St. Alban's, have Early English clearstories ; and in Warmington Church, Northants, we find this feature consisting of a series of two-light windows.† Clearstories in the smaller Churches of the Decorated period were usually lighted

* The term Label (borrowed from Heraldry) exclusively denotes a horizontal string with rectangular returns : and the terms dripstone and hood-mold, severally refer to exterior and interior strings which enclose arches or openings. These terms are often, but most incorrectly, used indiscriminately.

† See Parish Churches, Vol. I. p. 17.

by a series of quatrefoiled circles. Examples of this arrangement occur at Meopham, Kent; Filby, Norfolk;* and Great Milton, Oxfordshire. At Garsington, in Oxfordshire, the circles have six foils; and at Stanton St. John, in the same county, in place of circles,



MEOPHAM CHURCH, KENT.

the clearstory lights are triangular and with five foils.† In the exquisite Decorated Gothic Church at Cley, Norfolk, the clearstory consists of double-cusped cinquefoiled circles, alternating with single lancets. At Bottisham Church, Cambridge-



FILBY, NORFOLK.

shire, a series of finely molded two-light clearstory windows occur; and at Raunds, Northants, a similar series approximates more nearly to the subsequent period—the Perpendicular.‡

From the introduction of Perpendicular Architecture to its decline, the clearstory was almost invariably introduced into all new Churches; and very frequently (to the great detriment of their beauty) was added to those Edifices which had been previously



HUMBERSTONE CHURCH, LEICESTERSHIRE.

constructed. Bishop's Lydeard Church, Somerset, is one of the rare examples of a Perpendicular Structure devoid of this feature.§ In smaller Churches, two-light and three-light clearstory windows, with square heads, were in common use, as at Humberstone Church, Leicestershire; and similar windows segmental-pointed, as at Histon Church, Cambridgeshire. As the period advanced, clearstories became much more important members of the compositions into which they were introduced; and the several windows being placed in close connection the one with the other, they frequently exhibited a considerably larger surface of glass than actual walling. Of this arrangement the Churches of Lavenham and Long Melford, in Suffolk, afford truly magnificent examples: in other Churches, however, of about the same date, the clearstory destroys the whole beauty of the Building by its monotony and apparent insecurity. At Melton Mowbray the clearstory over the nave is pierced by twelve large three-light windows, which are also continued round the north and south transepts.

* See Parish Churches, Vol. I. p. 37.

† See Oxfordshire Churches.

‡ See Parish Churches, Vol. I. p. 69; also Northamptonshire Churches, Vol. I. p. 59.

§ See Parish Churches, Vol. I. p. 63.

BELFRY WINDOWS,

In Norman Structures, generally consisted of a doubled semi-circular arch, divided by a shaft: or in richer designs, parts of the panelling were pierced for this purpose, as at St. John's Church, Devizes. Another not unfrequent arrangement is exemplified at Iffley, Oxon; where two panels are formed upon each face of the tower by two external strips of masonry and one central strip, and a recessed window of a single arch occupies each of the panels. In Semi-Norman towers the double arch with a central shaft is retained, as at Duddington, Northants,* and Repps, Norfolk. The same arrangement was continued throughout the Early English Gothick period, with such modifications as the new style demanded: examples occur in the Churches at Etton and Barnwell,



NEWHAVEN CHURCH, SUSSEX.

Northants.† In the last-named Edifice, the belfry windows are richly ornamented with foliage and dog-tooth. In the more important towers of this period, a pierced arcade was also a common arrangement, as at Raunds, Northants.‡ And again, in this, and also in the succeeding period, the belfry windows consisted of a series of small quatrefoiled circles, one pierced in each face of the tower, as at St. Mary's Cray, Kent, and Lindfield Church, Sussex (Section I. Early English, Pl. 4). In the Decorated period, a single two-light window in each face of the tower was the most usual arrangement, as at Badgeworth, Gloucestershire. In the fine Decorated Gothick tower of Southfleet Church, Kent, the belfry lights are four single lancets, each trefoliated at the head.§ At Herne Church, in the same county, two similar lancets occur in each face of the tower;|| and in the large and magnificent church of St. Mary, Redclyffe, Bristol, the upper stage is divided into three compartments, each containing a fine three-light window. In Perpendicular Gothick Edifices, the belfry windows differed from those of the preceding period rather

* Parish Churches, Vol. I. p. 5. The tower at Repps is one of the circular flint Structures so common in Norfolk: in this example, however, the flint-work is headed by an octagonal stage of ashlar, forming an arcade which is pierced towards the cardinal points with shafted double belfry windows, of strictly Semi-Norman character.

† See Parish Churches, Vol. I. pp. 13 and 31.

‡ See Parish Churches, Vol. I. p. 69; and the Churches of Northamptonshire, Vol. I. p. 53.

§ See Parish Churches, Vol. I. p. 19.

|| See Parish Churches, Vol. I. p. 7.

in points of detail, than in general design. In Churches of moderate size, a two-light belfry window in each face of the tower was the usual arrangement; while in more important edifices two windows* were similarly placed. In the latter case the general effect was considerably heightened by a buttress rising up between each pair of belfry windows, and being crowned by a light and lofty pinnacle. The towers of the Churches of St. George, at Doncaster; of St. Margaret, at Leicester; and at Bishop's Lydeard, Somersetshire,† are good examples, each containing a series of double belfry windows; and a similar series also occurs in the noble tower of Magdalen College Chapel, Oxford.

The towers of many Churches in Norfolk and Suffolk contain a peculiar window deserving of notice. It lights the floor of the ringing loft; and usually consists of a square enclosing a foliated circle, or some other geometrical figure. Some specimens of this window are given in Section I. Perpendicular, Plate 22. In the Early English towers of Northamptonshire, a circular window of this same description is also very frequent; and it is used for the same purpose. Examples occur in the Churches of Barnwell and Aldwinkle.‡ Similar windows of the same period appear in the Church towers of Leicestershire, as at Humberstone Church. At Section I. Semi-Norman, Plate 5, is figured a window curiously situated: it is pierced through the south and east buttresses of the tower of



HUNWORTH CHURCH.

Clymping Church, Sussex; the detached chevron, which is carried round the opening, imparts considerable richness to its pleasing proportions.§ The window in the west of the tower of Hunworth Church, Norfolk, is of very singular design: it is exceedingly difficult to assign a date to it, and at first sight it presents the appearance of a very early gable Cross, built into the wall of the tower;|| the rough terminations of the four arms, however, show that this was not the case, though it is more than probable that a gable Cross suggested the idea.

* Windows of three lights, so frequently occurring in the body of the Church, appear to have been sparingly used in belfries. In towers of great magnificence, two double lights under one arch was a more usual arrangement, as in St. Margaret's Church, Leicester.

† See *Parish Churches*, Vol. I. p. 63. Also see *Bloxam's Gothick Architecture*, Ed. 8, p. 236.


‡ See *Parish Churches*, Vol. I. pp. 31 and 59.

§ See *Parish Churches*, Vol. II. p. 75.


|| See gable Cross from Edith Weston Church, Rutlandshire, Section I. E.E. Plate 16.

TURRET LIGHTS.

No part of an ancient Building, not even the minutest detail, was considered by the builders of old as unworthy of their attention: accordingly we find that these small openings for lighting a turret staircase frequently displayed considerable elegance in design, and no little skill in their construction. Early examples are of rare occurrence; for, during the continuance of Norman and Early English Architecture, a staircase turret was by no means an usual adjunct to the towers of parish Churches.* In that of the Norman tower of St. Martin's Church, Leicester, the lights are mere square-headed slits; while in the turret at the N.W. angle of the tower of Achurch Church, Northants, an Early English Edifice of great beauty, is a very graceful arrangement for admitting light to the stairs, consisting of a series of small lancets with gabled canopies. Early in the Decorated period lancet openings




ACHURCH CHURCH,
NORTHAMPTONSHIRE.



WINTERTON CHURCH, NORFOLK.

continued in use for turret lights; as in a turret to the N.E. of the choir of St. Alban's Abbey Church.† At this same period narrow cruciform openings were also in use for this purpose, as in the conventual buildings at Ely (Appendix, Plate 7), and



ST. ALBAN'S ABBEY
CHURCH.

Waltham Abbey Church (Section I. Decorated, Plate 3). Subsequently, and during the Perpendicular Gothick era, small circles, squares, or triangles were more generally adopted; and these for the most part were enriched with various cusping and tracery (Section I. Decorated, Plate 36, and Perpendicular, Plates 13 and 22).

* Even during the Decorated period we occasionally meet with towers in which the only ascent to the belfry is by means of ladders; such is the tower of Weekley Church, Northamptonshire (Parish Churches, Vol. II. p. 84). In Perpendicular Churches the turret is of invariable occurrence.

† The Newel in this stair-turret is encircled by a spiral molding, admirably adapted to the grasp of the hand.

SPIRE LIGHTS

In their general features did not differ materially from other windows in the same Edifice, except that, in consequence of the peculiarity of their position, they were somewhat narrow in proportion to their height: and also, being generally set at right angles to the ground line, they rose like dormer windows from the sides of the spire, and were surmounted by acutely pointed canopies, which most frequently terminated in beautifully designed Crosses. In some early spires, however, the lights were merely quatrefoiled openings lying in the same plane with the spire, as at Fleet Church, Lincolnshire,* and Humberstone Church, Leicestershire. Canopied spire lights occur singly, as at Newington Church, Oxfordshire; or in two rows, as at Leekhampton Church, Gloucestershire, and Duddington Church, Northants, which is an early specimen of such an arrangement; while in other spires, three and even four rows of lights have been introduced, as in the Churches of Warmington, Northants,† and Ewerby and Grantham, Lincolnshire. The lights of the lowermost tier were of course invariably placed upon the cardinal sides of the spire, the upper rows sometimes alternated, but very frequently continued on the cardinal sides.

ON THE CONSTRUCTION OF TRACERY IN WINDOWS.

From a review of the chief varieties of Gothick windows, we proceed to examine into the principles of their geometrical formation. It is impossible for any person to have observed with the smallest degree of attention any number of Decorated windows, without becoming aware of the constantly recurring combination of the equilateral triangle. With very few exceptions, the window-arches of the Decorated Gothick period are actually founded upon that figure, or upon a very close approximation to it. The greater number of the heads of Early English Gothick lancets are similarly formed, as is shown at Section I. Early English, Plates 1 and 7. In Plate 1, from Great Wenham Church, where the lights of the triplet are trefoiled, the system of equilateral triangles has been, nevertheless, kept in view, as is shown in Diagram (B.), where the centres for the curves are at the several points of the triangle.

* See Parish Churches, Vol. I. p. 51.

† See Parish Churches, Vol. I. pp. 65 and 17. Also for other specimens of spire lights, see pp. 11. 13. 31. 51. 55. 57. 59. 61. 69, and 77, &c., of the same volume. See also, Northamptonshire Churches.

A minute examination of numerous specimens of tracery, collected from all parts of England, has led us to form the conclusion that this same principle of the equilateral triangle constitutes in them all the basis of their formation: in very many cases its truth is undeniable, and it will not invalidate this (assumed) constructive law that in some others, examples occur which do not in mathematical strictness comply with its requirements: for it is both easy and just to imagine that occasionally the *design* may have been duly prepared from the fixed rule of the equilateral triangle, and yet in executing the work, may have been slightly altered or modified, to suit some particular circumstance or taste, or even as a mere practical experiment. Thus, for instance, the annexed illustration of a window from Southfleet Church, Kent, will be seen to have been both designed and executed upon strictly equilateral principles; the window-arch is equilateral, so also are the heads of the two lights, above which is placed a quatrefoiled circle. In Shorne Church, at the east end of the north Chapel, occurs another window of precisely similar *design*, but in the execution of which we may perceive that the architect has allowed himself to deviate slightly from the precision which characterises the window at Southfleet: still he can scarcely on this account be regarded as working in absolute variance from the principles which determine the formation of this style of window. Such a deviation is but an instance of the legitimate modification of a general rule; it does not in the slightest degree tend to furnish an argument calculated to disprove its existence. So in Classic Architecture, to the discreet architect is left the privilege of slightly varying from the exactly-defined relative proportions of the column and its entablature, without his being thereby rendered obnoxious to the charge of impugning the proportional laws which have been established.

In the window from Northfleet Church (to resume the illustration of two-light windows), it is distinctly evident that the architect had in view *the same principle* which produced the Southfleet window, though he chose to depart from it in practice so widely, by unduly increasing the circle in the window-head. These examples will serve to show that, in endeavouring to ascertain the correct principles of formation in different varieties of windows, a satisfactory result cannot be obtained by experimentalising upon any one particular specimen: on the contrary, the only course calculated to lead to a really accurate conclusion is, first to classify Gothick windows in general, and then to search out from



SOUTHFLEET CHURCH, KENT.



SHORNE CHURCH, KENT.




NORTHFLEET CHURCH, KENT.

a variety of specimens of each class (as, for example, from a variety of two-light windows having a circle in the window-head), the existence of some particular principle by which their formation may have been regulated.


For ourselves, having carefully proceeded with such an investigation from one class of windows to another, we have been led to adopt the opinion that the equilateral triangle is the basis of *all* Decorated Gothick tracery;* and now we desire to justify, and if possible establish, the accuracy of that opinion, by adverting to a diversity of examples in every class into which that important member can be divided, during the Decorated Gothick period.

In some windows it is difficult, or rather scarcely possible, to discover the existence of the equilateral principle of formation, except by actual admeasurement; in others,



a comparatively slight examination will render that principle clearly apparent; and again, in other examples, it is at once obvious to all beholders. Commencing with windows of this last character, we will adduce a specimen from the Church of St. Nicholas, at Colchester, which may be fairly regarded as a type of a class: here the principle of formation is distinctly evident; we easily perceive

that the equilateral triangle $A B C$, subdivided into four similar figures, will give all the centres for the tracery; B, C , being severally the centres of the window-arch, and e, e, e ,



the centres for the arches of the tracery. In Plate 2 of Section 1, Decorated, is a similar example from Northfleet Church; and in Plate 8 of the same subdivision, is figured another elegant variety of this style of window, from Capel St. Mary, Suffolk. Hingham Church, Norfolk, affords an example of a three-light window of like character (Appendix,

Plate 4), and in Trinity Church, Hull, is one of a similar design with six lights.† The circular window in Leek Church, Staffordshire, is also a remarkable specimen:‡ as are likewise those in the Bishop's Palace, Southwark,§ and Chichester Cathedral.|| The east window of the Church of St. John, at Staunton, Oxon,¶ again, is a curious example, and at the same time a most valuable witness in favour of this principle of the construction of tracery:

* The term *Tracery* must, to a certain degree, be restricted to the windows of the Decorated Gothick period: inasmuch as in those of the succeeding period, the window-heads for the most part degenerated into a species of pierced panel-work.

† See Sharpe's Decorated Windows.

‡ See Bloxam's Gothick Architecture, Ed. 8, p. 220.

§ See Britton's Antiquities, Vol. V.

|| See Britton's Antiquities, Vol. V.

¶ See Architectural Antiquities in the neighbourhood of Oxford, p. 225.

for here, what in other cases must have been the formation lines, are worked into the design, and the tracery consequently consists of intersecting lozenges which, if subdivided, would naturally produce a series of equilateral triangles. The example from Harbledown Church, Kent, could hardly be the result of any other than of a system of triangulation.

We pass on to the second class of windows, in the tracery of which this principle of formation, though existing, is not so manifest as in the preceding examples. Of these there are two chief varieties: first, those with intersecting tracery, as in the two-light windows at Stoke Albany (Section I. Early English, Plate 17), and Little Wenham, Suffolk (Section I. Early English, Plate 5); in three-light windows, at Meopham, and Herne, both in Kent (Section I. Early English, Plate 10, and Decorated, Plate 20); and in windows of five lights at Trumpington, Cambridgeshire (Section I. Decorated, Plate 29). In all these windows, whether of two or more lights, it will easily be seen that the outer arch being equilateral, all the subdivisions of the window-head, produced by tracery-bars following the curves of the outer arch, must of necessity be equilateral also. Many windows of this style have no further attempt at tracery than that which is formed by this intersection of tracery-bars continuous with the mullions: and even where further enrichment is added, it is always of a secondary character, and leaves the original formation of the more important members of the window-head distinctly visible. Such enrichment usually consists of circles, or other geometrical figures, which must of necessity be tangent to the four intersecting sides of the compartment within which they are inserted; or, sometimes it extends no further than to the mere foiling the several compartments. With these intersecting windows may be classified all two-light windows, in which tracery-bars diverge from the head of the mullions, and describe curves similar to those of the window-arch; in fact, these tracery-bars, if produced, would intersect the sweeps of the arch within which they are contained.* (See Section I. Decorated, Plate 3.)



HARBLEDOWN CHURCH, KENT.




SOUTHFLEET CHURCH, KENT.

The second subdivision of this second class of windows comprises by far the greater

* No two-light window can be said to have *intersecting* tracery, except upon the principle here laid down. It is upon this principle, therefore, that the tracery in the windows of the Churches at Stoke Albany and Little Wenham is said to intersect.

part of that manifold variety of designs which is exemplified in the window-heads of the Decorated Gothick period. In windows of net-tracery we detect, more readily perhaps than in any other variety of flowing tracery, the working of the equilateral principle. It is true, indeed, that in examples of this class the angularity of the figure which governs the formation is, in execution, altogether suppressed; not only is every line a curve, but also every curve is made to undulate: nevertheless, upon examination, the practical influence of this figure is speedily recognized, and in forming a diagram, it will almost involuntarily be reproduced. Thus in two-light windows of net-tracery, as at St. Margaret's, Herts (Section I. Decorated, Plate 8), three equal circles tangent to each other, the centres of which must of necessity be the three angles of an equilateral triangle, determine the tracery of the window; and the undulations of the main curves of the tracery all result from the apposition of other similar circles. In constructing a three, four, five, or six-light window of this class, we have only to set out a proportionate number of triangles, in order to find the centres for all the requisite curves. An admirable modification of this tracery, so easy to set out, and of such great beauty, is exemplified in the door of Holbeach Church, Lincolnshire (see Section I. Decorated, Plate 10): here the apparent capriciousness of the design is brought within the simplest rule, as shown in the accompanying diagram. One series of equilateral triangles determines the centres of the larger circles, while a second series of similar and equal triangles gives the smaller and inner circles. In the window figured in Plate 5 of Section I. Decorated, from Northfleet Church, this principle of formation is shown to determine the construction of a totally different design: the same is the case as regards the subsequent specimens, in Plates 6, 9, 11, 13, 15, 18, and 26, all differing more or less one from another.

Nor will this principle be found applicable only to tracery of windows. The beautiful



PAVEMENT IN WESTMINSTER ABBEY.

mosaick pavement in the Chapel of Edward the Confessor, Westminster Abbey, is a most remarkable example of the not always observed but ever active influence of the equilateral triangle in all the purer designs of the Middle Ages, and also of the earnest desire to assign to that figure a distinct and prominent position. The same remark is equally applicable to the exquisite diaper in the great Flemish Brasses at St. Alban's, Lynn, and Newark.

The peculiar geometrical properties of the equilateral triangle,—its easy subdivision into similar triangles,—the part it takes in the forma-

tion of the hexagon (the most compact of all figures, and therefore the best adapted to form the basis of tracery)—these points are more than sufficient to furnish a satis-



ST. ALBAN'S ABBEY CHURCH.

factory reason for our finding this triangle the governing principle in the formation of all that is most beautiful in the most beautiful style of Architecture. With its geometrical value, also, we may not fail to associate the remarkable symbolism of the equilateral triangle: a qualification of no slight importance in the sight of those who employed it so effectively; as we needs must infer from their evident anxiety visibly to impress its form upon their works, as well as to employ it as a governing principle in the formation of them. The very elegant tracery in the Spandrel from Bottisham Church (Section II.

Woodwork, Plate 14) illustrates in a striking manner

the desire both to use and to show the equilateral triangle: the construction of the design is evidently a combination of such triangles, and in the form and arrangement of the decorations we perceive throughout the prevalence of a similar figure; even the hexagon is subdivided into trefoils. So also in window tracery, the same studious display of triangularity is constantly apparent: the window in Northfleet Church, represented in Section I. Decorated, Plate 2, comprises three trefoiled lights, surmounted by as many triangles, each of which is doubly trefoiled, while single trefoils occupy the intervening spaces. This remarkable triplicity is, indeed, in a greater or a lesser degree inherent in all pure Gothic work. In Plate 25 of the Early English portion of Section I. this triplicity is even unusually apparent; for in the Cross engraved on a coped coffin stone at Barnwell, Northamptonshire, the entire design consists of a series of trefoiled leaves.

But let us return to the more direct consideration of the subject, from which we have permitted ourselves thus widely to digress. In the four-light window of Sleaford Church (Section I. Decorated, Plate 26) we are led, without any great difficulty, to detect the influence of the equilateral principle. Here the main bars of the tracery display, somewhat modified, the outline of a window of net-tracery of two lights only: and though it is not actually struck from the angles of an equilateral triangle, but has the central figure slightly elongated, in order to impart a greater degree of elegance to the second order of tracery with which it is filled; still it cannot be doubted that in this, as well as in all similar specimens, that same principle of formation was carefully kept in view. In the

other window from the same Church, which is figured in Section I. Decorated, Plate 18, the deviation from the outline of net-tracery is carried to far greater extent : but even here it would be difficult to maintain that the constructive principle of net-tracery had not, in the first instance, been used as the ground-work of the design. And once more, the four-light window from Holbeach Church (Section I. Decorated, Plate 7) is another instance of a somewhat similar departure from a strict rule with a view to suit the circumstances of a special case, or to gratify peculiar ideas of the beauty of a traceried window.

In the woodwork of the porch of Bradwell Church, Essex (Section II. Woodwork, Plate 13), are instances of two perfectly different designs of tracery, though both formed upon the same basis. In the same plate is another specimen, in which an attempt has been made to produce net-tracery from the intersection of *squares* instead of equilateral triangles ; but the effect thus produced is singularly distorted and unsatisfactory, and would appear still more so, were the design continued over a larger space. How different is the result where the triangle is the principle of formation : then all is consistent, harmonious, and elegant.

Finally, with reference to those windows, in which the equilateral principle, though certainly existing, cannot be discovered without a more searching examination ; the circular window in Waltham Abbey Church is a truly wonderful specimen. By referring to the diagram in Section I. Decorated, Plate 4, it will be seen that the intersection of a series of equilateral triangles will give the centres of every, even the minutest curve in the entire figure.* It cannot be that such a circumstance is merely fortuitous : rather it argues the window to have been the work of a profound practical geometrician, who produced his design, compass in hand. A similar instance occurs in the crowning ornament over the doorway into the cloister of the Abbey Church of St. Alban's (see Section I. Perpendicular, Plates 1 and 2) ; the curves for every portion of the design may be proved to have been described from centres determined by the angles of equilateral triangles (see Plate 2). In these and like examples, indeed, a careful investigation is necessary in order to discover the principle of formation, to reproduce, as it were, the original design. But then that principle is thus to be detected, and, in like manner, a similarly careful investigation will not fail to show that, throughout the purest period of Gothic art, the equilateral triangle was the great principle of general design and


* It does not appear necessary to increase the space occupied by this article upon windows by a further reference to any of the other plates ; still less because in nearly all the specimens of windows the centres of the tracery have been laid down, and the existence of the equilateral principle, in a greater or a lesser degree, made apparent.

formation, and also was, in very many cases, made prominently apparent in the work itself when executed. Hence, its *equilateral triangularity* may be pronounced an essential characteristic of Gothick Architecture. In the outline of the canopied windows, doorways, and niches of a Decorated Gothick Structure, and in the prominent position assigned to its buttresses and pinnacles, we may recognise this characteristic no less than in the form of its traceries and diapers,* its pavements and carved ornaments. It is true that some example of window† may be adduced which it would be difficult, if even possible, to class in common with any of the varieties which we have now examined: but, in an age in which the love of novelty in Architecture was ardent and almost universal, when every endeavour was constantly directed to the improving what already was of surpassing beauty; in an age in which there must have been gradations of talent scarcely less multifarious than the diversities in taste—in such an age the existence of some anomalies cannot be reckoned in any degree extraordinary, or rather it would indeed be most extraordinary had no such anomalies been found. As we before observed, therefore, in our search after a governing principle of Gothick formation, we must be guided, not by individual examples, but by the *general practice*.‡

* A very beautiful diaper on this principle occurs in Canterbury Cathedral. See Willis's account.

† The statements here made, with special reference to windows, extend with equal justice to the other members of the Gothick Edifice.

‡ The lodge in Rushton Park, Northants, exemplifies the practical application of the equilateral triangle in a manner too remarkable to be here altogether unnoticed. The plan is an *equilateral triangle*. The roof on all three sides is divided into *three equilateral gables*; and in the windows, and from them to every minutest detail, the same principle has been carefully kept in view. We subjoin a cut of one of the windows of this curious building, a full account of which will be found in the "Builder," Vol. III.



WINDOW IN RUSHTON LODGE.

MOLDINGS.*




IN treating of the Moldings of Mediaeval Architecture, we propose to notice separately the more important of those members with which they are usually associated; for we hope to be better enabled by this, than by any other system of arrangement, to produce a practical analysis of the science of Gothick Moldings, without at the same time being in any degree induced to depart from that conciseness and brevity which the general plan of this work renders imperatively necessary. It appears requisite, however, first to advert to the great and remarkable difference which is apparent between Gothick Moldings and the corresponding members of Classick Architecture; a difference extending alike to their outline, grouping, and position. Thus, the entire collection of moldings in ancient examples comprises but a few different forms; and these definite in their character, and introduced into certain positions, and in accordance with established rules: whereas, in Structures of the Middle Ages, variety of outline is no less essentially characteristick of the moldings themselves, than the frequency of their occurrence is characteristick of the Gothick style. Gothick moldings, indeed, appear in almost every conceivable position: from the bases of piers and the piers themselves to the ribs of the fretted vaults which they sustain, scarcely a member occurs which is incapable of receiving consistent decoration by this most elegant method. And it may be added that in this multiplicity of molding-work, the almost only combinations which are *not* commonly found are such as would have appeared to assimilate to, or to have been derived from, classick authority.

Such being the practice of the Masters of Gothick Art, we are disposed rather to assign to themselves the invention and development of their own admirable system of moldings, than to seek its origin from another source. It is no argument whatever in support of the opinion that Gothick Moldings are derived from Classick Architecture, that in buildings of the Anglo-Norman style a rude resemblance to certain ancient moldings may be traced, especially in bases: for the Anglo-Norman, being a form of Romanesque, is altogether distinct from Gothick Architecture. Neither does the same supposition acquire much weight from the fact of a casual similitude of outline in a

* The authors feel much pleasure in availing themselves of this opportunity to express thus publicly their high opinion of the Treatise upon Moldings, lately published by Mr. Paley, which possesses the rare combination of being equally valuable to the professional architect and the amateur student of Architecture.

few instances, between Roman and Gothick Moldings; or from a close approximation to the attic base, occasionally to be observed in some few Early Gothick examples.



No. 1.

This resemblance to a regular classick member only existed during a transitional, and necessarily an imperfect, period: with the final abandonment of the circular arch, a sudden change appears to have taken place in the moldings of bases, as well as of other members; and, in place of the modification of the attic base, a widely different composition was introduced. In the annexed figures No. 1 is the attic base, No. 2 its Early



No. 2.



No 3.

English imitation, and No. 3 a base which is found to have immediately succeeded to the latter, if, indeed, it was not in use at the same time.

Leaving to others a further investigation of their origin, we now proceed to the more direct consideration of Mediæval moldings.* These members most frequently occur in the jambs to windows and doorways, in pier-arches, in capitals and bases, in cornices, vaulting ribs, strings, basements, and in some other positions. And first of JAMB MOLDS. These, in the earliest examples of Norman doorways, are for the most part simply squared back from the walls without the slightest attempt to enrich the surfaces with moldings, properly so called, as at Fritwell Church, Oxfordshire. Recessed jambs were, however, introduced at a very early period of the style; and this arrangement continued in favour, both in windows and doorways, until the most perfect period of Gothick art.† In Norman jamb molds when thus recessed, it was the prevalent habit to place detached shafts in each nook or interior angle, and in this case the several recessed orders, and sometimes the jamb shafts also, were often enriched with the peculiar though diversified surface-carving of the style; the south doorway of St. Mary's Church, Easton, Hants, furnishes a good example of shafted jambs; and other specimens are figured in Section I. Norman, Plates 1, 4, 6. These jamb shafts occur in a great variety of forms; most frequently, indeed, they are circular, yet occasionally their form is octagonal, or twisted, as at Section I. Norman, Plate 4, or slightly pointed; this last-named variety is restricted to late specimens, as in the Chancel arch at Codford St. Mary's (Section I. Semi-Norman, Plate 5); and again, at Weald, in Essex, in the south



ST. MARY'S, EASTON.


* The moldings of the Anglo-Norman style being in so many Edifices associated with their Gothick successors, it has been considered expedient here to give a place for the consideration of these latest developments of Romanesque work, in connection with Gothick moldings.

† It will be borne in mind that the jambs of Norman windows differ but very slightly, if at all, from those of the doorways: in fact, in most cases they are precisely identical, except in use and position.

doorway, another curious form of jamb shaft is exemplified. In some arches the customary shafts were either entirely dispensed with, or restricted to the sub-arch only, while the different faces of the recessed orders in the jambs were richly ornamented, as at Iffley Church, Oxon, and Malmsbury Abbey Church.

Before proceeding any further, we must remark that in jamb and arch molds, three different planes occur in which the moldings lie: these have been distinguished by Mr.

Paley as the *Wall Plane*, that is, any plane (A A) parallel with the main wall; the *Soffit Plane*,* or any plane (B B) at right angles with the wall plane; and the *Chamfer Plane*, or such a plane (C) as is generally, but by no means invariably, placed at an angle of 45° with the two planes before mentioned.



In the Anglo-Norman style the jamb molds were almost always worked in the wall and soffit planes; and this continued to be the general arrangement throughout the Early English Gothic period, although we occasionally (as in Section I.




Early English, Plate 3) find the jamb molded on the chamfer plane. During the earlier portion of the Decorated Gothic period, the wall and soffit planes still continued to be most generally used, but then in tolerably frequent connection with the chamfer plane, which at this time was in most cases worked exactly at an angle of 45° with the wall and soffit planes. Perpendicular moldings are generally characterised by their lying in the chamfer plane, which was no longer usually true to the angle of 45° : and as the style advanced towards the era of decided architectural debasement, the moldings shared in the prevailing desire to produce a meretricious effect, without any reference to correctness of composition: accordingly we find that in many late examples, as in the west doorway of Lavenham Church, Suffolk (Section I. Perpendicular, Plate 7), the moldings, besides the debasement of their contour and grouping, appear hardly to lie in either of the proper molding planes.

But to return to the jamb molds: in the Early English Gothic period, the door-jambs continued most frequently to be worked in a series of rectangularly recessed orders, with detached shafts of cylindrical form and comparatively slender proportions placed in every nook. An elegant deviation from the common and simple form of this arrangement occurs in the south doorway of St. Martin's Church at Leicester (Section I. Early English, Plate 23), where a secondary series of shafts is introduced with excellent effect. In this period, also, as in the preceding style, some door-jambs occurred in which shafts took no part in the design; or at least in which (also as before) they only appear as supporters of the sub-arch of the compound archway: in these examples, however, the angles of the several orders which the

* This term is scarcely correct, when applied to jamb molds: still, it has been here retained in consequence of its general accuracy, and to avoid the introduction of new terms.

Norman architects left untouched, their successors invariably chamfered off ; and the chamfers thus produced were frequently hollowed out and filled with the beautiful tooth ornament, or they were carried up plain to the impost of the arch, and there terminated in some elegant device (see Section I. Early English, Plate 21). In the Decorated Gothick period the detached shafts were entirely abandoned, in door-jambs as well as other positions ; in doorways, however, shafts were still retained, but so far altered in their character as to be almost invariably attached to the mass of the Structure. It may here be remarked as a general rule, that when shafts, engaged or otherwise, were used, the moldings they carried were placed



FEN DITTON, CAMBRIDGESHIRE.

on the *rectangular planes* ; but if the shafts were dispensed with, and the jambs were continuous with the arch, then the moldings were worked on the *chamfer plane*, as in the priest's doorway, Fen Ditton Church, Cambridgeshire. This arrangement is well illustrated in the north doorway of Swatton Church, Lincolnshire (Section I. Decorated, Plate 23), where part of the jamb mold is on the chamfer plane, and part on the rectangular planes ; the former is continuous with the arch mold, the latter has a shaft with cap and base, and carries a perfectly distinct series of arch moldings. Perpendicular jamb molds being, perhaps, invariably worked on the chamfer plane, were therefore much more often continuous with the arch mold than produced by shafts.

The arrangement of the window-jambs during the successive periods was generally in close accordance with that of the doorways. In the richer examples small shafts were introduced (after the fashion of the Norman architects), which, rising up to the springing of the window, carried one or several orders of the arch moldings. At all times these shafts were used much more frequently in the interior of the window than on the outside ; a window in the south transept of Wissendine Church, Rutland, however, has a magnificent arrangement of triple jamb shafts externally, resting on a steep and weathered sill. The south aisle of St. Martin's Church, Leicester, has some excellent examples of the use of this member internally.

Other instances of jamb shafts in windows will be found in Section I. Early English, Plate 13, where they are placed outside ; and in Plates 10, 12, 15, 17, and 20 ; and Section I. Decorated, Plate 29, in all of which they occur on the inside.

It must, however, be borne in mind that though most exquisite adornments, moldings are not nevertheless essential accessories : many windows with tracery of the richest description have their mullions and jambs composed of simple chamfers ; see the windows in Northfleet, Section I. Decorated, Plates 2 and 5 ; and also those given in Plates 13 and 15.

ARCH MOLDINGS, even when not continuous, partook of the same general arrangement as those in the jambs, with greater richness of detail: thus, when shafts were employed, they carried groups of moldings more elaborate than those of the jambs, though still falling upon the same planes; as in the west doorway of North Mimms Church, Herts (Section I. Decorated, Plate 25). During the continuance of the Norman, Early English, and Decorated periods, it was the invariable practice, in the case of arches dividing the nave from the aisles, or the Chancel from its adjoining chapels, to keep them entirely distinct from the piers on which they were carried: these latter were frequently simply circular, or octagonal, while the arches were most elaborately molded or enriched, as in New Shoreham Church. (Section I. Semi-Norman, Plate 3.) Even when both members were equally ornamented, as in the magnificent examples in St. Patrick's, Patrinton, their separate characters were nevertheless preserved; while in Perpendicular, on the contrary, we may perceive a much closer connection to exist between them. The piers and arches given in Section I. Perpendicular, Plate 14, show the arrangement generally adopted at this period; shafts placed at the cardinal points of the pier supported part of the arch moldings, the remainder being continuous and common to both members.

CAPITALS were either molded or carved with foliage, animals, &c.; they always however, consisted of three distinct parts, which require to be most strictly kept in view, if we would preserve the peculiar character of this important feature. These three divisions of the capital may be described as the *head mold* A, the *bell* B, and the *neck mold* C.

In Norman capitals the head mold was, almost without exception, square on plan, and consisted of a few simply arranged moldings; in the richer examples this member was adorned with some of the innumerable sculptures common at that period. (See Section I. Norman, Plate 5.) In this same plate are represented different examples of ornamented bells,* some of them very quaint. The peculiar form of capital which occurs in Waltham Abbey Church, has been distinguished by the name of cushion capital; it is usually a mark of early work. At other times, and especially in late work, the bell was carved with the most elaborate, and sometimes most beautiful, sculpture; geometrical and interlaced patterns, foliage, flowers, rude representations of animals and human figures, and even entire legends, occupied the whole space. Such endless variety in design would excite our surprise, were we not to reflect that it was (and indeed *is*) in the spirit of Gothick


* This term, borrowed from classick Architecture, is in many cases scarcely appropriate; yet it is so convenient, and its meaning withal is so well understood, that it has been considered advisable to retain it, rather than add further complexity to the architectural nomenclature by the introduction of a new term.

architecture to embody in its sculpture any matter of faith or legend, which were thus transmitted from one generation to another ; even passing events we may imagine to have been, in the olden times, at once, and almost imperishably, noted down with the chisel. Could we but read them, how much of historical lore might not these old Norman sculptures reveal to us.

The neck mold, the lowest portion of the capital, never assumed an important position ; and during the Norman period generally consisted of a bead, or a square with the angles taken off.

In the succeeding styles these three parts of the capital, though always existing, were less prominently marked ; and indeed it has been a very common practice in the revived Gothick moldings to lose sight of the *distinct* existence of the head mold and bell, which have accordingly merged into one, and the *character* of the capital been thereby entirely destroyed.

In the accompanying cuts, A is a capital from St. Alban's Abbey Church ; and B shows how the separate parts of the head mold and the bell, if lost sight of by the undue projection of the latter, become converted into one. Now a close examination of ancient examples will establish, as a general rule,* that the head mold was the most projecting member ; then came the bell, falling back a little from it ; and lastly the neck mold, which receded still further



from the face of the bell. In other words, we might regard a Gothick capital as consisting of three circular pieces of stone : the lower one a thin slab, out of which the neck mold would be produced ; the second, a thick block projecting considerably over the first, would form the bell ; and lastly, another slab at top, somewhat thicker than the first, and projecting the most of the three, out of which would be cut the head mold.

The heaviness observable in some modern capitals is principally owing to the neglect of this simple arrangement.

The bell, when not foliated, generally consisted of a group of moldings in the upper part, which were united to the neck mold by a beautifully undereut and gracefully curved outline ; or occasionally, and the effect is extremely beautiful, the bell was double, consisting of two different groups, the one receding from the other, as in Fig. 3, Section I. Early English, Plate 24 ; and Fig. 2, Decorated, Plate 35. The neck mold of the Gothick period did not acquire more importance than it had during the Norman ; it still consisted of a bead or some other simple molding. Finally, we would remark that while a general squareness of outline marked the Norman capitals, the Early English and Decorated were distinguished by being circular, and the Perpendicular by being octagonal.

* Examples are occasionally found in old work in which this principle has not been followed, but their rare occurrence in no way affects the general rule.

BASES consist of two distinct parts, the *plinth* and the *base moldings*: the former member was most apparent during the Norman and Early English periods; in the subsequent styles, though always to be found, it was, nevertheless, at times hardly discernible. The Norman plinth, in conformity with the head mold of the capital, was almost invariably square, and usually consisted of a plain unmolded mass of stone, on which rested the base moldings: these latter took the shape of the pier, and the blank spaces which result from placing a circle or octagon upon a square, were enriched with foliage, animals, or other ornaments. (See Section I. Semi-Norman, Plate 3.) Frequently the plinth was double, in which case the lower member was generally chamfered, as at Orpington (Section I. Semi-Norman, Plate I.); or molded, as in the triplet from the Chapel of St. Bartholomew's Hospital (Section I. Early English, Plate 15). In Early English, double and even triple plinths are commonly met with, as at Clymping (Section I. Early English, Plate 5), and from the richness of the moldings with which they are ornamented, frequently assume considerable importance: see a base from Westminster Abbey Church, Section I. Early English, Plate 24, Fig. 12. During the Decorated period, the plinth lost much of its prominence; in fact, the entire base was generally a less striking feature than it was in the preceding style: instances, however, may be found of triple plinths, as in Hingham Church, Norfolk (Section I. Decorated, Plate 33, Fig. 10); and Tunstead Church, in the same county, furnishes an example of a quadruple arrangement of this member. The Perpendicular plinth grew to a most exaggerated height, was constantly double or triple, and from the number and richness of its parts, requires a close examination to separate it from the base moldings. The tower piers of St. Margaret's Church, Westminster, have fine specimens of this style. Sometimes, as in the sedilia at Cobham (Section I. Perpendicular, Plate 9), the base consisted solely of a plinth, the base moldings being entirely omitted. In plain Churches of the Early English, and still more so of the Decorated period, a chamfered plinth, of a few inches' projection, was the most usual termination to the nave piers.

Shortly after the introduction of the Early English, the plinth began to adapt itself to the form of the pier which it supported: the change, however, was gradual; the square became an octagon, as in Westminster Abbey Church, where delicately carved knobs of foliage fill up the spaces which occur between the octagonal plinth and the circular base molds; finally, the plinth assumed the form of the base moldings and bent in and out with the outline of the pier. It is very singular that, after a lapse of time, the plinth should once more have become octagonal, though the base moldings still retained the circular form; and in Perpendicular it was frequently the case that both plinth and base molds were wrought in octagonal faces, leaving only the upper molding of the latter to follow the shape of the

shaft. In Churches of Perpendicular date it was customary for the base moldings to encircle the shafts only; while the plinths, on the contrary, were carried round the whole pier, as in Lindfield and Lavenham Churches (Section I. Perpendicular, Plate 14).

BASE MOLDINGS admit but of little variety of form or arrangement. A very common Norman base molding consisted of a hollow and quarter-round, and it is not a little singular that the resemblance to the attic base did not occur till the style was considerably advanced; in fact, it was during the Early English period that this resemblance became complete.



Base moldings were also extensively used round the walls, buttresses, and towers of Churches. Those of the Early English period were generally very plain and unimportant. The beautiful little Church of Skelton, near York, is enriched inside with moldings of the most elaborate description, though externally the walls and buttresses have merely a chamfered *table*.* The tower of Fen Ditton Church, Cambridgeshire (Appendix, Fig. 1, Plate 6), has a plain but effective arrangement of moldings. In many of the Decorated and Perpendicular towers the base moldings became highly ornamental and essential portions of the design: those in Hingham Church are peculiarly magnificent, and are panelled with a great variety of beautiful designs.† The tower of Worstead Church is an equally rich example of a somewhat later period; the combination of the panelled flint work and the sunk quatrefoils has a very good appearance. The neighbouring Church of Tunstead, of the same date, has also some excellent and carefully wrought moldings. (Section I. Decorated, Plate 30.) Generally in Decorated work the grouping of the moldings is so judicious, that even when left unenriched by tracery, they still present a pleasing, and in some instances, a grand and imposing effect. Perpendicular basement moldings were much more frequently panelled. In Norfolk and Suffolk, flint panelling is a very common enrichment, and, indeed, a volume might be devoted to the illustration of the elegant and ever varying devices which abound in these counties. St. Mary's, Stratford, may be cited as a most perfect specimen of this style of workmanship. In this instance an inscription appears on the basement moldings, by which we learn that that part of the Church (the north aisle) was erected in 1430; see Section I. Perpendicular, Plates 11, 19, and 20. In producing these flint enrichments, the "modus operandi" consisted in tracing the outline of the design on the stone, then sinking it a few inches, and afterwards filling up the sunk parts with small flints; or where the cavities were very minute, a kind of black pigment was used.


* Table appears to have been the general term for any horizontal member in Gothick Architecture; such as corbel table, crest table, skew table, water table, &c. See Willis's Nomenclature.

† This interesting and pure specimen of a Decorated Church was erected between the years 1316 and 1359. It is illustrated by two views and a plan in Vol. I. of the Parish Churches.


STRINGCOURSES and DRIPSTONES are so frequently identical, the one being carried on and forming the other, as to render it necessary to examine them together. Strings perform no insignificant part in the general design of the Building, "sometimes rising abruptly in graduated and rectangular heights; sometimes carried over a doorway or round an arch; now dying into the wall; now as it were passing into some interrupting projection, and, nothing baffled by it, re-appearing on the other side; now starting aloof into a window label and playing the most fantastic tricks before it again descends; a stringcourse at once relieves naked masonry, and binds into a whole the seemingly detached portions of a rambling and irregular construction."*

The most usual, and perhaps the essential position of the stringcourse is under the windows; which are thus divided from the more solid parts of the basement. The greater number of Churches, especially those of the Early English and Decorated period, were adorned with this apparently insignificant member; and in most cases where it was omitted, the walls present an unfinished and naked appearance. A corresponding string was generally carried round the inside of the Church, under the windows and over the doorways, as at Southfleet Church, Kent.

Norman strings were usually heavy in their outline, and rarely displayed any particular beauty of arrangement: they were, however, very frequently much enriched with the ornamental sculpture of that period, as in Waltham Abbey Church, and St. Peter's, Northampton. Early English strings, on the contrary, were remarkably light and elegant, and displayed a great amount of taste and judicious treatment: freed from the restraint and horizontality of the previous style, they delighted in closely attaching themselves to those members which they were intended to adorn; accordingly we find



GOSGROVE CHURCH, NORTHANTS.



TICHMARSH CHURCH, NORTHANTS.

them now rose up close under the sill of the window, and then suddenly dropping to accommodate themselves to the arch of a low doorway, and again rising to run immediately under the adjoining window: at this period the strings were generally carried round an intervening obstacle, such as a buttress, rather than dying against it to re-appear on the other side, and such became the most accustomed treatment in the following style.


Decorated strings were frequently of great beauty; in these and in all other moldings of this period, there is a gracefulness of outline and a finish of

* Paley's Gothic Moldings, p. 69.


execution, that we look for in vain in any of the other styles. The very interesting Church of Bottisham in Cambridgeshire, may be mentioned as peculiarly rich in moldings of the most exquisite workmanship. In opposition to the practice, till then prevalent, the dripstones were most usually quite distinct from the stringcourse, and terminated in heads, flowers, animals, or some quaint devices. Occasionally, however, the hoodmolds were continued on from one window to the other, of which arrangement the Chancel of Chartham Church, Kent, offers a most pleasing example. (Section I. Decorated, Plate 22.) In the beautiful Decorated Chapel of St. Etheldreda in Ely Place, Holborn, the continuation of the hoodmold between each window, rises up into gables enriched with flowing tracery.

Perpendicular strings differed but little from the Decorated, except in their outline; which partaking of the general character of the moldings of this period, became more angular and distinctly marked. Their use was less frequent than was previously the case, and often the small village Church was erected entirely without them. Dripstones, however, were generally retained, and in most cases were simply returned at the springing of the arch, instead of finishing with terminal heads and flowers, such as were used by the Decorated Architects. In the richer Buildings, initials, shields bearing the Sacred Monogram, squares, pentagons, and octagons, sometimes with small flowers in the centre, and innumerable other devices were freely introduced. (Section I. Perpendicular, Plate 27.)

CORNICES are not essential features in Gothick Architecture; in fact, when used they might more rightly be considered as enlarged stringcourses. They occur principally under parapets, or at the eaves of roofs and spires: of the important part, however, which they perform in the open timber roofs of Norfolk and Suffolk, we shall treat hereafter. In Norman, and some Early English Buildings, the cornice was formed by the projection of the upper part of the wall, which was supported on brackets or corbels, and hence termed the *corbel table*. This arrangement was susceptible of, and frequently received, considerable enrichment; at Bicker Church, Lincolnshire, this table assumes the appearance of the heraldick nebulé line; by an easy modification the circles afterwards became trefoiled, and sometimes ornamented with dog-tooth in the soffit, as at Romsey. The *spire table* is deserving of considerable attention, for in a great measure the beauty of the spire depends on its judicious



ST. MARTIN'S CHURCH, LEICESTER.



BICKER CHURCH, LINCOLNSHIRE.

junction with the tower. Its projection from the wall was in all cases very inconsiderable. In the Early English Structures a series of small trefoiled arches, corbelled out from the wall,



OADBY CHURCH, LEICESTERSHIRE.


are commonly met with; the beautiful spires of St. Mary's, Stamford, and Ketton, Rutland, have examples of a very elegant arrangement; and a single hollow, studded here and there with ball flower or heads, was also introduced with excellent effect.

The hollow, more properly termed the *casement*,* which holds a prominent position in most cornices, was generally filled with heads, flowers, or running

ornaments: we may notice that the flowers in Decorated cornices usually spread over the remainder of the moldings (Section I. Decorated, Plate 37), while in the Perpendicular examples they were most frequently confined to the casement. (Section I. Perpendicular, Plate 12.)

Having now reviewed the arrangement, and the most ordinary positions in which moldings occur, we will examine the subordinate parts of which they are composed.

The earliest molding found in Norman work appears to be the circular bowtel, worked out of the edges of a recessed arch. This formation is clearly shown in many instances where the bowtel only commences some few inches above the springing of the arch, as in Sandridge Church, Herts.† A bowtel alternated with a hollow forms the principal arrangement of Norman moldings; their great richness was rather the result of a profusion of sculpture, always wrought on the rectangular planes, than of multiplicity or beauty in the moldings. The chevron and its almost innumerable varieties were conspicuous ornaments in Norman Architecture, and in some instances their formation was so complex as to require no little attention to disentangle the maze of stone-work. This beautiful ornament continued in use long after all others of the same date had been discarded. It was of constant occurrence in Semi-Norman, and may even occasionally be traced in Early English work.




SANDRIDGE CHURCH, HERTS.

Norman stringcourses partook of the heaviness of the moldings of that period. They

* Willis's Nomenclature.

† It is a peculiar characteristic of pure Gothick, that all moldings, panelling, or sculpture were always *sunk* from the face of the work. Such an arrangement is the natural result of a style, a distinguishing type of which was *only to introduce ornament as an embellishment to construction*; thus a capital would naturally be corbelled from the pier, the better to carry the superincumbent weight; hence its subdivision into head mold, bell, and neck mold; panelling resulted from a desire to enrich that which would otherwise be a plain surface, and consequently was wrought out of the face already existing; a row of dog-tooth generally exemplifies very well how ornaments also were worked out of the block. As the debasement gradually crept in, we find the contrary to have taken place.

had very little variety in form, frequently consisting of projecting ledges with one or both sides chamfered off. A few sections of the most oft occurring varieties are given in Appendix, Plate 6. The adjoined Semi-Norman example occurs internally in the north chapel of Bapchild Church, Kent, and in the original is coloured blue and yellow.



The hollow soon after its introduction became more and more undercut, and in the Early English style was frequently carried to such an extravagant excess, as to materially affect the durability of the moldings. During the continuance of the Semi-Norman, a new member made its appearance, the *pear-shaped* or pointed bowtel. We can easily trace its formation from the circular mold already noticed, by leaving the aris of the original square block uncut. From this *pointed bowtel* most of the subsequent Gothick moldings will be found to be derived, for by an easy transition it became a bowtel of one, two, or three fillets; all of which, with their numerous varieties, performed important



parts in the molding system of the purest period. The example in the appended cut was common in Early English and Decorated



work, and eventually gave rise to the wave molding—that most elegant of Gothick moldings—it having become usual by this time to gently round the fillet into the bowtel.* That this



wave mold derived its origin from the filleted bowtel is singularly clear; for at first we meet with instances, as in the doorway of St. Margaret's Chapel, Herts, with only one of the fillets rounded; and shortly afterwards, in the Chancel windows of Fleet Church,† Lincolnshire, we find both fillets rounded off, though



ST. MARGARET'S CHAPEL,
HERTS.



FLEET CHURCH,
LINCOLNSHIRE.

the molding still preserves its character of a filleted bowtel. As the Decorated period advanced, it lost more and more of its resemblance to its prototype; the curve, which at first gently united the fillet to the bowtel, gradually assumed more importance, at the expense of the latter: and it is not a little singular that in its most complete state, and when Decorated had arrived at its highest degree of perfection, the formation of the wave mold appears to have been from the three points of an *equilateral triangle*. A group of two or more wave molds, with intervening hollows, was a common and most beautiful Decorated arrangement. This mold was also of frequent occurrence in Perpendicular, though belonging more especially to the former period.



* This fillet gradually became smaller and smaller, until at last it was reduced almost to an aris.

† For a drawing of one of these windows, see Appendix, Plate 4, Fig. 37. The Church itself is illustrated in the Parish Churches, Vol. I. p. 51.



The ogee, the most generally used perhaps of all moldings, may with equal certainty be traced to the same source as the wave mold. It is in fact a half of the filleted bowtel. The



double ogee, formed by the junction of two ogees, was introduced towards the close of the Decorated, but became a more constant

and characteristick feature of the Perpendicular period. A remarkably early instance of this molding (probably fortuitous) occurs in the central shaft of the double bell gable of Skelton Church, Yorkshire: its formation



DOUBLE OGEE.

appears the result of an arrangement of four clustered filleted bowtels.

SKELTON CHURCH,
YORKSHIRE.

One more molding remains to be noticed, and though last it is perhaps the most characteristick and essentially Gothick of any: we allude to the *scroll mold*. Here again we may certainly refer to the bowtel for its origin. It is in fact a bowtel, with one fillet partially developed, and, as might be expected, its first occurrence is traced to shortly before

the close of the Early English period. Agreeably with their ideas of beauty, the Decorated architects treated it as they had the filleted bowtel: we find its angular outline gently softened, and at last it assumed the appearance so peculiar to the 14th century. This mold was more extensively used perhaps than any other, and its varieties became so numerous as almost to defy classification. It entered abundantly into the formation of capitals, bases, hoodmolds, and strings: it was rarely used in Perpendicular work.



Before leaving this subject, yet one other variety must be mentioned. The *sunk chamfer* is simple in its construction, yet generally effective in execution. Its production may have




SUNK CHAMFER.

been the result of cutting away the projection from the filleted bowtel, though it is perhaps easier to imagine that it was simply sunk from the plain chamfer with a view of gaining more effect. In the mullions and tracery of windows, it is of particularly happy introduction.

To resume briefly the various peculiarities in moldings at the different periods. We observe that the Norman hardly got beyond the alternating round and hollow; that the Early English, extending the example set them by the architects of the Semi-Norman period, hollowed their moldings to an extravagant degree, and that the hollows until then *divided individual members of a group*, but that in Decorated the hollows only *divided the complete*

* It is occasionally, though very rarely, found in vertical groups of moldings, such as door and window jambs. It occurs in Wootton Church, Beds, in the north doorway; in such instances, however, it should rather be considered as a partially developed filleted bowtel. At other times, and more especially in bases, this mold will be found reversed; these, however, are exceptions to the general practice, and can hardly be sanctioned by correct taste.

groups;* that while Early English moldings, from the irregular section of their hollows, present more the appearance of having been drawn “*liberâ manu* ;” Decorated, on the contrary, were remarkable for geometrical precision ; that in Perpendicular, the hollow was converted into the shallow casement, the character of the moldings suffering, in common with all other parts, from the general debasement of Architecture ; and lastly, that the many beautiful moldings, which at various times made their appearance, may all be distinctly traced to a common origin, the bowtel ; thereby clearly showing how little was derived from Classick Antiquity in the formation and gradual perfection of these most lovely adornments of Gothick art.



DOORWAYS.

Norman doorways are generally remarkable for excessive richness and elaborateness in design. On perhaps no other part of their Buildings, did the Architects of those days bestow such care and attention ; they seem to have considered no detail so minute, but that it was capable of receiving further decoration, which was liberally supplied from apparently an unfailing source.† Their usual arrangement consisted of two or more recessed arches, with a corresponding number of shafts in the jambs. A common practice was to place a stone lintel from jamb to jamb, thus forming a square-headed door, with the spandrel under the arch generally enriched with sculpture. Such is the example from St. Mary Magdalen's Church (Section I. Norman, Plate 4). In other examples the lintel is slightly arched to gain a little additional height, or perhaps merely to produce an effect of greater lightness, as in Middleton Stoney Church, Oxfordshire, and Essendine, Rutland. This lintel became afterwards enriched by having carved on its soffit three ornaments like

* Paley's Moldings, p. 34.

† The extraordinary power of invention and facility of execution displayed in the ornaments of the Norman Architects are perfectly surprising. The entire succeeding periods of Gothick Architecture failed to equal them in versatility of design, however superior they may have been in chasteness and elegance of form. Many Norman designs are of such exceeding intricacy, that we must entirely reject the idea of their having been projected on paper or board ; they must be considered as the productions of clever artificers, designed and set out on the stone itself, and possibly considerably modified as the work proceeded.

pellets, as in Weald Church, Essex. This device may possibly have suggested the idea of a triple arch, such as we find in Nately Church, Hants (Section I. Norman, Plate 1), and in Bibery Church, Gloucestershire.

Norman doorways occasionally occur without shafts, the arch moldings being continuous down to the ground, as in Iffley Church, Oxfordshire; a very fine example of this kind occurs in Malmsbury Abbey Church, Wilts, where the wide bowtels which run down the jambs terminate in bases.*

It was a common practice at this period to project that part of the wall through which the doorway was pierced, and hence, from the necessity of protecting this projection, the doorways became gabled, as in Merrington Church, Durham, or Sempringham Church, Lincolnshire, the latter of which is surmounted by a Cross (Section I. Norman, Plate 6); a magnificent example of the same description occurs in St. Germain's Church, Cornwall. Sometimes the projection of the wall was weathered at top in lieu of being gabled, as at Iffley; and in other examples the gable, no longer an object of necessity, was retained as an ornamental accessory. In St. Margaret's, at Cliffe, near Dover, a valuable and interesting Structure, of pure Norman character, is a doorway of this description once recessed, with one set of jamb shafts. The gable is formed by an ornamental string, which, rising from the springing of the arch, terminates in a kind of trefoil.

During the transitional period which occurred between the close of the Norman and the complete establishment of the Early English Architecture, we meet with many extraordinary arrangements in the designs of doorways, as well as in all other parts of the Edifice. Such arrangements are by no means to be adopted, and are merely interesting as showing with what reluctance the old style was finally abandoned, after having been used in the erection of a greater number of magnificent and costly Buildings than were called into existence in any of the subsequent periods of Gothick Architecture.† In the doorway of Little Snoring Church, Norfolk,‡ we find a pointed arch enriched with the chevron, between two circular arches, the outer one being stilted; such a construction would almost indicate that they were fearful of trusting solely to the strength of the newly introduced form of arch. In Northleigh Church, Oxon, the south doorway is pointed and enclosed within a circular arch.§ Transition doorways, however, were sometimes of elegant design and careful workmanship. The west doorway of Orpington Church, Kent (Section I. Semi-Norman,

* Engraved in the Antiquarian Itinerary.

† Between the Conquest and the first year of Henry III. there were founded and re-established 476 abbeys and priories, and 81 alien priories.—Tanner's *Notitia Monastica*.

‡ Britton's *Architectural Antiquities*.

§ *Antiquities of Oxfordshire*, Part II. p. 163.

Plate 1), is an excellent specimen of good proportions, with a delicate trail of dog-tooth and a boldly undercut chevron, which produce a beautiful effect. A benatura, or holy water stoup, has been rather awkwardly introduced against one of the shafts, as shown in the plate. Highly enriched examples of Norman doorways occur in Ketton Church, Rutlandshire, and in the priory church of St. Leonard's, Stamford; this latter has an almost unique arrangement of double jamb shafts. Both these are flanked on either side by blank arches on a somewhat smaller scale, partaking of the character of arcading, yet belonging essentially to the general design.*

Early English doorways are distinguished by their usually great beauty and purity of detail, yet they are by no means so numerous as those of the preceding style; in part, no doubt, owing to the general custom of preserving the older examples. They may be classed under the various heads of shafted, continuous, discontinuous, banded, foliated, and double arched. The large doorways, when shafted, commonly preserve the deeply recessed Norman character; bold and effective arch moldings, often enriched with trails of dog-tooth or flowers, are carried on the detached shafts, which very frequently were of a different stone from that used in the rest of the doorway. Purbeck marble was most generally employed for the purpose, and was in great requisition during the entire duration of this style. The immense consumption of this costly material in Westminster Abbey Church is truly surprising. It probably never was employed without being highly polished; those, therefore, who have seen the restored purbeck piers in the Temple Church, London, can form an idea of what must formerly have been the effect of this magnificent Abbey Church, with its vast masses of dazzling brightness.

A fine example of a shafted doorway from the south aisle of St. Martin's Church, Leicester, is given in Section I. Early English, Plate 23. In this case a beautiful and effective arrangement is obtained by using a double row of shafts, the inner ones being engaged. The moldings of the arch, however, are of a somewhat poor character; and though lying in the rectangular planes, the four orders of which they are composed have lost considerably of the rectangularity of outline so characteristic of that epoch, by being in two instances subdivided into secondary groups. Dunstable Church, Bedfordshire, retains in its west front a magnificent though sadly mutilated example, with five detached shafts, alternating with as many others that are engaged; the arch moldings, as may be imagined, are of very great beauty, and are enriched, among other ornaments, with a very elegant

* The very frequent occurrence, in all parts of the country, of Norman doorways, evidences the estimation in which this feature, however plain in its design, was generally held by the Gothic architects. It appears to have been the custom to spare these interesting works of the early builders, even when all the rest of the Church was taken down to make way for the more magnificent structure in the then prevailing style of building.

variety of the dog-tooth. In the example from Barnwell Church (Appendix, Plate 7), the moldings are of two orders, very rich, with two rows of dog-tooth. Here we may observe a feature, borrowed from the Normans, and extensively used during this style: we refer to the band which occurs midway, and which became a necessary constructive arrangement; for the diameter of the Early English shafts was so small, that without some such contrivance, it would hardly have been possible to have effected a durable joint in their length.

In Felmarsham Church, Bedfordshire, is a fine doorway with detached and engaged jamb shafts, and with an arrangement already noticed in Norman works, namely, an arcade on either side in continuation of the central design.* In the present instance, two trefoiled panels, or *orbs*,† with a quatrefoil above, are enclosed in a pointed arch springing from the same level as the doorway. The interior arrangement of this example will be found illustrated at page 75.

The foiled doorways introduced by the Normans were preserved and still further enriched by the Early English Architects, and during the continuance of this style were of frequent occurrence. In large examples, it was most usual for the first order of moldings only to be foiled, as in the beautiful specimen from Warmington Church (Section I. Early English, Plate 21), a very perfect illustration of a pure Early English doorway, where the jambs are composed of four detached shafts placed in a corresponding number of square recesses, whose arrises are chamfered; and while the two outer chamfers are simply hollowed and terminate in delicately carved trefoiled flowers,‡ the centre one is richly ornamented with dog-tooth.

The arch moldings are all placed on the rectangular planes, and exhibit most of the members characteristic of the style; among others are the pear-shaped or pointed bowtel, and the filleted bowtel. The quasi bases, resting on the capitals and terminating the filleted bowtel of the first order, must not pass unobserved, though they are features belonging more particularly to the succeeding periods. We may notice in the capitals the early appearance of the scroll mold, which is also repeated in the dripstone. Other examples of foiled doorways occur at Merstham Church, Surrey,§ which has one row of shafts, and is enriched with dog-tooth; at Woodford Church, Northamptonshire, a singularly beautiful composition, with the inner order of moldings trefoiled, the others as well as the

* The west front of this interesting Building is well worthy of an attentive examination; it is a beautiful and pure specimen of Early English. Four views and a plan of this Church are given in the *Parish Churches*, Vol. II. p. 96.

† Willis's *Nomenclature*.

‡ See Section I. Early English, Plate 26.

§ *Parish Churches*, Vol. II. p. 99.

dripstone being circular ; and at Higham Ferrars Church, where the priest's doorway has a trefoiled head : in this charming little specimen, the dripstone, as was generally the custom, is simply pointed, and in each of the spandrels which occur between it and the trefoiled head, is sunk a carved rose. Illustrations of these two last-mentioned examples will be found in "The Churches of Northamptonshire." In other foliated specimens all the moldings follow the form of the foliations, as in the doorway in the cloisters of Salisbury Cathedral, which is cinquefoiled ; even in this case the dripstone, in accordance with natural construction, follows the sweep of a pointed arch instead of the outline of the several curves.

The doorways of this period were not always pointed ; under certain restrictions a square-headed form was introduced, and in many instances added an increased charm to the beauty of the general design. Their use was however chiefly confined to the priest's entrance, or to turret and other small doorways. A good example occurs on the south side of the Chancel of Meopham Church, Kent, and is illustrated in Plate 3, of Section I. Early English. Westminster Abbey Church furnishes many instances of its introduction, in the narrow passage which is continued all round the Building in the thickness of the walls. In all these cases a trefoiled appearance is produced, by the lintel being carried on two projecting corbels : this form is generally distinguished as the square-headed trefoil.

During the Early English Architecture the double-arched doorway first made its appearance. This magnificent feature, however, is almost entirely confined in its application to Cathedrals and Conventual Buildings. Though very rarely met with in the smaller Edifices, we are enabled to mention two fine examples : the one at Higham Ferrars, and the other at St. Cross, near Winchester. The former is, in fact, almost two distinct doorways, under one large arched recess or porch ; each having its own distinct jamb molds, which are continuons round a segmental-headed arch : both entrances are richly sculptured with foliage, and between them rises a slender shaft, which in a most elegant manner bursts forth into foliage at the top ; forming a pedestal for a figure, now destroyed. The space between these two arches, and the large circumscribing one, is diapered with circles containing scriptural subjects.* The pseudo porch, within which this double doorway is contained, is very general in the more important Churches in these parts ; we find it in the immediate neighbourhood at Raunds,† and also at Rothwell. The immense weight of the lofty spires, so numerous in the Midland Counties, required proportionably thick walls to sustain them ; and in Northamptonshire, in many instances, advantage has been taken of this thickness to form openings, which, while they present all the appearance of deeply recessed archways, have at the same

* This doorway is very faithfully represented in page 25 of the "Churches of Northamptonshire," a valuable and elegant serial work, now publishing.

† Parish Churches, Vol. II. p 69.

time the convenience of porches ; the soffit being generally diapered (as in Higham Ferrars), or otherwise enriched. The gabled doorway of the Norman period continued a favourite feature in this and the following style : excellent examples of it abound in the middle counties, where, indeed, they are more abundantly met with than elsewhere.*

Loddington Church, Northamptonshire, has a very curious doorway in the west of the tower, the gable of which projects considerably, and is carried on two brackets placed at the springing of the arch. The very beautiful Early English Church at Uffington, in Berkshire, has a good gabled priest's doorway, also a very excellent gabled entrance on the east side of the south transept ; a most unusual position, but which, in this instance, from its approximation to an Altar, appears to have been reserved for the sole use of the priest.

DECORATED DOORWAYS are distinguished from those of the former periods, by the gradual abandonment of detached shafts in their jambs. The gabled doorway from Milton Church (Section I. Decorated, Plate 14), presents a rare example of their retention. In this instance, the Norman method of projecting the jambs has been adopted, without however obtaining the originally intended advantage of increased depth. An apparent effect of projection is obtained for the gable by the set-off in the wall of the tower, which takes place above the string

* This frequent occurrence of certain features in particular districts, to the almost total exclusion of them in others, is a very remarkable fact in the history of English Church Architecture. We can readily conceive that a difference in the supply of building materials may have regulated to a certain extent the designs of Churches erected in parts where such a difference existed ; for instance, that in the stone-bearing counties of Northants, Lincolnshire, Leicestershire, &c., the spire, gracefully tapering, by a bold display of masonick art shall attain a most daring elevation ; while, on the contrary, in the woody districts of the southern counties, the timber and shingle-covered spire will be seen modestly peeping over the woodland scenery. But the distinctions to which we refer had clearly no connection with peculiar facilities or wants ; neither did they any way result from alterations in the style, for so long as it lasted, *that* remained singularly uniform throughout the land : and yet there appears to have been very often a local method of treating one particular part of the Building, the style being identical and the material the same. Let any person observe the characteristic towers of Kent, and compare them with those of Somersetshire : both examples may consist of the same number of parts, both have buttresses, embattled parapets, and a staircase turret, yet how essentially different are the two designs. So also in the arrangement of the eaves of the roofs : in some districts, parapets were invariably constructed to collect and carry away the water ; while in other parts, such as Norfolk and Suffolk, Churches, even of the richest description, were most frequently erected without them. From these facts we would gather, that while the style itself was in the hands of an experienced body of men, and by them jealously guarded and gradually improved ; still, that in the execution of any particular Church, the design of its several details was greatly influenced by that of the neighbouring Cathedral, or most important Conventual Establishment. The beautiful little Church at Skelton favours this supposition, for "there can be little doubt, from the close similarity which many of the details of its Architecture bear to similar parts in the transepts of the Minster (York), that some of the same hands that were employed upon that magnificent building were also concerned in the erection of this more humble but not less beautiful little Church."—Evan Christian's Skelton Church, p. 3.

course. The termination to the gable, now broken away, probably partook of that trefoiled form so common to the gabled buttresses of this period.* In the capitals to the shafts, we may remark the somewhat unusual feature of a double bell. The bases have been very plain, but are so much decayed, that their correct outline can no longer be ascertained. The small bowtel, which originates in the jambs, is carried round the arch, and winds through the intricacies of the panelled gable, adding considerably to its richness and good effect. The tower in which this doorway is placed is a fine specimen of flint work, and in the Plate, the junction of the flint with the dressed stone is shown with minute accuracy. As the Decorated style advanced, crockets and foliage became more frequently and abundantly used in its Architecture; and these, combined with a more studied and harmonious arrangement of moldings, operated considerably in promoting the greater splendour of the doorways. Cley Church, Norfolk, a complete study in itself of the richest and most perfect details of Decorated Gothick, possesses a west doorway of such great magnificence, and with such beautifully and carefully executed parts, that it is probably unequalled by any other occurring in a Church of similar size (Section I. Decorated, Plate 39). In the abrupt, and perhaps awkward, manner in which the arch moldings join on to those of the jamb, we may trace a lingering indication of a past era.† Possibly it was felt that these arch moldings were too minute and delicate for the exposed position of the jamb, which was consequently simply rounded off: but even then, one cannot help wishing that a more perfect and studied junction had been practised. However, the artificers of those days thought otherwise, and it ill becomes us to criticise such minute points, when the whole is so surpassingly elegant.

This single specimen almost comprises in itself all the several characteristicks which occur in doorways of this period. We have the beautifully crocketed and finialled dripstone (ogeed, although the arch is pointed, a peculiarly Decorated feature); the exquisitely carved drip terminations, in this instance, crowned heads (probably indicative of royal benefactors); the well molded arch of two orders, the inner one becoming cinquefoiled, and each foil again trefoiled; the leafy cusps and richly carved spandrels; the quaintly wrought foliage in the capitals, and delicate finish to the chamfers in the jambs; the double-plinthed bases; the stone sill; and last, though not least, the original and richly ornamental ironwork of the door: all these features, each highly worthy of observation, combine together to form a most magnificent and characteristic Decorated doorway.

The stone sill was frequently used during this and the preceding period. An example is given of it in Section I. Decorated, Plate 23, the doorway in Swatton Church, Lincolnshire: and it occurs also in the priest's doorway at Fen Ditton. (See page 51.) In the arch

* See buttresses from Holbeach Church, Section I. Decorated, Plate 17, and also those in Plate 19.

† See arcade from St. Alban's Abbey Church, Section I. Early English, Plate 28.

moldings we may observe, that those which come over the engaged shafts, lie on the rectangular planes, whereas those which are continuous are on the chamfer plane; thus illustrating and strengthening a remark we have already had occasion to make in the chapter on moldings. The beautiful roses which stud the inner soffit, although not very conspicuous in a geometrical drawing, nevertheless add considerably to the general richness, and are themselves well displayed and set off by the elegant moldings over which they are placed. Under the crown of the arch a head occupies the place of a rose.

The Church at North Mimms offers an example of a plainer but equally characteristick doorway. (Section I. Decorated, Plate 25.) We may here again notice, that the arch moldings carried on the engaged shafts, lie on the rectangular planes. They are very beautiful and effective, and the flowers placed in the hollows add not a little to the elegant simplicity of this specimen. The foliage of the capitals is of a very peculiar character, and in its arrangement essentially Decorated, rather twining round the bell than rising up stiffly against it. The bases are extremely plain, and in this respect they agree with those in the Milton doorway; the square return of the dripstone is not the most usual arrangement of this period.

Gabled doorways were still very commonly introduced, occurring, as did those of the previous style, more frequently in the south of Lincolnshire and those counties that immediately surround it, than elsewhere. Ewerby* has a very fine example of this description; it is finialled, though not crocketed, which is a peculiarity observable in many of the details in this Church. In the gable there has been, as at Milton, a small niche for the statue of a saint: it has been blocked up, and is now hardly discernible. The inner order of moldings forms a trefoil arch; the upper foil being slightly ogeed, as at Cley Church. Some very elegant foliage fills up two of the hollows.



EWERBY CHURCH, LINCOLNSHIRE. SOUTH DOORWAY.

At other times the gable was ogeed and richly crocketed and finialled, as in the priest's doorway at Crick Church, Northamptonshire: in this case the head of the doorway is also a flat ogee, and the space between it and the gable is filled with very beautiful foliage. The moldings are continuous and on the chamfer plane. Byfield Church in the same county possesses two very fine examples: that in the south of the Church is ogeed, terminating in a bunch of foliage which supports a niche, and

* For a further description of this beautiful Building, see *Parish Churches*, Vol. II. p. 77.

is flanked by pinnacles, crocketed and finialled; the other, at the west, is of the same description, but without the niche.

Doorways with continuous moldings occur very frequently in Buildings of this period, though the effect is rarely satisfactory; the absence of shafts is severely felt, for without them the springing of the arch, which should always be well defined, appears undetermined.

The doorway from Holbeach Church (Section I. Decorated, Plate 10) is a good plain example, with a door of the same date very rich and perfect. The framing, and the "setting out" of its tracery will be found fully explained in the plate. The jamb shafts have molded caps and bases: these latter are of a very unusual character, or perhaps, rather of no particular character. It is curious to observe, even in works of considerable richness, how frequently the bases were neglected and left very plain, as in the examples from North Mimms and Milton; or presented some extraordinary anomaly, as in the present instance; or seemed to lack a sufficient projection, as in the doorway from Heckington. In truth, good moldings in any position were much more rare in this style than in the preceding one: in many cases simple chamfers were used throughout the entire work. In the arched monuments and in the smaller details of the Church, such as the sedilia and piscina, we are more likely to meet with minute and exquisitely wrought moldings. The doorway from Heckington, referred to above, and illustrated in Plate 23 of Section I. Decorated, is a beautiful example, with three rows of shafts having foliated caps, and with excellent arch moldings. The finial which terminates the dripstone is not quite perfect, and judging from its present mutilated condition, we should imagine that it had had another leaf on either side lapping back. Here we may once more remark, that shafts being used in the jambs, the arch molds lie on the rectangular planes.


Circular-headed doorways were occasionally introduced, but must be considered rather as instances of the caprice of the builders, than as features appertaining to this style. A very rich example occurs in Badgeworth Church, Gloucestershire; the moldings are continuous, of extraordinary merit, and profusely studded with ball flower.*

Towards the close of the Decorated period, the label over the pointed arch, and spandrels filled with rich carving, gradually gained ground. Worstead Church, Norfolk,† and Deopham in the same county, both present instances of the introduction of this new feature: in the latter the label is embattled. In the doorways to turret staircases, almost

* A window from this Church is illustrated in Section I. Decorated, Plate 38, the moldings of which closely resemble those of the doorway; in fact, the two dripstones are identical. A plan and two views of the entire Building are given in the *Parish Churches*, Vol. II. p. 67.

† *Parish Churches*, Vol. I. p. 35.

any shaped arch was equally applicable ; and accordingly we find them sometimes pointed, or sometimes ogeed, now square-headed, or again, as in the example from Aldwinkle Church,



ALDWINKLE CHURCH,
NORTHAMPTONSHIRE.

partaking of the character of all. The priests' doorways are frequently particularly interesting : those already mentioned, in the Churches of Crick and Heckington, are beautiful and rich examples ; that at Oadby, Leicestershire, has a tracced head ; and the one in Brandon Church, Norfolk (Section I. Decorated, Plate 12), is commendable for its simple elegance. The example at Sutton at Hone, Kent (Section I. Decorated, Plate 1), is an instance of continuous moldings occurring on the rectangular planes. A solitary case like this, however, can hardly militate against, but should rather be considered as an exception from, a general rule which, for the greater convenience of study, we would attempt to establish, without at all presuming to put it forth as the one by which the masters of old worked.

Indeed, we cannot readily conceive that such rules as these were then wanting, for they are but the necessary results of that natural construction which is so remarkably displayed in all their works. If shafts are used, as a consequence almost, they would be placed in square recesses, and hence lie on the rectangular planes ; and their capitals, projecting from these planes, become naturally so grouped as only to be consistently adopted for arch molds that also lie in similar planes. At the present day, when the student in Mediæval Architecture has before him such exquisite specimens of the art in its matured phase—when he can turn at once to the truly graceful compositions of the Edwardian period, it is perhaps mainly as a matter of curious inquiry that his mind is directed to the minute steps by which such excellence was gradually accomplished ; and yet the investigation must assuredly enable him to arrive at a more refined appreciation of its eminent beauties, while it will also forcibly illustrate the great advantage resulting from close application to the study—it will show how master minds, through many generations, continued to labour in the same field, each generation receiving with reverence the bequest of its predecessor, and invariably striving to advance it on the road to perfection. This research may be the more useful, inasmuch as Gothick Architecture, at present at any rate, can scarcely be reduced to precise laws—its spirit soars above rule—yet often when it may wear the appearance of caprice, close investigation will prove it to have been guided by purest taste : it must be studied in the spirit in which it was conceived, and pursued with ardour and constancy. The ancient architects, devoting the energies of their powerful minds but to *one style* of building, were every way qualified to develop the manifold graces it is capable of, and thus render it more and more worthy of its high purpose. Yet, however great the excellence thereby attainable, it can hardly *now* be of frequent occurrence that an architect should devote his sole and undivided attention to the

study and advancement of one particular style out of the many which are in full practice, and each of which has its ardent votaries: the more especially when we consider (and the consideration, after all, is of some weight) how disproportionate would be the encouragement he would probably meet with. But be that as it may, as regards Gothick Architecture, the day is surely coming when it will no longer be studied as a dead language, as an art which a gulf of nearly four centuries divides from us: once well understood (it is already appreciated), its admirers will boldly strike out anew the track in which our ancestors laboured; and, armed with their principles, will advance it to a climax of beauty unknown even to them. To return to the subject more immediately under our consideration:

IN PERPENDICULAR DOORWAYS, the constant use of the label characteristically distinguishes them from those of the preceding styles, though, as we have already observed, this feature may occasionally be found in Decorated work; in Perpendicular, however, its appearance is in keeping with the then prevailing fashion, which delighted in the contrast of horizontal and vertical lines.

In the example from St. Alban's Abbey Church (Section I. Perpendicular, Plate 1), the entrance into the south aisle from the cloisters, we find combined many beauties and excellencies. The interior elevation, which is the one represented in the plate, is flanked by two niches with pedestals, the whole forming a very grand and imposing composition, adapted of course only to a very large Church; and in so far, perhaps, not consistently occupying a place in the present work, were it not for the many valuable points which it possesses, peculiar to the doorways of this period. The very beautiful effect produced by the double-cusped arch, carried in front of and distinct from, the first order of moldings, may be observed in many examples of a similar date. In the present instance, the terminations of all the primary cusps are broken off, with the exception of one representing a lion's head. The singularly beautiful crowning ornament exhibits a very early specimen of that distinguishing Perpendicular decoration, the strawberry leaf, combined with much that belonged to the stage of art which had just closed: on its geometrical formation, which is exhibited in the plate, we have already commented in page 46. The door itself is a very rich and well preserved specimen, and will be found illustrated more at large in Section II. Woodwork. Plate 4. The small roundlets with which it is studded seem to have been suggested by the ball flower of the Decorated era. The arms of England and those of the Abbey are placed in the spandrels.

The doorway from Coltishall Church (Section I. Perpendicular, Plate 20) is a very good type of the general arrangement of the period at which we have now arrived. It is placed at the west end of the Church and in the tower, and exhibits the combination of both label and dripstone; the horizontal part of the former is continued through, and is carried round the

tower as a string.* Above it is placed a very rich band of flint and stonework, consisting of shields in octofoiled eircles, alternated with the crowned I for St. John the Evangelist. The same device occurs in the base moldings of the tower, and his symbol, the Eagle, is carved in the spandrels of the door. A second stringcourse eneloses the band of circles, and immediately above is a three-light window. This arrangement had then become the prevailing fashion; a west doorway and window might almost be considered as forming one design; we meet with an early instance of it in the Decorated tower of Worstead Church, Norfolk.† The jamb molds of the Coltishall doorway are on the chamfer plane, and consist of an exaggerated filleted bowtel between two casements, leaving two wide, plain chamfers, which in the arch have a kind of wave mold sunk from the face.



TOWCESTER CHURCH, NORTHAMPTONSHIRE.

The west doorway in the tower of Towcester Church, Northamptonshire, is a singularly rich and beautiful specimen of this style. It is very deeply recessed, and has a crocketed and finialled dripstone within a group of moldings which follow the outline of the label. The slender octagonal bowtel, rising from the ground and at top spreading into a small pedestal for the reception of a statue protected by a crocketed canopy, is a rather unusual but beautiful feature. The moldings all lie on the chamfer plane, into which they die at the bottom.

In the tower of Lavenham Church, Suffolk (Section I. Perpendicular, Plate 6), is a magnificent though very late specimen. Even in this instance, the two-centred arch is still retained, with the addition of an ogeed dripstone beautifully crocketed, which, interpenetrating the stringcourse, appears again on the upper part, and was originally terminated with a finial. The moldings are of very poor character: in the desire for richness of appearance, the usually wide, and sometimes effective casement has been abandoned, and

groups of moldings have been formed; but by their not lying in either of the usual planes,

* This arrangement was a very common practice, and is also observable in windows; see window in north Chapel of Barnwood Church, Gloucestershire, *Parish Churches*, Vol. II. p. 71.

† *Parish Churches*, Vol. I. p. 35.

they produce an effect at once confused and unsatisfactory. In the arch head, especially, the various groups are composed of very minute members, divided by large and plain hollows; very different from the previous and purer practice, when all was so beautifully blended together. The peculiar shape of the middle shaft in the jamb should be noticed; many instances of it may be found in Perpendicular work, and it would appear to be a corruption of the Decorated filleted shaft. All the caps have double bells, but are otherwise as irregular in their construction as the moldings of the arch and jambs. They are all octagonal, and in the principal ones, small square flowers of four leaves occupy the place of the beautiful foliage of former times. In the bases we may notice the then prevalent fashion of their being exceedingly stilted; the outer base is exaggerated to such an extent, as to be nearly equal to the shaft in height. The buttresses and shafts which flank the doorway, however elegant they may appear at first sight, must be considered as instances of a debased taste, which sought more after meretricious effect than correct and consistent decoration. Still the design is so rich and attractive, and the base moldings and the buttresses to the tower are all in such excellent keeping, that we are induced to overlook the imperfections of the details, in our admiration of the composition as a whole. The door itself has been a rich and beautiful design, but is now so much decayed, that the moldings and smaller portions of the tracery are no longer discernible. The flint work of the tower is remarkably well worked; a portion of it is shown in the Plate.

Islip Church, Northamptonshire, possesses a very good illustration of a small Perpendicular doorway. There, as at Coltishall, we find both label and dripstone; the



SHORNE CHURCH, KENT.

latter ogeed, and both uniting and carried on small shafts, resting on the base moldings of

the tower. Some well carved tracery fills up the span-drels, which, with a deeply sunk casement, produces a fine, bold effect. The string round the tower is lowered, to allow of the usual accompaniment of a window: altogether this is a simple yet pleasing example. The west doorway of Shorne Church, Kent, is well adapted for a plain village Church. It is flanked by buttresses, which are judiciously



ISLIP CHURCH, NORTHAMPTONSHIRE.

introduced into the composition; and in either jamb is a shaft carrying a single group of moldings. It has no dripstone nor label: and this leads us to notice a peculiarity, which we may also observe in Basingstoke Church (Section I. Perpendicular, Plate 3), and in Chesham Church (Plate 17), namely, that in some cases, especially in the more advanced and fully established Perpendicular, the spandrels to the doorways form an essential part of the composition, and would exist whether a label were thrown over them or not; whereas in



CRANSLEY CHURCH, NORTHAMPTONSHIRE.

others, and principally the earlier examples, the spandrel is the immediate result of using both label and dripstone, as in the doorway from Coltishall; and it would appear probable that on the dripstone becoming gradually obsolete, the spandrel assumed its position as an actual portion of the doorway, and was enclosed by the outer molding of the jamb. Continuous moldings were now very frequent, but even in small examples they were very deficient in beauty; and when employed on a large scale, as at Potterspury Church, Northamptonshire, the effect was altogether poor and unsatisfactory.

Perpendicular priest's doorways were usually plain and uninteresting. The example, however,



LEIS CHURCH, LEICESTERSHIRE.

In the arrangement of these doorways we have frequent opportunities of remarking instances of that unbounded freedom, so characteristic of this style of building. Does a window occur just where it was wished to have placed a doorway,—with the utmost boldness they are both incorporated into one design; or, does a buttress present an apparently insurmountable obstacle to the doorway's being placed in a particular position,—it is at once made to expand on either side, and by a clever contrivance the desired doorway is pierced through it; or again, we may have to admire the ingenuity with which the difficulty has been overcome, of both erecting a buttress, and adding a porch to an already existing

doorway. Throughout every minutia of Gothick Architecture, we shall ever find that construction and design go hand in hand,



TRUNCH CHURCH, NORFOLK.

and that anything actually required by the former, instead of being concealed, is immediately and gracefully made subservient to the beauty of the latter. The priest's doorway in Merstham Church, Surrey, exhibits a graceful combination of the jambs




GRUNDISBURGH CHURCH, SUFFOLK.

are altogether brought forward from the face of the wall ; the arrangement of the dripstone is also commendable.



MERSTHAM CHURCH, SURREY.

The interior of the doorways frequently shows how a necessary constructive feature is converted into a highly ornamental one. In an arched entrance, where the door is placed considerably nearer the outer than the inner face of the wall, it becomes necessary to stilt or give a different form to the inner arch, so as to allow to the door opening ; hence the constant use of the segmental pointed arches on the inside of doorways. In Section I. Perpendicular, Plate 7, is shown the very elegant arrangement of the inner arch of the doorway in the tower of Lavenham Church, the soffit of which is richly panelled with quatrefoils. The Early English archways in Felmarsham Church* are also very graceful, with slender shafts carrying a beautiful group of moldings.



FELMARSHAM CHURCH, BEDFORDSHIRE.

* See Parish Churches, Vol. II. p. 95.

Trumpington Church, Cambridgeshire,* has a singularly fine interior arch, with a hoodmold and bold moldings carried, as in Felmarsham Church, on slender shafts with molded capitals.

The priest's doorway in Higham Ferrars Church presents a good example of internal arrangement; a few moldings on the face of the arch, with the stringcourse continuing as a hoodmold over it, are all that are required to produce a very satisfactory effect. In Northamptonshire, Lincolnshire, and other counties, where stone spires abound, a small opening is most usually contrived in one of the faces of the spire to give access to the parapet; these openings are generally well managed, and occasionally, as in Weekley Church, are made ornamental features.



HIGHAM FERRARS CHURCH, NORTHAMPTONSHIRE.



WEEKLEY CHURCH,
NORTHAMPTONSHIRE.


PIERS AND ARCHES.

CHANCEL ARCHES.—With such rare exceptions as in Ewerby, Lincolnshire; Raunds and Higham Ferrars, Northamptonshire, and some few other Churches, it was an universal practice to mark the termination of the nave and the commencement of the Chancel, by an arch thrown across from one wall to the other. In early Norman Buildings this separation is occasionally indicated by a triplet of arches, an arrangement very frequently met with in the village Churches of Sussex, as in Piecombe Church, and Ovingdean, near Brighton. Though sometimes occurring of extreme simplicity, as in Keymer Church, Sussex, the Chancel arch of this period was in general highly enriched; those in the Churches of Adel and Bubwith, in Yorkshire, are beautiful examples. The Semi-Norman architects followed closely in the footsteps of their predecessors; the substitution of a pointed for a circular arch being the most important change which they effected. In the Church of Codford St. Mary is a good instance of a transition Chancel arch (Section I. Semi-Norman, Plate 5): the outer shafts are slightly pointed on plan, and the cap, band and base moldings are considerably undercut; on the east side, on the contrary, the shaft is

* An excellent engraving of the interior of this doorway is given in "The Churches of Cambridgeshire," p. 53.

simply circular, and the arch recessed but not molded. It is said that during some repairs [that have recently taken place, it was discovered that the outer portion of the arch had been remodelled, and converted from Norman into Semi-Norman by pointing it, and making the other members somewhat to partake of the new style then coming into vogue; but that the inner or east side had been left almost in its original state. Certainly the east elevation is very plain and simple, compared with the west, but this will be found to be almost always the case in Norman work; the parts that would more immediately strike the eye are very richly ornamented, while the others are left comparatively unadorned. This we find to be particularly the case with Chancel and nave arches; in New Shoreham Church, for instance, the arches dividing the Chancel from the aisles are richly molded and elaborately carved with foliage on the sides which open into the Chancel, while those sides which face the Chancel aisles are almost without moldings, and the foliage is altogether omitted.* That such a practice was due to some received idea of beauty in composition, and not to that contemptible spirit which would seek only to decorate those portions more immediately in sight, we may gather from the extreme care with which every part of the Building was finished. In this very Church of New Shoreham, the window which lights the space between the roof and the vaulting over the Chancel aisle and which naturally could hardly ever be seen, is nevertheless richly ornamented inside with moldings and dog-tooth, while (curiously enough) outside, the opening is perfectly plain; being simply once recessed. (See Appendix, Plate 1, Fig. 6.)


A favourite and elegant Early English practice, was to carry the inner rim of the Chancel arch on Corbels, the other moldings being most frequently continued down to the ground. Such is the arrangement at Acton Bunnell;† a small foliated shaft carries the inner order of moldings, while the outer order



* The arches in Felmarsham Church are also richly molded towards the nave, while the sides in the aisles are simply chamfered; see *Parish Churches*, Vol. II. p. 95.

† We are indebted to the kindness of C. Hansom, Esq., Architect, for the use of some very accurately measured drawings of this excellent example.

dies into a broad chamfer, which is continued down to the ground. The Chancel arch in Barnwell Church, Northamptonshire, is similarly managed, but with a corbel of far greater



BARNWELL CHURCH, NORTHAMPTONSHIRE.

beauty ; the shafts are detached and carried on a group of notch-heads, which are singularly effective. In Warmington Church, in the same county, slender corbelled shafts, with foliated caps of exquisite workmanship, are also introduced ; and indeed, in this instance, form quite a peculiar feature in the internal decoration of the Church, for they are employed to support the springers of the groined roof. In Clymping Church, Sussex,* the inner order is carried on a corbel, and the jambs of the archway have small nook shafts, indicative of their very recent emancipation from Norman rule. In Whitwell Church, Rutlandshire, the arrangement of the Chancel arch is yet more simple, the corbels being dispensed with, and the inner moldings dying into the jambs on either side.†

In other instances, and more particularly as the style advanced, the arch was carried on a regular cluster of columns, properly capped and based, as in Skelton Church, Yorkshire:‡ a half octagonal pier is a very ordinary arrangement, which continued in practice until the termination of the Decorated period. This, a simple and always effective method

of treating the Chancel arch, is well illustrated in the example from Long Stanton Church, Cambridgeshire.§ Preston Church, Sussex, a pure and simple little Early English Building, has a very good and characteristick arch. (Section I. Early English, Plate 5.)

It is not a little singular, however, that in very rich and splendid Churches, such an important feature as the Chancel arch should so frequently have been left devoid of ornament. The arch in Raunds Church, Northamptonshire, a Decorated addition to

* See interior of this Church in *Parish Churches*, Vol. II. p. 75.

† See view of the Chancel arch, in Vol. II. of *Parish Churches*, p. 85.

‡ Hartlepool Church, Durham, has a richly molded Chancel arch, carried on beautifully clustered shafts, having very early foliated caps with square headmolds. See *Billing's Durham*.

§ *Parish Churches*, Vol. I. p. 33.


the Building, is ornamented with a double row of ball flower, but this forms quite an exception to the general rule: a few simple moldings, or even a recessed and chamfered arch, is far more frequently met with. Even the Perpendicular examples do not exhibit any particular alteration in the mode of treatment: the moldings and details were of course accommodated to the new fashion, but the Chancel arch itself did not assume more importance than in the preceding style.

To resume, then, we may remark, that in most cases the Norman Chancel arch was distinguished by its quaint ornaments and rich sculpture, and was very usually carried on shafts in recessed jambs; that the Early English was generally, and especially if the inner moldings were carried on corbels, of considerable elegance, though carved ornaments were then but very rarely introduced; while Decorated and Perpendicular arches were of great simplicity, with the moldings either supported on semi-piers or continuous down to the ground. It is not improbable that the gradual introduction of rich and costly screens of wood induced the builders to transfer to these latter the decorations which, had they not existed, would have been lavished on the former. As regards their proportions, it is with the Chancel arch, as with those of the nave, the belfry, and all the other arches in the Church, scarcely possible to lay down any positive rules: every variety of size and shape may be met with, and in each case it appears to have been mainly influenced by other parts of the Structure. Besides, we can easily conceive that many circumstances would influence its proportions: an unusually handsome east window or roof would naturally induce the builder to heighten his arch; or, when it was intended, as was very frequently the case, to paint the Last Judgment over the west face, he possibly might be inclined to lower it, so as to give a wider field for the display of the artist's talent. In some Churches the height of the Chancel arch piers corresponds with those of the nave, in which case the moldings are generally identical, as in Weekley Church, Northamptonshire; at other times, and much more frequently, the springing of the Chancel arch is quite independent of any other.

Norman piers were generally circular or octagonal, and in the earlier Buildings, of great size and of massive proportions. Such are the octagonal piers at St. Nicholas, Harbledown, Kent: those in Sandridge Church, Herts, also octagonal, are of much better and more graceful outline. In Polstead Church,* Suffolk, we find the pier, which is rather a late specimen, subdivided into parts, and considerable effect produced by the introduction of engaged nook shafts. Early English piers, octagonal and circular, are frequently, as in Felmarsham, counterchanged in the same Building. Other examples are of extraordinary beauty, with complex arrangement of shafts. At Boxgrove Church,

* See Appendix, Plate 6.

Sussex,* those on the north are most daringly detached from the central pier, while on the south small channels have been sunk for their reception: in both cases Purbeck marble, richly polished, is the material employed. Eaton Bray Church, Bedfordshire,



EATON BRAY, BEDFORDSHIRE

furnishes an example of a somewhat similar grouping, and has well carved foliated caps. At St. Alban's, the piers are magnificently clustered, with four detached and twelve engaged shafts. Even in Early English work, however, the shafts were not always detached: in St. Martin's, Leicester,† we find four small shafts engaged, between four other and larger ones, which we may observe are filleted. This fillet, applied to the face of the principal shafts, became an established feature in Decorated piers. We may notice it

in the examples from Bottisham and Trumpington (Plates 16 and 27), and elsewhere. Morton Church, Lincolnshire (Plate 21), has a simple and elegant pier, the plan being produced by four half circles applied to the several sides of a square. All the caps in this Church are beautifully foliated.

The occasional absence of molded work in this style frequently extended itself to the piers, which were simply octagonal, and carried plain chamfered arches, even in Buildings whose details in other respects testify the care that was bestowed upon them. The exceeding, yet beautiful, simplicity of the piers and arches in a Decorated Church, were little in accordance with the taste of the Perpendicular Architects, who consequently very rarely copied them, though it can scarcely be allowed that they replaced them by a more appropriate substitute. A great sameness pervades the piers of this period: the most usual form is shown in Section I. Perpendicular, Plate 14, a pier from Lindfield Church, Sussex. Afterwards, and especially towards the close of Gothick Architecture, the plan assumed more of a diamond shape, by being made considerably wider from north to south than from east to west, as in Lavenham Church, Suffolk. As we have already had occasion to observe, a peculiar characteristick of Perpendicular piers, and one which distinguishes them from all previous examples, consists in the moldings of which they are composed being partly continuous from the arch.

ARCADES were generally employed as decorative features to the lower parts of walls; their use was principally confined to the interior, but they are not very commonly met with in Parish Churches. The Norman Architects, however, delighted in extensively introducing them in their works, and frequently enriched with them the outer walls of their towers. In St. Alban's, a small cloister formerly connecting the Church with the

* See Appendix, Plate 6.

Abbey buildings, is enriched with an arcade, the details of which are very carefully wrought, with capitals remarkably quaint and variously carved. Two examples of Semi-Norman character, from New Shoreham Church, are given in Section I. Semi-Norman, Plate 2. The Chancel of Stone Church, Kent, a deservedly well-known Early English Structure, has a very beautiful arcade both on the north and south sides, which, in this case, appears to answer the purpose of the customary wooden stalls that were afterwards used; for it is placed immediately over a stone bench table, of a convenient height for a seat. In Westminster Abbey Church (see page 8) the arcade occupies a similar position with regard to the bench table. The example from St. Alban's Abbey Church, given in Section I. Early English, Plate 28, is rather late in the style; it has very beautiful moldings, and is highly effective. Polebrook Church, Northamptonshire, contains some very good arcading in the north transept; other instances of its application internally in Churches of this date will be found at Histon Church, Cambridgeshire, and Thurlby, Lincolnshire. In the Chancel of Merstham Church, Surrey, a capital and a portion of an arch may yet be traced, built up with the Perpendicular additions and alterations. At All Saints Church, Stamford, an Early English arcade is carried externally round the greater part of the Church. Arcading was frequently a decorative adjunct to the towers of this period, as at St. Mary's, Stamford; Ketton, Rutlandshire; and Raunds, Northants. In Decorated architecture the arcade was generally omitted, and was at last entirely superseded by the introduction of panelling, which rapidly increased during the Perpendicular era, and was eagerly introduced in the Buildings then erecting. There was no portion of the wall but what was considered susceptible of receiving this new enrichment: buttresses, parapets, soffits and jambs of doorways, windows, and archways, and especially basement moldings, are found profusely ornamented with it. The Abbot's tower at Evesham is completely covered with panelling, from the basement moldings to the parapet. Tichmarsh Church, Northamptonshire, has a double row of panels, very rich and effective. Those from Lavenham Church, given in Plate 8 of Perpendicular, are of a very unusual character, and in the centres of several of them are the initials and mark of the clothier, Thomas Spring, the munificent founder of this noble Structure. In the flint work to which we have already referred, foliated panels are abundantly introduced; or in their stead we find, as at Coltishall and Hunworth Churches, in Norfolk, the crowned initial letter of the patron saint; or a cypher, as in Kenninghall Church.

During the Early English and Decorated periods, a beautiful method of diapering plain surfaces was very prevalent. This diaper usually consisted of a small flower or geometrical pattern. We may notice its appearance even in Norman work, as over the window in

Stourbridge Chapel (Appendix, Plate I. Fig. 2), and in the gable of the west doorway of St. Margaret's at Cliffe; but it is in Early English Buildings, such as Chichester Cathedral and Westminster Abbey Church, that we may first remark the extensive use of this enrichment: the last named Edifice contains many beautiful and varied designs. In Dunstable Church it is used externally over the doorway; Beverley Minster may also be mentioned as an instance of its external application. Four Early English examples are given in Plate 19 of Section I., and four of Decorated date in Plate 24. The elegant and well known specimen at Canterbury is illustrated in Professor Willis's History of the Cathedral.*

BUTTRESSES are distinguishing, as they are also important, members in Gothick Architecture. They do not occur very frequently in Norman work, the most usual resemblance to a

buttress being a narrow strip of wall, which is generally flush with the corbel table; so that in fact it was the wall that was made to recess rather than the buttress to project. The tower of St. Peter's Church, Northampton, has some very curious angle buttresses, somewhat resembling on plan a cluster of three engaged shafts; they diminish gradually in stages. At the east end of the Chancel and under the window is another small Norman buttress, semi-circular on plan, with a conical cap. The Semi-Norman tower of Clymping Church† has some good examples with weathered heads; they are divided midway with a string, but have the same projection above as below.



ST. MARGARET'S, LEICESTER.

In the small Early English village Structures, the buttresses still remained but secondary features in the design; their projection was very slight, and they were rarely divided into more than two stages. Very frequently their heads were gabled, as at Little Wenham Church, Suffolk (Section I. Early English, Plate 14); or a small gablet rose from the weathering, sometimes enriched with cusping, as in Raydon Church, Suffolk (see the same Plate); or with incipient tracery, as in Achurch, Northamptonshire. A curious variety occurs in Raydon Church, on the north side of the Chancel; it is triangular on plan with a sloping head. (Also illustrated in the above Plate.) In larger Buildings of the same date, we find the buttresses more fully developed. Good examples occur in Felmarsham‡ Church; in the Chancel they have a very slight projection, but at the west end they stand out boldly, and are well proportioned. St.

* Also beautifully engraved in Bloxam's admirable Principles of Gothick Architecture.

† See Section I. Semi-Norman, Plate 5, and Parish Churches, Vol. II. p. 75.)

‡ Parish Churches, Vol. II. p. 95.

Margaret's, Leicester, has a fine arrangement of buttresses : those on the north side are gabled, on the south they are simply weathered ; in the latter an elegant peculiarity may be observed in the leafy terminations of the lower set-offs. It was during the Decorated era that buttresses reached to their fullest development of beauty : they were then always worked in stages, frequently had gabled heads, and were enriched with niches, tracery, &c. Very excellent examples, however, are frequently met with, without the slightest attempt at decoration : deriving all their beauty from their graceful proportions. Such are those in Pytchley Church, Northamptonshire. Fen Ditton Church, Cambridgeshire (Section I. Decorated, Plate 17), has also some plain yet very good specimens of about the same date : in this instance the arrises throughout




REDGRAVE CHURCH, SUFFOLK.

are chamfered ; a practice which prevailed during the preceding period, yet perhaps not to the extent that is generally imagined, at least as applied to village Churches. In the same plate is figured a buttress from Holbeach Church ; a large and imposing Decorated Structure, in which the buttresses, partaking of the magnificence of the other parts, are gabled and terminate in a

kind of trefoiled ridge. In Bottisham Church, Cambridgeshire (Section I. Decorated, Plate 19), they are also similarly finished, with the addition of beautifully molded chamfers at the angles, and a trefoiled panel on the face. Dronfield Church, Derbyshire, has some magnificent examples in the Chancel, worked in two stages with both set-offs gabled, and enriched with tracery. In Debenham Church, Suffolk (Section I. Decorated, Plate 19), is an instance of a buttress having a niche with an ogeed and trefoiled head, beautifully finialled, and flanked by diminutive crocketed buttresses. Another very interesting specimen occurs

at the east of All Saints Church, Colchester. At Towcester Church, Northants, the niche is placed on the side instead of the face. The buttresses from Redgrave Church, Suffolk, are of



PYTCHELEY CHURCH, NORTHAMPTONSHIRE.

perfect beauty ; very lofty, and rising in graduated stages, they terminate in gables with trefoiled ridges, and have very elegant foliated niches in the upper stages, with pedestals exquisitely carved. It is during this period (the Decorated) that we may first notice the habitual practice of placing the corner buttresses at an angle of 45° with the walls. This position however has been considered, without sufficient grounds, as a distinctive peculiarity of Decorated work ; whereas an inspection of some of the finest and purest specimens, will show that it was by no means the invariable practice. In tower buttresses we sometimes find both kinds used conjointly in the same group : those placed at an angle of 45° being uppermost ; partly dying into the others that are at right angles with the tower, and partly corbelled out or carried on small cusped and gabled squinces ; as in the rich examples from St. Margaret's, Leicester.



BESTHORPE CHURCH,
NORFOLK.

upper part. In the same plate is engraved a buttress from New Walsingham Church, it is of three stages, though very much lower than that from Ryall Church ; the small gablet on the lower set-off, and the diminished width of the upper one, give it a peculiar and pleasing character. The example from St. Mary's, Stratford (Section I. Perpendicular, Plate 11), becomes interesting, from the knowledge we have of the date of its erection (1430), it being stated in an inscription, which is carried round the basement moldings. It is exceedingly simple in outline, and derives its claim to beauty principally from the elaborate flint ornaments with which it is enriched, in common with the whole of the north aisle. The initials of the two founders, Edward and Alice Mors, and the mark of the husband's trade, occur on shields in various parts of the design. Blakeney Church, Norfolk, has also some good buttresses, worked out of flint and stone with panelled faces : those, however, in Lavenham Church far exceed all previously mentioned in richness and elaborate detail. (Section I. Perpendicular, Plate 12.) They are entirely of dressed stone, with faces variously panelled, and are in excellent keeping with the other portions of this magnificent Structure. The armorial



BLAKENEY CHURCH, NORFOLK.

bearings of the Veres, Earls of Oxford, and generous benefactors to the Church, appear on the buttresses.

Pinnales were sparingly used during the Decorated period, and then do not appear to belong so much to the design of the entire Building, as to particular parts of it. For instance, we frequently find an aisle, as at Rickenhall Church, Suffolk,* highly enriched with pinnaled buttresses, while the Chancel is of excessive plainness; or again, the Chancel may have been enriched with pinnales, as in Over Claybrook, Leicestershire, without the other portions of the Church displaying a similar degree of enrichment; so that we may conclude that these elegant features were not usually introduced into the architecture of the ordinary parish Church, until the full establishment of the Perpendicular, when they became of frequent occurrence. Staunton Harold, Leicestershire, is thus enriched with them. In Ayston Church,* Rutlandshire, pinnales occur at the angles of the Chancel only. In Knowle Chapel, Warwickshire, they rise out of the buttresses to the Chancel and aisles, and also out of the embattled parapet to the clearstory. Louth Church, Lincolnshire, is similarly enriched.

The tower Buttresses to the Early English Churches were generally simple and elegant; at Etton,* Northamptonshire, they are of three stages, the upper one dying into the spire table. At Stanwick,* in the same county, they appear rather as ornamental accessories, are very low, and are profiled off on the sides, as well as in front, in a very curious and unusual manner; while at Achurch they only rise to the second stage of the tower. Again, some towers, even of the Decorated period, have no buttresses at all; such are Southfleet,* Kent; and Barnwell, Northamptonshire; while in other, and far more frequent cases, the buttresses in towers, such as Fleet,* Donington,* Ewerby,* Worstead, and St. Mary, Redcliffe, have never been surpassed for magnificence and grandeur of outline. In all these instances the buttresses are placed at right angles with the walls.

Perpendicular towers are mainly indebted for their grandeur to the noble proportions of their buttresses, most usually terminating in richly crocketed pinnales: very fine examples occur in the Churches of Bishop's Lydeard,* Beaminster (Dorset), Ludlow (Salop), the Holy Trinity, Coventry; St. Mary's, Taunton; Louth, and St. George's, Doncaster. In Martham Church* they are excellently proportioned, but terminate below the parapet with a simple weathered table. In Deopham Church* they are in six stages, and finished in hexagonal turrets, embattled and panelled.

The PARAPET, as we have elsewhere remarked, is as frequent in some parts, as it is rare in others. The Norman Architects seldom introduced it into their works; they

* See engravings and plans of these several Churches in Vols. I. and II. of the Parish Churches.

seem to have preferred the corbel table with dripping eaves; very possibly, however, many Norman parapets, becoming ruinous owing to their exposed situation, have been replaced by others in the style in vogue at the time the restoration occurred. The tower of Clymping Church* has a plain parapet, apparently original; it is chamfered at top, and carried on a row of corbels. In its complete state, the parapet may be divided into three distinct parts: the string or cornice, the parapet wall, and the coping. Polebrook Church, Northants, has some very good examples of Early English character; at Sutterton, Lincolnshire, the cornice is filled with a variety of ornaments, notch heads, dog-tooth, hearts, &c.; Evington, in Leicestershire (Section I. Decorated, Plate 37), has one over the north aisle of a little later date, where the cornice is similarly enriched, but with the parapet wall carved with a succession of sunk trefoils, filled with leaves or flowers in low relief. In Decorated examples, the parapet wall is frequently pierced with quatrefoils, trefoils, or some flowing tracery, as in Heckington Church (Plate 37). In this style, also, we may first notice the positive introduction of battlements, though it is not at all unlikely that they were used in Churches of an earlier period. Higham Ferrars exhibits some examples of very early date. The embattled parapet became almost an universal feature with the Perpendicular architects: a difference that may be noticed between the earlier and later examples is, that the coping in the former is only employed in its legitimate and horizontal position, whereas subsequently it was made continuous, and carried down the sides of the battlement. In the two Churches of Hingham* and Martham,* in Norfolk, the distinctive peculiarities of the Decorated and Perpendicular parapet are well contrasted. In St. Mary's, Stratford, erected in 1430, the legitimate use of the coping is still held in view; in Lavenham Church, on the contrary, it is continuous; the battlements, also, in the latter, are pierced with a four-centered arch; the opening thus formed being partly filled up with a large leaf rising upwards, and the intermediate spaces enriched with boldly carved foliage in square panels.


By far the richest specimens of Perpendicular parapets, however, are to be met with in the towers of the period. Bishop's Lydeard* is very fine, with a row of quatrefoils, above which the embattlement rises; in Badgeworth Church* it is of a simpler, yet still pleasing, character. The parapet in Martham Church* exhibits a good specimen of flint decoration; the coping is not returned. In Deopham Church* a crocketed gable, much enriched with flint panelling, and surmounted by a fine Cross, rises out of the parapet on the four sides of the tower; and at Filby, near Yarmouth, the parapet, rising in graduated stages, forms a stepped gabled in the centre, with two half ones, also stepped, abutting against the angle pinnacles. This stepped parapet is a characteristic

* Engraved in the Parish Churches, Vol. II.

feature in Norfolk towers. The tower of St. George's, Doncaster, has a remarkably rich pierced parapet, with three slender pinnacles rising out of it on each side. Louth, Lincolnshire, and Bitton, Gloucestershire, have both very handsome panelled parapets, with pinnacles rising out of each battlement.

The Cross,* the most natural and appropriate termination of a gable, was made use of at a very early period. From the testimony of the old Saxon MSS. we may conclude, that even then they were invariably introduced; though, owing to the want of durability in the material, it is hardly likely that any have lasted to the present day. The fanatical violence of the Puritans sacrilegiously destroyed many which the ravages of time would longer have spared and left unharmed.

The Church builders of old delighted in exhibiting the symbol of their faith, not only on gables, but in every position where it would become a commanding and distinct object. We find Crosses, carved in low relief, over the windows of the ancient tower at Barnack, and worked in flint over the belfry windows of Martham Church. In Cranford St. John's, they occupy the N.E. and S.E. angles of the aisles, which have lean-to roofs. In a Church near Norwich, we find them at the four angles of the tower; and at Deopham, in the same county, they crown the centre battlement, which is gabled to receive them.



BARNACK CHURCH, NORTHAMPTONSHIRE.

The earliest Crosses (probably for symbolical reasons) appear generally to have been enclosed within a circle, or with the arms slightly projecting, as in Edith Western Church. (Section I. Early English, Plate 16.) The Cross, lately destroyed, over the Norman Chancel of Barnwood Church, is mentioned by Lyson as a Cross patée inscribed within a circle, the badge of the Knights Hospitallers of St. John of Jerusalem. During the Early English period this form was considerably modified, and led to many varied and elegant arrangements. For facility of examination we would classify them in the several divisions of—1, Simple Crosses; 2, Wheel Crosses; 3, Floriated Crosses; 4, Tracery Crosses.

In Simple Crosses the arms are sometimes merely chamfered, as in Churchdown Church, Gloucestershire; or engrailed, as at Badgeworth Church, in the same county; or cusped, as at Tinwell (Section I. Decorated, Plate 28); or with the extremity of the arms trefoiled, as in St. Mary's Church, Stamford; or again, we sometimes meet with them ornamented with a small flower raised on the face of each arm. A fine and perfect example of a wheel Cross occurs over the east gable of the nave of Oadby

* The authors are now preparing illustrations of a series of Gable Crosses, to which they would refer for a more ample account of this beautiful feature.

Church, Leicestershire ; it has eight spokes with trefoiled terminations, radiating from a small flower in the centre. Whitwell Church, Rutland, has also a fine Early English example. The Cross from Helpringham Church, Lincolnshire (Section I. Early English, Plate 16), may likewise be included in this class, for though the circle is omitted, its influence in the design is very visible. In floriated Crosses small branches diverge from the arms of the Cross, grouping the whole together in a very beautiful manner, as at Hingham Church, Norfolk (Section I. Decorated, Plate 33), or at Peterborough (Plate 28). Cley Church, Norfolk, probably possesses the finest example of this class in the kingdom. Tracery Crosses are generally of great beauty and richness ; that at Hasingfield (Section I. Decorated, Plate 33) is certainly the most magnificent of its class that the authors have hitherto met with : it remains very perfect, owing to the durable material (Barnack) out of which it is worked. In this class we would include the very rich eight-armed Crosses frequently to be found in Norfolk ; such are those from Stoke Ferry and Moreton (Section I. Perpendicular, Plate 15), Ludham (Plate 33), and Trunch and Stody (Plate 21). Two early and exceedingly elegant examples of this class are given in Section I. Decorated, Plate 28) from Peakirk and Methwold.

Other varieties may occasionally be noticed which are not so easy to classify ; yet they are in reality but quaint modifications of one or other of the classes we have been examining. Such is the simple and effective Cross over the Chancel of Wichford Church, Wilts (Section I. Early English, Plate 16), and its enriched counterpart from St. Mary's, Norwich (Decorated, Plate 33). Over the north transept of Gunthorpe Church, Norfolk, is one which would be classed with tracery Crosses, had not the usual arrangement been whimsically departed from in the lower part, and cusps substituted for the two secondary branches.

On some Crosses we find the figure of our Saviour carved on one of the faces, as at Oakham (Section I. Perpendicular, Plate 21) ; while at Little Casterton a smaller Cross is inclosed within a circle sunk upon the larger one. At Louth a Crown of Thorns is beautifully twined round the arms ; and at Godeby Maureward, the Cross has (or had) its outer circle cut into teeth like a saw, symbolizing thereby the martyrdom of some of the early Saints of the Church.

The Cross was generally let into the saddle stone to the depth of five or six inches, and fixed with a leaden joint, a practice which has probably caused the destruction of many beautiful examples ; for, in course of time, the expansion of the metal bursts the thin socket, the Cross is loosened, and finally drops down ; and very rarely, (we hope we may now say) in former days, was it set up again. The thickness of the Cross depended of course, in a great measure, upon the strength of the stone employed ; generally

from four to five inches may be considered a fair average. Over the south aisle of Humberstone Church, Leicestershire, the stem of the Cross was (for the socket is all that now remains) only five inches by two and three-quarters: the material is Barnack stone.

The limits of this work forbid our entering into a description of the many different ways in which the Cross is introduced into the sacred Building and its adjuncts: we will, therefore, merely refer briefly to its beautiful and appropriate use in marking the resting place of the departed faithful. Two elegant examples of floor Crosses are given in Section I. Early English, Plate 25. The one from Barnwell Church is carved in relief, while the other, from the Cathedral Church of Dublin, is incised or sunk in the slab.

Ancient FONTS,* even if regarded merely in an æsthetical point of view, will be found to possess so much interest, and to exhibit in so high a degree the architectural character of the times in which they were executed, that we can hardly conclude without at least directing attention to them. At the same time, the great number and exceeding variety of beautiful specimens, render it impossible to give an illustration, even of the types of the different fonts used during the three grand periods of Gothick Architecture. The examples introduced, each illustrating one of these epochs, must be considered, therefore, as good specimens of their several eras, but by no means as decided characteristicks of the dates they represent. It has been considered inexpedient to give an illustration of a Norman font, for it would be rather difficult to select one only (and the limits of the work forbid a greater number) among the many which are constantly met with; all very quaint, and some elaborately and beautifully enriched.

The two earliest forms of Norman fonts appear to have been the tub-shaped and the cube: the former, still preserving its circular character, was afterwards raised on a low stem with molded cap and base (a very beautiful example of this arrangement occurs in Shefford Church, Berkshire, and is engraved in the "Baptismal Fonts"), while the latter was most usually raised on a central stem, surrounded by four small shafts. In many Early English fonts this fashion was preserved: the Churches of Merstham and Shiere, in Surrey, have excellent specimens of this class. The single stem was also occasionally made use of, as in the font of Weston Church (Section I. Early English, Plate 27); it is a simple and elegant design, and has a broader step at the west for the priest, which is not shown in the plate.

In the shape of Decorated fonts, greater license seems to have been used than at any other time; at Galway the font is square, carried on a central stem, and four small angle shafts; at Orchardleigh, it is circular and cup-shaped; and at Ewerby is an hexagonal

* For a brief yet interesting account of ancient fonts we would refer to the "Baptismal Fonts," lately published by Van Voorst, and illustrated by many excellent woodcuts.

font, with the sides richly diapered. It is in the fonts of this period that we first find the richly crocketed canopy, and the octagonal stem with slender engaged shafts, as at Redgrave Church (Section I. Decorated, Plate 32), or panels divided by small pinnacles, as at Hedon Church, Yorkshire.

Perpendicular fonts, though frequently richer than the previous ones, exhibit nevertheless considerable sameness and repetition of design. They were generally eight-sided, and raised on a molded stem, though at Hurley Church, Berkshire, the font is a simple octagonal block, tapering downwards, with panelled sides, and buttresses at the angles; while in Cornwall some extraordinary and anomalous forms are occasionally met with. Sculptured decorations were then very prevalent; animals, especially lions, frequently surround the stem, while the basin is supported by rows of angels with extended wings. Walsoken Church, Norfolk, has a very beautiful and rich font of this description, rendered highly interesting from the date of its execution (1544) being cut upon it, together with the names of the donors.* Both bowl and shaft are octagonal; the former has at the angles buttresses and pinnacles, and on the sides are crocketed ogee arches supported by brackets formed of foliage and angels, and which are occupied by the Crucifixion and the seven sacraments of the Church of Rome. The buttresses, also, are supported by angels. The shaft is ornamented in the same manner as the bowl, but the niches contain figures of saints, very well carved and displaying much artistick skill. The emblems of the Crucifixion occur in shields placed round the base. The example given in Plate 28, from Clymping Church, though very inferior in point of richness, is nevertheless a pleasing specimen, of good proportion, with some very well executed foliage.

Fonts of all dates were not unfrequently raised on a series of steps, either square, circular, or octagonal. In the later examples, the risers are frequently enriched with quatrefoils; as in the Churches of Walsingham and Worstead, in Norfolk. In both these instances the upper step is in the form of a Cross, while the lower one follows the shape of the font. A kneeling stone, consisting of a raised block or step at the west of the font, for the use of the priest, was a very usual appendage: it is met with even in early fonts, though more commonly in those of a later date.

The SEDILIA, or seats for the officiating priests, always south of the Altar, were frequently of great beauty. Examples are given in Section I. Early English, Plate 6, and Perpendicular, Plate 9. Sometimes the sill of the window was lowered to form the sedilia, as in Great Wenham Church, Suffolk (Appendix, Plate 2, Fig. 14), and in St. Martin's, Leicester. The piscina, or water drain, was very frequently incorporated in the same design as the sedilia.

* Engraved in the "Baptismal Fonts."

SECTION II.—OF WOODWORK AND METALWORK.

ROOFS.*



TIMBER roof of the fifteenth century, with its massive timbers elaborately wrought and molded, its rows of hammer-beams terminating in beautifully carved figures of angels, its enriched panelling and traceried spandrels, its exquisite bosses, and above all its profusely ornamented cornice,—is truly as glorious a sight, as it is a grand triumph of the carpenter's art.

Such excellence, however, was but very gradually accomplished.

Of unquestionably Norman work, very few specimens indeed remain : judging from them, we would conclude that the construction of that period was as unscientific as it was rude. These early roofs may, perhaps, without exception, be all classed under the head of tie-beam roofs.† The one over the Chancel of Adel Church, Yorkshire, is of this description, and appears original : the principals pitch on to the tie-beam, and are braced together by collars ; slanting struts are also tenoned into the principals, and are carried down on to the tie-beam, which thus receives a great part of the weight of the roofing. Over the nave of Whitwell Church, Rutland, is a roof of a somewhat similar construction ; the collar, however, is much lower down, and immediately under it is a purlin, which supports the rafters, and is itself carried on struts framed into the beam, as at Adel : these struts are further strengthened by smaller ones, framed from them into the tie-beam, and following very nearly the rake of the roof. There is a continuous plate inside ; and another would probably be found, almost flush with the external wall, in accordance with what seems to have been then a very general practice. All the timbers are very roughly worked : indeed, cutting off the projecting knobs and branches seems

* Such an important subject requires a more extensive and careful illustration than the limits of the "Analysis" permitted ; the authors have therefore devoted a separate volume to its consideration—the work is now in the press, and they hope very shortly to be able to lay before the public the fruits of their researches.

† In all ancient roofs the tie-beam was employed to hold the walls together ; and in addition generally carried the greater part of the weight, which was brought down on to it by the king-post and struts ; being the reverse of the present principle, by which the king-post is employed to tie it up.

to have been all the finish that has been bestowed upon them. Yet, even in very early examples, we sometimes meet with a certain degree of embellishment, evincing careful workmanship: one of the beams of the Norman roof remains in Old Shoreham Church, Sussex, and is enriched with a billet molding; and other instances are occasionally found in various parts of the country.

The next advance in the framing of roofs, was to truss each rafter, sometimes by means of cross braces pinned into the two opposite rafters, and halved at the intersections, as in the example over the porch of Stuston Church, Suffolk (Section II. Woodwork, Plate 24); or, as was more usually the case in roofs of considerable span, each rafter had a collar, and was further stiffened by braces sometimes crossing above the collar, and at other times tenoned into its underside. The foot of each rafter was so framed, as to assume the shape of a triangle, whose base generally was equal to the thickness of the wall on which it rested, and by this contrivance obtained an excellent hold: thus any danger from spreading was almost entirely obviated. These roofs have frequently only one plate, placed midway in the wall, the feet of the rafters being halved upon it; but sometimes they occur with an internal and external plate; or, as at Heckington, with a central plate, and an internal one molded, and forming a slightly projecting cornice. Neither ridge-pieces or purlins ever occur, and when they are not boarded, which is very frequently the case, it becomes quite a matter of surprise how such roofs should have held up so long. When not boarded, however, the trusses are generally out of the perpendicular, inclining either to the east or the west. In the earlier instances of this kind the tie-beam was still retained, and introduced at intervals in the length of the roof; as in the example over the Chancel of Sandridge Church, Herts, which has a molded cornice projecting from the wall and carried on notch heads, and into which the tie-beam with similar moldings is framed. There are two ties in the length of the Chancel, with about twelve rafters between each.* It was not long, however, before the tie-beam was altogether omitted; and the rafters, simply trussed, continued a favourite style of roofing with the Early English and Decorated architects. The rafters are generally from one foot six inches to two feet from centre to centre; their scantling averaging about five inches by four. Remaining examples of these roofs are more numerous than any others, but in most cases they have been lathed and plastered. That in their original state they were occasionally boarded appears extremely probable; though after all, for picturesqueness and beauty, nothing can exceed the view of the rafters intricately crossing. Sometimes a trussed rafter roof spans both the nave and aisles, as in St. Michael's, Long

* The roof over the nave of Clymping Church is an Early English construction, with internal and external wall plates, and occasional tie-beams. See an engraving of it in the *Parish Churches*, Vol. II. p. 75.

Stanton, Cambridgeshire; the rafters to the nave being continued down on to the side walls, and terminating in the usual triangularly-framed foot.

Decorated roofs, however, far from being always of this simple description, are frequently of great beauty, and display considerable constructive knowledge in the framing of their principals, ridge, purlins, &c. They may be considered under the two heads of tie-beam and collar roofs. The former, perhaps, are the most frequent; an excellent example remains in Adderbury Church, Oxfordshire, enriched with good and characteristick moldings. Its framing may be described as a tie-beam *supporting* a king-post, from the four sides of which spring braces framed into the principals and ridge; both principals and braces being foliated, produce an excellent effect. Other curved and molded braces are framed into the underside of the tie-beam, forming a pointed arch, and serving to bring the weight of the roof lower down on the walls.

Higham Ferrars Church, Northamptonshire, also, has a good roof of Decorated date; the tie-beam is very much cambered, and forms an arch with the curved braces which are framed into it, and spring from small shafts with caps and bases; a king-post rests on the tie-beam, with braces supporting the ridge; small struts also rest on the tie-beam, and with similar braces carry the purlins. The cornice and principal timbers are simply molded. An equally interesting specimen is the roof over the nave of Wymington Church,* Beds, built by "*Johēs Curteys dñs de Wylmington*," who died in 1391. The Church remains almost entirely as first designed, and unquestionably the roof is of the same period. It consists of a cambered beam with foliated braces, carried, as in Higham Ferrars, on small shafts; the ridge is also supported in the same manner as in this last-named Church, and so low is the pitch in this example, that the purlins rest directly on the tie-beam without any intervening strut. The spandrels between the beam and the curved braces are pierced with trefoils.†

Of Decorated roofs without tie-beams there is a simple yet beautiful example over the south aisle of Knighton Church, Leicestershire. It is of very bold construction: each truss

* For an engraving of this roof, see *Parish Churches*, Vol. II. p. 93.

† Ancient roofs, though characteristically acutely pointed, were by no means invariably so: an angle of 90° was perhaps the most usual for Norman roofs; while Early English ones, although acutely pointed, are nevertheless rarely found of an equilateral pitch, or angle of 60°: indeed, in this and the succeeding style we occasionally meet with some so remarkably low as to rival the flattest of the Perpendicular roofs; such are those over the Early English Church at Warmington, Northants; the interesting example from Polebrook Church, in the same county, is also very low. The Decorated roof over the south aisle of St. Martin's, Leicester, has a span of twenty-one feet, with a rise of only four. The roofs in Wymington and Higham Ferrars are both very flat. The Perpendicular architects gradually lowered their roofs, though in Norfolk and Suffolk many beautiful examples remain of noble pitch.

consists of a pair of principals, which pitch on to a molded cornice plate; about midway is a collar, also molded, with small curved braces framed from it into the principal; on the collar lies the purlin, which is further strengthened and kept in its place by small curved braces, tenoned into the principal. There is a carved flower under the centre of the collar, and carved heads projecting from the wall at the foot of each principal. There is a roof of a somewhat similar construction over the Chancel of St. Mary's Church, Leicester, with the addition, however, of wall pieces, into which the braces are framed. Over the large south aisle of St. Martin's Church,* in the same town, is a roof of very early Decorated character, and exceedingly interesting. Its construction is simply an enormous beam rising up to the ridge, and following the rake of the rafters: the underside is slightly curved in the centre, the curve being completed by means of the braces, so as to produce almost a semi-circular arch. These braces, and that part of the beam which enters into the curve, are beautifully molded, as are likewise the ridge and cornice plates; the former is partly carried on corbel heads tenoned into the tie-beam, into which also are framed the latter, the moldings at the junction being stopped with foliage; the spandrels are filled with tracery. A peculiar and interesting feature in this roof are the figures which are carved out of the wall pieces, and carry the curved braces; they are about four feet in height, exceedingly well carved, and full of expression; we might suppose them to be emblematical of some of the principal virtues, Humility, Patience, &c.

The roof over the nave of Chapel St. Mary's Church, Suffolk, shows a great advance upon the examples we have already examined. Here we may first notice the introduction of that distinguishing feature of the Suffolk roofs, the hammer-beam. In this instance the pitch is exactly at an angle of 90° ; the embattled collar, which is placed very high up, supports a strut or small king-post, into which the principals and ridge are framed; a curved brace in two pieces is tenoned into the undersides of the collar and principal, and fixed with wooden pins; and the foot of the brace is also framed into the hammer-beam. In these roofs the cornice is altogether differently constructed, and answers a distinct purpose from that of previous examples, where it generally served as a plate for the rafters to pitch upon. In the roofs of Suffolk and Norfolk it may be divided into three parts: the lower one, usually consisting of a molded plank of three to four inches in thickness, is tenoned from hammer-

* St. Martin's Church has two south aisles; the roof over the larger one is a span roof, and the rafters from it are continued down over the smaller aisle, which is covered by a lean-to. The parishioners have lately, in the same hearty spirit which actuated their ancestors, reconstructed entirely, and with similar worthy materials, these two roofs, as well as that over the Chancel (a very fine and rich Perpendicular example): in both cases, the originals having been minutely copied, as to scantlings and details. The old timbers, on being taken down, were found to have been richly coloured; why not fully carry out the restoration, and extend this enrichment to the new roofs?

beam to hammer-beam, to which it affords an additional lateral tie ; the centre one is either pierced with panelling or otherwise ornamented, not unfrequently with angels having expanded wings, as at Knapton Church, Norfolk ; while the upper part, like the lower, is usually molded, and sometimes, as in Capel St. Mary's, becomes in fact an additional purlin, being in every respect similarly treated. We may easily trace the origin of these cornices to a peculiarity in these two counties already referred to—namely the absence of parapets ; for where eaves were used, the hammer-beams and rafters were carried very far back, and in some cases quite to the outer face of the wall, thus leaving a considerable space inside between the wall plate under the hammer-beam and the soffit of the rafters. To fill this space with masonry would not only be a piece of useless construction, but it would also tend much to destroy the beauty of the design as a whole, by separating the hammer-beam from the remainder of the roof. This space was therefore either left open, or the cornice was adopted as affording a legitimate mode of further enriching the roof, and at the same time giving it greater lateral strength. In Old Basing Church, Hampshire, in a Perpendicular roof of rather peculiar construction, a similar difficulty has been met by the use of upright panelling ; the effect, however, is very inferior to the Suffolk arrangement.

The example over the north aisle of Wymondham Church, Norfolk (Section II. Woodwork, Plates 17, 18, 19), exhibits the hammer-beam roof in its fullest development. The most usual way of framing these roofs may be briefly described as follows :—A hammer-beam is bedded on a plate, and extends sometimes almost to the outer face of the wall ; while internally its projection varies perhaps from one-fifth to one-sixth of the width of the opening ; a wall piece is framed into its underside, and is generally, though not of necessity, carried on a corbel ; the weight on the hammer-beam is brought down to the wall piece by means of the curved or spandrel brace, which is tenoned and pinned to the soffit of the former, and in a similar manner is also fixed to the latter. A strut rising from the extreme end of the hammer-beam supports the principal, which is tied in by the collar, and further strengthened by curved braces which bind it to the collar and supporting strut : the whole framing is thus perfectly secured. The Wymondham roof presents a curious variety ; for the collar is rather daringly dispensed with, and at the summit is a large wedge-like piece of wood, into which are tenoned the extremities of the principals and ridge. The sides of the roof are divided into compartments by three purlins and an intermediate principal, and are enriched with foliated panels : the tracery in the spandrels is also very varied, many of the designs produced being of exceeding beauty : eight specimens are given in Plate 19 ; in one of them we may notice the crowned M. These tracery panels rarely exceeded an inch in thickness, and the pattern is merely pierced through, or with the edges chamfered, as in the examples before us, but with no eyes to the eusps. Very beautifully carved bosses cover the intersections of the

principal timbers. In this roof we may notice the introduction of wall braces, uniting and stiffening the cornice and wall pieces.

In Grundisburg Church, Suffolk (Section II. Woodwork, Plates 26 and 27), we find a double range of hammer-beams, one above the other: the principle of the construction, however, is precisely the same, but with a proportionate increase in rich effect. The king-posts are beautifully wrought into figures of angels with outspread wings, and others also with expanded wings are placed at the feet of the wall pieces, and at the extremities of the lower hammer-beams. The effect produced by this host of angels, leaning forward from their airy height, is grand and solemn almost beyond description. In the example over Knapton Church, which is also a double hammer-beam roof, the angels, representing the heavenly choir, hold in their hands instruments of music, or some holy texts or symbols. Trunch Church, also in Norfolk, has a magnificent roof over the nave, without a collar, being merely tied in by the curved braces; its tracery spandrels are of the most elaborate richness. Woolpit Church, in Suffolk, has a most glorious double hammer-beam roof;* every part of it is profusely ornamented; the rafters and purlins are richly molded; rows of Strawberry leaf divide the cornice, and angels, applied to the extremities of all the hammer-beams, seem hovering midway in the air on their extended wings. The lower parts of the wall pieces are also worked into niches, filled with figures of saints, over whose heads are suspended elaborately carved canopies. The splendour of the roof of St. Mary's, at Bury, is too well known to need description.

In another kind more frequently met with in the Midland Counties, and also in Devonshire and Somersetshire, the tie-beam once more becomes an important constructive feature. A highly enriched example occurs in Cirencester Church: the braces under the tie-beam are double-cusped and have foliated spandrels; the wall braces are of the same elaborate description; the tie-beam itself is finely molded with a deep casement filled with flowers; and in fact every part susceptible of enrichment has received it in a high degree.

As the Perpendicular period drew to a close, the expiring genius of Gothic art exhibited itself in the roofs no less than in all other parts of the sacred Edifice. They were then made exceedingly flat, and what was missing in constructive skill was sought to be remedied and replaced by crowded, but frequently ill-executed, ornament. Such an example occurs over the north chapel of Wellingborough Church, Northamptonshire.

Many other specimens of roofs might be adduced, for the variety is almost infinite; but we have already exceeded the limits which we proposed in the present work to devote to this interesting subject; and therefore, in conclusion, we will briefly sum up the most striking points concerning these ancient constructions:—1st, we may be sure that a vigilant search

* For an engraving of this roof, see *Parish Churches*, Vol. I. p. 49.

would prove Decorated and Early English roofs to be yet remaining in tolerable abundance, and that even Norman specimens are not wanting ; 2nd, that their pitch varied from an angle of 90° to one of 60°, rarely exceeding the latter, but not unfrequently, even in Early English examples, very much below the former, and that tie-beams are common to the roofs of all the different periods ; 3rd, that the various timbers were simply tenoned and pinned together ; 4th, that the purlins, in lieu of lying over the principals, as in a modern roof, are invariably framed into them, thus allowing the rafters to lie flush with the tops of the principals ; and finally, that in common with all the other accessories of a Church, these elaborate and splendid works were richly coloured and gilded. Perhaps even now, most examples, if closely examined, would still present some lingering marks of their past splendour. And, before leaving the subject, we would fain raise our humble voice, urgently pleading for the careful restoration of these truly national glories : for after all, none other than our own oak-bearing land can boast of roofs such as those that abound with us, either in beauty or boldness of execution. But while we would urge their restorations as peculiarly national works, let not the pressing necessity of such a course be forgotten. None but those who have devoted close attention to the subject, climbing the ladders and bestowing a careful and minute inspection, can form an idea of the effect produced by nearly four centuries of neglect and decay. A few years must assuredly witness the restoration, or total destruction, of many most exquisite roofs,—pious legacies of our forefathers.

The general arrangement of the old seats in our Churches will be sufficiently understood from an examination of the plates ; for notwithstanding that they were frequently profusely ornamented, the actual construction and disposition ever remained the same, and consisted of a continuous sill laid along the floor, into which the bench ends were stubbed, the seats being supported on brackets placed at intervals, with the backs either terminating level with the seats, or carried down to the floor ; the book board was placed but little higher than the seat, and never slanting ; it was, in fact, simply a ledge to lay the book on when not in use.

Great Waltham Church retains almost all its old seats in very good preservation ; their arrangement and details are shown in Plate I. of Section II. Woodwork. The sill is molded, as was almost always the case, and the bench ends are ornamented with small buttresses, in this instance cut out of the solid, and some very excellent tracery panels, all varying more or less one from the other ; a selection of the most beautiful is given in Plates 2 and 3. The top of the bench ends is capped with a molding, also carried round the backs, which finish level with the underside of the seats. In Comberton Church, Cambridgeshire, we find the same description of seat, but very much more highly enriched ; here the backs are continued down to the floor, and framed into a cross sill. The square bench end was also generally adopted in Devonshire and Somersetshire. Bishop's Lydeard, Trull, and Crowcombe

Churches are still filled with very beautiful seats, though they are all of late workmanship. Several examples are given in Section II. Woodwork, Plate 31. The date of those in Crowcombe Church (1534) is carved on one of them in conjunction with some initials, having probably reference to the name of the donor.

At other times, and especially in Norfolk and Suffolk, the bench ends were ogeed, and finished with finials,* affording the carver opportunities for the freest display of his imagination, which indeed appears to have been most wonderfully prolific, for not only were two finials rarely found alike in the same Church, but even the two sides were generally different. St. Mary's Stratton, in Norfolk, would furnish nearly one hundred distinct patterns; nor is this a solitary case. Thirteen varieties are given in Plates 6, 16, 20, and 30. The peculiar form common to most finials is supposed by some† to be derived from the fleur de lis, both a religious emblem and a royal heraldic charge. Poppy, or poppy head, the more correct term for designating these wooden "Crops," would appear to be derived from the frequent custom of working the terminations into figures of priests, warriors, &c. Ketton Church, Rutland, furnishes many beautiful specimens of this description; in one instance a bishop is represented in his pulpit. Grundisburgh Church, Suffolk, has some fine examples of ogeed bench ends richly panelled, though of rather late date and exhibiting a declining taste. The bench ends in the Church of St. Mary's Wiggshall, Norfolk, are of the most elaborate splendour; they are ogeed and finished with a poppy head, supported on either side by figures, while another figure occupies a niche in the panel.

The CHANCEL SCREEN, a no less beautiful than necessary appurtenance, yet remains in many of the remote village Churches of Norfolk in almost all its original splendour. Though the carver exhausted on it the resources of his wonderful art, still was it not considered complete and worthy of its purpose, until it had been made to glow with the richest colours and gilding. To delineate the delicacy of the tracery, without at the same time supplying the rich tints of the colour, is to deprive the design of a principal part of its beauty: the aid of polychromy, eagerly acknowledged in all parts of the Church, in the case of screens more especially, was considered essential. Scriptural texts were constantly introduced in the cornice, and sometimes, as in Bishop's Lydeard, the whole of the Creed filled the casement. On the lower panels were customarily painted the holy Apostles, or other Saints and Martyrs.

* This word is singularly degenerated from its original and proper meaning: its present sense however is now so universally adopted, that we must almost despair of seeing the abuse corrected. The ancient "fynyall" always represented the entire pinnacle, while the *crop* is the legitimate term for the bunch of foliage terminating the finyall: "et altitudo a le gargayle usque le *crop* qui finit le stone-work 31 pedes," see Willis's Nomenclature of the Middle Ages.

† See Ecclesiologist, Vol. V. p. 209.

But a few specimens of screens have been given, for, to do them justice, a whole work should be devoted to the subject : and we much hope that such a one will soon be undertaken,—one in which shall be depicted, not only the architectural beauties, but also the polychromatick effects. An interesting example of a Decorated screen from Waltham Abbey Church is given in Section II. Woodwork, Plate 7 ; its proportions are exceedingly massive, and its moldings very characteristick. Other examples of Decorated woodwork, selected from screens in Bottisham Church, Cambridgeshire, are given in Plate 14 : a spandrel piece in this plate is remarkable for the beauty and *triangularity* of its design. In Plate 21 is a selection of panel heads from a very beautiful screen lately in Chester Cathedral, but which we understand to have been destroyed since our drawings were made. Barton Church, Cambridgeshire (Section II. Woodwork, Plate 10), has a very beautiful Chancel screen in good preservation, the doors alone being missing. The carving in this example is particularly well executed ; some of the crockets, spandrels, and cusps terminations are given in Plate 11. The lower panels of the doors to the screen in Wells Cathedral (Section II. Woodwork, Plate 8) have some very rich tracery, in which the equilateral triangle, as the groundwork of the formation, is made apparent.

The construction of the DOORS was always of the most solid description ; early examples, however, never display any carved work, owing to the general practice of those times of introducing ironwork in the design : at once a strengthening and a beautiful enrichment. Some few Norman doors are yet existing ; their framing is exceedingly rude, and they derive their great strength from the ironwork with which they are banded. Such is the example in Sempringham Church, Lincolnshire (Section I, Norman, Plate 6), where the material, strange to say, is deal.* Towards the close of the Early English period, ornamental ironwork began to fall into disuse, although tracery was hardly yet introduced. St. Margaret's Chapel, Herts, has a very good and perfect specimen of an early Decorated door : it consists of battens slightly raised towards the centre, which are tongued into each other, and divided by molded ribs cut out of the solid. These panels are strengthened and tied together by cross pieces placed inside, and nailed through to the outer face : the entire thickness is three inches and a half. Milton Church, Kent (Section I. Decorated, Plate 14), has a door precisely of this description. In North Mimms Church (Section I. Decorated, Plate 25), the door is similarly framed, but without the raised panels. Rushden Church, Northamptonshire, has a Decorated example, where the head brace is elegantly shaped into an ogeed trefoil. The south door of Holbeach Church is a beautiful and perfect specimen of Decorated woodwork ; its framing

* Only one other instance has come under the notice of the authors, where this material has been preferred to oak, namely, the doors to the Chapter House at York, which are of later date, but also profusely enriched with ironwork.

and details are minutely described, and will be best understood by reference to the Plate 10, in Section I. Decorated. Stoke Church, Suffolk, has a magnificent door, probably unsurpassed in richness; tracery, moldings, figures of saints, and canopies, all of the most costly workmanship, cover the entire surface.

Many perfect and elaborate examples of Perpendicular doors remain; the one in Deopham Church is transitional from Decorated, and has some good flowing tracery in the head. The Abbey Church of St. Alban contains many beautiful Perpendicular specimens; one of them is represented at large in Section II. Woodwork, Plate 4. Other instances will be found in Section I. Perpendicular, Plates 6, 17, 20, and in Section I. Early English, Plate 23.

Porches were frequently built of oak, and Decorated and Perpendicular examples are even now very numerous. The south porch of Aldham Church, Essex, is illustrated in Section I. Woodwork, Plates 12 and 13. The accompanying plans and sections will sufficiently explain the construction, which was very similar in all cases.

Plates 9, 25, 28, and 30, illustrate different specimens of strings, bosses, spandrels, and cusps terminations, all exhibiting in a high degree the talent and taste of the artificer. The bosses from Haslingfield Church, in Plate 28, are situated at the intersections of the principal timbers of an interesting Decorated roof, remarkable for the beauty of its moldings.

METALWORK.



DIFFERENCE and cupidity on the one hand, and the ravages of time on the other, have despoiled our Churches of the greater part of their ancient ironwork; enough remains, however, to show that in the treatment of it, difficult as it is to work, the same care and patient attention was devoted as was bestowed upon all other materials entering into the composition of the sacred Fabrick. The Norman Architects frequently displayed the greatest ingenuity in this branch of art. In St. Alban's Abbey Church are some hinges of that early period; two of them are engraved in Plates 1 and 9, of Section II. Metalwork. That in Plate 1 has the strap continued quite through and is finished with an ornamental termination, a portion of which only now remains: in the second example, in Plate 9, the strap terminates with the commencement of the scroll work. The knob at the welding point is fashioned into the head of a serpent; this device, with jaws extended, also occurs at the ends of some of the scrolls,

is in high relief, and exceedingly well executed considering the nature of the material. In both these examples the surface is enriched with a kind of chevron, easily produced with the chisel: the thickness of the metal is three-eighths of an inch at the commencement, and is gradually brought down to one-eighth towards the extremity. A most valuable and perfect specimen of Norman ironwork is to be found in Sempringham Church, Lincolnshire. The entire door is represented in Section I. Norman, Plate 6, and a portion of the ironwork to a larger scale in Plate 5 of Metalwork. The north door of St. Margaret's Church, Leicester, is also covered with some very early work: the design is rather fantastick, and consists of top and bottom hinge, in which, as at St. Alban's, we may notice the terminating serpents' heads; and between the two hinges is a radiating centre-piece of eight branches; the whole being enclosed in an ornamental border, as in Sempringham.

The art of working this metal, however, was as yet but in its infancy; the Early English Architects rapidly improved it, and, perhaps, brought it to the highest degree of perfection attained during the Middle Ages; for if the finish of the workmanship was not quite so great as in subsequent periods, the freedom and beauty of the design were incomparably superior. Numerous examples of doors, covered with the elegant scroll work of this age, are yet remaining in different parts of the country. The example from St. Mary's, Norwich, is most excellent, and in a very perfect state; it is represented in Plate 8, with several of the ornamental parts at large. The broad and enriched Norman border, which we have noticed, is here restricted to a very narrow strip, nailed at intervals. No less beautiful and perfect is the work on the south door of Eaton Bray Church, Bedfordshire (Plate 11). That which is spread over the doors of the Chapter House at York, is merely used as a stiffener, the hinges being kept quite distinct. The design and execution of this example (see Plate 6) are quite worthy of the extreme beauty of the Building to which it is attached. The raised boss for the closing ring is very ingeniously managed; the narrow border strip occurs here as in St. Mary's, Norwich. The doors to a closet in Chester Cathedral belong also to this class of ironwork. They are divided into four panels, which division is made apparent in the different designs of the scroll work; they are all exceedingly graceful, and of the most finished workmanship. The details which are appended (see Plate 4) exhibit some of the varieties of the terminations, and also the junctions of the several scrolls, which are cleverly managed, a leaf generally lapping over to hide the welding point. In all these examples we may remark, that the small branches invariably proceed from the outer side of the scroll; the section of the scroll is sometimes raised to an arris, as in Chester Cathedral, or with a channel sunk on it as in York Chapter House.

Many plainer examples of hinges are dispersed throughout the accompanying Plates: a

very good one from Market Deeping is engraved in Plate 9. In the same plate is given a very elaborate stiffener from Tunstead Church, and also one of a plainer description from Great Casterton Church. Sometimes the closing ring was so enlarged as to answer both as a ring and a tie to the door; as in the examples from Aldham Church, Essex (Plate 5); St. Mary's, Norwich (Plate 8); and Filby Church (Plate 13).

The closing ring, or door latch, was generally more or less enriched, even when the remainder of the ironwork to the door was left quite plain. Examples of all kinds are very abundant; they generally consist of three parts: the flat plate or washer, fixed to the outer surface of the door; the handle or ring; and the spindle to which it is attached, which, passing through the door, is fixed to the latch inside. The plate is susceptible of great richness, and occurs from the simply indented pattern in the Churches of Diss and Bapchild (Plate 7), to the highly ornamented examples in Eye and Martham Churches* (Plates 5 and 12). The most usual construction is shown in Plate 5, where a flat plate, slightly raised in the centre, to allow of the handle hanging clear, has two rims of metal variously enriched applied to its surface; and the whole is firmly fixed to the door, with nails having heads ornamented in keeping with the rest. In Martham, the washer is further enriched by being pierced with tracery. The ring was not so generally ornamented; very frequently it consisted simply of a plain circle, or it was elongated, as at Exton and Haconby Churches (Plates 7 and 12); at Ashby St. Leger's it assumes a trefoiled shape, and is slightly ornamented; while at St. Alban's two serpents twine round it. A good effect was frequently produced, as at Floore Church (Plate 9), by simply forming the ring out of a square bar of iron twisted. The closing ring in Plate 12, from St. Nicholas, Gloucester, is an extraordinary specimen of the smith's art. Even the key plate was frequently made an ornamental feature, and helped to carry out the general richness of the whole door. At Martham Church (Plate 13) is a very elaborate specimen enriched with tracery; Westminster Abbey Church has also some good specimens (Plate 2), and in Diss Church, Norfolk (Plate 7), there is one of a triangular shape, and finished with serpents' heads at the angles. The termination of the stanchion in the ironwork of the windows was occasionally ornamented, sometimes being finished with a kind of fleur de lis, as at Rushden (Plate 13); or with tracery heads, as at Potterspury (in the same plate); or with a bunch of oak leaves and acorns, as at Eyworth Church, Bedfordshire; or simply twisted, as at Rothley, Leicestershire.

The few examples that remain of the railings round monuments, are generally characteristick of the time of their erection. Some specimens of this kind are still

* When enriched with tracery, a piece of crimson cloth was frequently placed between the door and the plate, the better to show off the design of the foliations; this cloth sometimes remains.

preserved in Arundel Church. The tomb of the Black Prince at Canterbury also retains its original railing, enriched with various devices. Queen Eleanor's tomb was formerly protected by a most costly and elaborate piece of metalwork, consisting of scrolls and flowers peculiar to the period (1292) : though removed from its proper position, this beautiful work of art still remains in the Abbey. The doors into the Chantry of Henry V. were formed of cross bars of iron bolted together at each intersection : a screen of this description remains in good preservation in St. Alban's Abbey Church, a portion of which is represented in Plate 13. In the same plate is given another piece of screen work, also from St. Alban's.

In thus bringing the Analysis to a close, we will candidly admit that our researches have furnished us with many more subjects that we would most gladly have transferred to its pages, had our prescribed limits permitted.

For the sake of various beautiful examples, we would fain have extended our work into greater detail and more elaborate illustration ; but we have borne in mind the terms of our prospectus, and have endeavoured to adhere to it as closely as possible. Besides, the possession of the most voluminous collection of Examples will never make a Church Architect ; something more than books is necessary. Let him who would aspire to the honourable title, go and minutely examine and study the Buildings themselves ; there is hardly a village Church, however unpretending, but will furnish some information to the diligent inquirer ; for,

“ Yet do the structures of our fathers' age
Shame the weak efforts of art's latest stage.”

THE END.



INDEX TO CHURCHES REFERRED TO.

| BEDFORDSHIRE. | |
|------------------|------------------------|
| | PAGE |
| Dunstable | 63, 82 |
| Eaton Bray | 80, 101 |
| Eyworth | 102 |
| Farndish | 33 |
| Felmarsham | 64, 75, 76, 77, 79, 82 |
| Wootton | 60 |
| Wimington | 93 |

| BERKSHIRE. | |
|------------------|----|
| Hurley | 90 |
| Lyddington | 28 |
| Shefford | 89 |
| Uffington | 66 |

| BUCKINGHAMSHIRE. | |
|-------------------|----|
| Chesham | 74 |
| Stoke Pogis | 18 |

| CAMBRIDGESHIRE. | |
|-----------------------------------|----------------------------|
| Barnwell | 18 |
| Barton | 99 |
| Bottisham | 28, 36, 45, 57, 80, 83, 99 |
| Comberton | 97 |
| Conventual Buildings, Ely | 39 |
| Ely Cathedral | 2, 35 |
| Fen Ditton | 51, 55, 67, 83 |
| Haslingfield | 88, 100 |
| Histon | 36, 81 |
| Stourbridge | 13, 81 |
| St. Michael's, Long Stanton | 18, 78, 92 |
| Trumpington | 24, 43, 76, 80 |

| CHESTER. | |
|-------------------------|---------|
| Chester Cathedral | 99, 101 |

| CORNWALL. | |
|---------------------|----|
| St. Germain's | 62 |

| CUMBERLAND. | |
|--------------------------|----|
| Carlisle Cathedral | 28 |

| DERBYSHIRE. | |
|-----------------|------|
| | PAGE |
| Ashborne | 32 |
| Dronfield | 83 |
| Repton | 18 |

| DEVONSHIRE. | |
|------------------------|----|
| Exeter Cathedral | 27 |

| DORSETSHIRE. | |
|------------------|----|
| Beaminster | 85 |

| DURHAM. | |
|--------------------------|--------|
| Hartlepool | 78 |
| Houghton-le-Spring | 22, 31 |
| Merrington | 62 |

| ESSEX. | |
|---|--------------------------------|
| Aldham | 100, 102 |
| All Saints, Colchester | 83 |
| Bradwell | 46 |
| Castle Hedingham | 14 |
| Roydon | 27, 34 |
| St. Botolph's Priory Church, Colchester | 14 |
| St. Nicholas, Colchester | 42 |
| Waltham Abbey Church | 12, 13, 14, 39, 46, 52, 56, 99 |
| Great Waltham | 97 |
| Weald | 49, 62 |

| GLOUCESTERSHIRE. | |
|--------------------------------|----------------|
| Badgeworth | 37, 69, 86, 87 |
| Barnwood | 15, 18, 72, 87 |
| Bibery | 62 |
| Bitton | 87 |
| Brockworth | 17 |
| Cirencester | 96 |
| Churchdown | 24, 87 |
| Gloucester Cathedral | 28 |
| Leekhampton | 34, 40 |
| St. Mary Magdalen .. | 61 |
| St. Nicholas, Gloucester | 102 |

HAMPSHIRE.

| | PAGE |
|----------------------------|----------------|
| Arreton | 21 |
| Basingstoke | 74 |
| Old Basing | 95 |
| Nately | 12, 62 |
| Romsey Abbey | 13, 15, 57 |
| St. Cross | 13, 14, 15, 65 |
| St. Mary's, Easton | 49 |
| Winchester Cathedral | 13, 31, 32, 33 |
| Winnal Magdalen | 20 |

HEREFORDSHIRE.

| | |
|------------------|----|
| Leominster | 28 |
|------------------|----|

HERTFORDSHIRE.

| | |
|-----------------------------|---|
| North Mimms | 52, 68, 69, 99 |
| St. Alban's Abbey | 5, 7, 16, 20, 22, 23, 24, 28, 29, 33, 35, 39, 44, 45, 46, 53, 67, 71, 80, 81, 100, 101, 102, 103 |
| Sandridge | 53, 79, 92 |
| Sawbridgeworth | 27, 28 |
| St. Margaret's Chapel | 44, 59, 99 |
| Wheathampstead | 30, 31 |

IRELAND.

| | |
|---------------------------|-----|
| Galway | 89 |
| St. Patrick, Dublin | ib. |

KENT.

| | |
|---|------------------------------------|
| Bapelchild | 59, 102 |
| Barfreston | 14 |
| Canterbury Cathedral | 15, 47, 82, 102 |
| Chartham | 28, 57 |
| Cobham | 54 |
| Darenth | 12 |
| Hartley | 18 |
| Headeorn | 32 |
| Herne | 24, 26, 33, 37, 43 |
| Hythe | 18 |
| Meopham | 21, 23, 36, 43, 65 |
| Milton | 66, 68, 69, 99 |
| Northfleet | 24, 27, 41, 42, 44, 45, 51 |
| Orpington Church | 54, 62 |
| Patricxbourne | 14 |
| Shorne | 17, 41, 73 |
| Southfleet | 24, 27, 28, 34, 37, 41, 43, 56, 85 |
| St. Bartholomew's Hospital Chapel | 19, 54 |
| St. Margaret at Cliffe | 35, 62, 82 |
| St. Mary's Cray | 37 |
| St. Nicholas Harbledown | 34, 43, 79 |
| Stone | 81 |
| Sutton at Hone | 70 |
| Thannington | 33 |

LEICESTERSHIRE.

| | |
|------------------------|----------------|
| Belgrave | 21, 28 |
| Bothley | |
| Dunton Bassett | 24 |
| Evington | 21, 25, 33, 86 |
| Godeby Maureward | 88 |
| Humberstone | 36, 38, 40, 89 |

| | PAGE |
|---|------------------------------------|
| Knighton | 93 |
| Leir | 74 |
| Melton Mowbray | 36 |
| Oadby | 58, 70, 88 |
| Over Claybrook | 85 |
| Rothley | 102 |
| St. Margaret's Leicester | 38, 82, 84, 101 |
| St. Martin's | 39, 50, 51, 57, 63, 80, 90, 93, 94 |
| St. Mary's Hospital Chapel, Leicester | 18 |
| St. Mary's | 94 |
| Staunton Harold | 85 |

LINCOLNSHIRE.

| | |
|-------------------------------|------------------------|
| All Saints', Stamford | 81 |
| Bicker | 34, 57 |
| Billinborough | 27, 33 |
| Croyland | 15 |
| Donnington | 85 |
| Ewerby | 40, 68, 76, 85, 89 |
| Fishtoft | 27 |
| Fleet | 40, 59, 85 |
| Grantham | 23, 40 |
| Haconby | 102 |
| Heckington | 29, 69, 70, 86, 92 |
| Helpringham | 88 |
| Holbeach | 44, 46, 67, 69, 83, 99 |
| Lincoln Cathedral | 2, 16, 35 |
| Louth | 85, 87, 88 |
| Market Deeping | 101 |
| Morton | 80, 88 |
| Sempringham | 62, 99, 100 |
| Sleaford | 26, 29, 45, 46 |
| St. Leonard's, Stamford | 63 |
| St. Mary's, Stamford | 58, 81, 87 |
| Stow | 12 |
| Sutterton | 86 |
| Swatton | 51, 67 |
| Thurlby | 81 |
| Weston | 89 |

MERIONETHSHIRE.

| | |
|----------------|----|
| Llanabar | 18 |
|----------------|----|

MIDDLESEX.

| | |
|---|--|
| St. Etheldreda's Chapel, Ely Place, Holborn | 57 |
| St. Margaret's, Westminster | 54 |
| Temple Church, London | 63 |
| Westminster Abbey ... | 2, 6, 7, 8, 9, 10, 29, 32, 33, 44, 54, 63, 65, 81, 82, 102, 103 |

NORFOLK.

| | |
|---------------------|-------------------------|
| Besthorpe | 84 |
| Blakeney | 20, 33, 84 |
| Brandon | 34, 70 |
| Castle Rising | 13 |
| Cley | 36, 67, 68, 88 |
| Coltishall | 71, 72, 73, 74, 81 |
| Deopham | 33, 69, 85, 86, 87, 100 |
| Diss | 102 |
| Filby | 36, 86, 102 |
| Gunthorpe | 88 |

| | PAGE |
|-------------------------------------|--------------------|
| Hingham..... | 42, 54, 55, 86, 88 |
| Hunworth..... | 38, 81 |
| Kenninghall..... | 81 |
| Knapton..... | 95, 96 |
| Little Snoring..... | 62 |
| Ludham..... | 88 |
| Martham..... | 85, 86, 87, 102 |
| Methwold..... | 88 |
| New Walsingham..... | 84, 90 |
| Norwich Cathedral..... | 13 |
| Repps..... | 37 |
| St. Mary Magdalen, Wiggenshall..... | 32, 62, 98 |
| St. Mary's, Norwich..... | 88, 101, 102 |
| St. Mary's, Stratton..... | 98 |
| St. Nicholas at Lynn..... | 31, 44 |
| Stody..... | 88 |
| Stoke Ferry..... | 88 |
| Trunch..... | 75, 88, 96 |
| Tunstead..... | 31, 54, 55, 101 |
| Walsoken..... | 90 |
| Winterton..... | 39 |
| Worstead..... | 55, 69, 72, 85, 90 |
| Wymondham..... | 95 |

NORMANDY.

| | |
|---------------------------------|----|
| Deseerated Church at Rouen..... | 30 |
| St. Ouen at Rouen..... | 7 |

NORTHAMPTONSHIRE.

| | |
|-------------------------------|----------------------------|
| Achurh..... | 39, 82, 85 |
| Aldwinkle..... | 22, 34, 38, 70 |
| Ashby St. Leger's..... | 32, 102 |
| Barnack..... | 29, 87 |
| Barnwell..... | 37, 38, 45, 64, 78, 85, 89 |
| Byfield..... | 68 |
| Cottingham..... | 27, 35 |
| Cranford St. John..... | 87 |
| Cransley..... | 74 |
| Crick..... | 34, 68, 70 |
| Duddington..... | 37, 40 |
| Etton..... | 18, 20, 22, 85 |
| Floore..... | 102 |
| Fotheringay..... | 9 |
| Glaphthorne..... | 21 |
| Gosgrove..... | 56 |
| Higham Ferrars..... | 65, 66, 76, 86, 93 |
| Islip..... | 73 |
| King's Sutton..... | 31 |
| Loddington..... | 66 |
| Oundle..... | 17, 20, 22 |
| Peakirk..... | 88 |
| Polebrook..... | 81, 86, 93 |
| Potterspury..... | 74, 102 |
| Pythley..... | 83 |
| Raunds..... | 36, 37, 65, 76, 78, 81 |
| Ringstead..... | 18, 27 |
| Rothwell..... | 65 |
| Rushden..... | 99, 102 |
| Rushton Park Lodge..... | 47 |
| Stanwick..... | 18, 85 |
| Stoke Albany..... | 23, 43 |
| St. Peter's, Northampton..... | 35, 56, 82 |
| Tiehmarsh..... | 56, 81 |
| Towcester..... | 72, 83 |

| | PAGE |
|---------------------|----------------------------|
| Warmington..... | 19, 20, 35, 40, 64, 78, 93 |
| Weekley..... | 39, 76, 79 |
| Wellingborough..... | 27, 96 |
| Werrington..... | 19 |
| Woodford..... | 64 |
| Wooton..... | 24 |

NOTTINGHAMSHIRE.

| | |
|------------------------|------------|
| Newark..... | 44 |
| Southwell Minster..... | 13, 16, 35 |

OXFORDSHIRE.

| | |
|--------------------------------|--------------------|
| Adderbury..... | 93 |
| Bloxham..... | 15 |
| Charlton-on-Otmoor..... | 31 |
| Dorchester..... | 29 |
| Fritwell..... | 49 |
| Garsington..... | 36 |
| Great Milton..... | 36 |
| Ifley..... | 13, 14, 37, 50, 62 |
| Magdalen College Chapel..... | 38 |
| Merton College Chapel..... | 29, 32 |
| Middleton Stoney..... | 61 |
| Newington..... | 40 |
| Northleigh..... | 62 |
| Oxford Cathedral..... | 13, 14 |
| Stanton Harcourt..... | 19 |
| Stanton St. John..... | 36, 42 |
| St. Mary's Church, Oxford..... | 32 |

RUTLANDSHIRE.

| | |
|-----------------------|-----------------|
| Ayston..... | 85 |
| Edith Weston..... | 38, 87 |
| Essendine..... | 61 |
| Exton..... | 102 |
| Great Casterton..... | 17, 18, 19, 101 |
| Ketton..... | 58, 63, 81, 98 |
| Little Casterton..... | 10, 18, 88 |
| Manton..... | 17, 18 |
| Oakham..... | 88 |
| Ryall..... | 84 |
| Tinwell..... | 19, 20, 87 |
| Whitwell..... | 78, 88, 91 |
| Wissendine..... | 51 |

SHROPSHIRE.

| | |
|---------------------|----|
| Acton Bunnell..... | 77 |
| Buildwas Abbey..... | 15 |
| Ludlow..... | 85 |

SOMERSETSHIRE.

| | |
|---------------------------------------|----------------------------|
| Bishop's Lydeard..... | 34, 36, 38, 85, 86, 97, 98 |
| Crowcombe..... | 97 |
| Monksilver..... | 35 |
| Orchardleigh..... | 89 |
| St. James's Church, Bristol..... | 14 |
| St. Joseph's Chapel, Glastonbury..... | 15 |
| St. Mary, Redclyffe, Bristol..... | 37, 85 |
| St. Mary's, Taunton..... | 85 |
| Trent..... | 27 |
| Trull..... | 97 |
| Wells Cathedral..... | 99 |

| | PAGE | | PAGE |
|----------------------------------|--|----------------------------------|-------------------------|
| STAFFORDSHIRE. | | Portslade | 18 |
| Leek | 42 | Preston | 78 |
| SUFFOLK. | | Southase | 12 |
| Capel St. Mary's | 42, 94, 95 | Steyning .. | 12, 13, 35 |
| Debenham | 83 | Tangmere | 12, 17, 18 |
| Eye | 102 | Westhamptnet | 33 |
| Great Wenham | 18, 20, 24, 40, 90 | WARWICKSHIRE. | |
| Grundisburg | 75, 96, 98 | Beauesert | 13 |
| Holton St. Mary's | 27 | Holy Trinity, Coventry | 85 |
| Lavenham | 36, 50, 55, 72, 75, 80, 81, 84, 86 | Knowle | 85 |
| Little Wenham | 18, 43, 82 | Temple Balsall | 33 |
| Long Melford | 36 | WILTSHIRE. | |
| Polstead | 79 | Codford St. Mary's | 49, 76 |
| Raydon | 23, 33, 82 | Malmsbury Abbey Church | 15, 50, 62 |
| Redgrave | 29, 83, 90 | Salisbury Cathedral | 35, 65 |
| Rickenhall | 24, 85 | South Newton | 18 |
| St. Mary's, Bury | 96 | St. John's Church, Devizes | 37 |
| St. Mary, Stratford | 31, 55, 84, 86 | Wichford | 88 |
| Stoke | 99 | WORCESTERSHIRE. | |
| Stuston | 92 | Abbot's Tower, Eversham | 81 |
| Woolpit | 96 | YORKSHIRE. | |
| SURREY. | | Adel | 76, 91 |
| Bishop's Palace, Southwark | 42 | Beverley Minster | 32, 82 |
| Merstham | 64, 75, 81, 89 | Bubwith | 76 |
| Oakham | 20 | Fountain's Abbey | 15 |
| Shiere | 89 | Hedon | 90 |
| SUSSEX. | | Holy Trinity, Hull | 42 |
| Arundel | 102 | Howden | 27 |
| Boxgrove | 79 | Ripon Cathedral | ib. |
| Chichester Cathedral | 14, 42, 82 | Rivaulx Abbey | 2 |
| Clymping | 12, 17, 18, 34, 38, 54, 78, 82, 86, 90, 92 | Rudston | 27 |
| Hangleton | 20 | Selby Abbey | 29 |
| Keymer | 34, 76 | Skelton | 55, 60, 66, 78 |
| Lindfield | 37, 55, 80 | St. George's, Doncaster | 38, 85, 87 |
| New Haven | 37 | St. Patrick's, Pattrington | 52 |
| New Shoreham | 14, 52, 77, 81 | Whitby Abbey | 2, 19, 28 |
| Old Shoreham | 92 | York Cathedral | 17, 28, 33, 66, 99, 101 |
| Ovingdean | 76 | | |
| Piecombe | 76 | | |

INDEX TO ILLUSTRATIONS (a).

| WINDOWS. | NO. OF LIGHTS. | FIGURE | PAGE | SECTION | PLATE |
|--|----------------|--------|-------|----------------------------|-------|
| Waltham Abbey Church | one | . . . | . . . | I. Norman | 3 |
| Interior of same | one | . . . | . . . | I. Ditto | 3 |
| Darent Church, Kent | triplet | . . . | . . . | I. Ditto | 2 |
| Tangmere Church, Sussex | one | . . . | 12 | | |
| Waltham Abbey Church | circular | . . . | 14 | | |
| New Haven, Sussex | belfry | . . . | 37 | | |
| *Southeast Church, Sussex | one | 1 | | | |
| *Stourbridge, Cambridgeshire | one | 2 | | | |
| *Nateley, Hampshire | one | 3 | | | |
| *Interior of same | | 4 | | | |
| *Waltham Abbey Church | clear story | 5 | | | |
| Clymping, Sussex | one | . . . | . . . | I. Semi-Norman | 5 |
| *New Shoreham, Sussex | | 6 | | | |
| Stoke Pogis, Bucks | couplet | . . . | . . . | I. Early English | 1 |
| Great Wenham, Suffolk | triplet | . . . | . . . | I. Ditto | 1 |
| Shorne, Kent | lancet | . . . | . . . | I. Ditto | 1 |
| Ovington, Hampshire | lancet | . . . | . . . | I. Ditto | 1 |
| Eastwick, Herts | lancet | . . . | . . . | I. Ditto | 1 |
| Wivelsfield, Sussex | triplet | . . . | . . . | I. Ditto | 4 |
| Lindfield, Sussex | triplet | . . . | . . . | I. Ditto | 4 |
| Clymping, Sussex | lancet | . . . | . . . | I. Ditto | 4 |
| Hangleton, Sussex | lancet | . . . | . . . | I. Ditto | 4 |
| Lindfield, Sussex | quatrefoil | . . . | . . . | I. Ditto | 4 |
| Little Wenham, Suffolk | two | . . . | . . . | I. Ditto | 5 |
| Lindfield, Sussex | two | . . . | . . . | I. Ditto | 5 |
| Oundle, Northamptonshire | five lancets | . . . | . . . | I. Ditto | 7 |
| Interior of same | | . . . | . . . | I. Ditto | 7 |
| Raydon, Suffolk, North side | lancet | . . . | . . . | I. Ditto | 8 |
| Ditto Ditto, South side | lancet | . . . | . . . | I. Ditto | 8 |
| Wiley, Wilts | triplet | . . . | . . . | I. Ditto | 9 |
| Meopham, Kent | three | . . . | . . . | I. Ditto | 10 |
| Brockworth, Gloucestershire | lancet | . . . | . . . | I. Ditto | 11 |
| Exterior of same | | . . . | . . . | I. Ditto | 11 |
| Meopham, Kent | three | . . . | . . . | I. Ditto | 11 |
| Barnwell, Cambridgeshire | triplet | . . . | . . . | I. Ditto | 12 |
| Great Casterton, Rutland | lancet | . . . | . . . | I. Ditto | 13 |
| Raydon, Suffolk | two | . . . | . . . | I. Ditto | 13 |
| St. Bartholomew, Sandwich | triplet | . . . | . . . | I. Ditto | 15 |
| Exterior of same | | . . . | . . . | I. Ditto | 15 |
| Hythe, Kent | lancet | . . . | . . . | I. Ditto | 17 |
| Stoke Albany, Northants | two | . . . | . . . | I. Ditto | 17 |
| Hythe, Kent | lancet | . . . | . . . | I. Ditto | 20 |
| Tinwell, Rutland | triplet | . . . | . . . | I. Ditto | 20 |
| Great Casterton, Rutland | one | . . . | . . . | I. Ditto | 20 |
| Manton, Rutland | lancet | . . . | 17 | | |
| Tangmere, Sussex | lancet | . . . | 17 | | |
| South Newton, Wiltshire | couplet | . . . | 18 | | |
| Glapthorne, Northamptonshire | } two | . . . | 21 | | |
| Ditto Ditto | | | | | |
| Ditto Ditto | | | | | |

(a) Those marked with an asterisk are in the Appendix Plates.

| WINDOWS— <i>continued.</i> | NO. OF LIGHTS. | FIGURE | PAGE | SECTION | PLATE |
|--|----------------|--------|------|--------------------|-------|
| Aldwinkle, Northamptonshire . . . | four | . . . | 22 | | |
| Dunton Bassett, Leicestershire . . . | three | . . . | 24 | | |
| Evington, Leicestershire . . . | four | . . . | 25 | | |
| Ditto Ditto . . . | four | . . . | 25 | | |
| Westhampton, Sussex . . . | lancet | . . . | 33 | | |
| Achurch, Northamptonshire . . . | lancet | . . . | 39 | | |
| *Clymping, Sussex . . . | lancet | 8 | | | |
| *Lindfield, Sussex . . . | lancet | 9 | | | |
| *Winnal Magdalen, Hampshire . . . | lancet | 10 | | | |
| *Clymping, Sussex . . . | lancet | 11 | | | |
| *Thanington, Kent . . . | lancet | 12 | | | |
| *Hythe, Kent . . . | couplet | 13 | | | |
| *Great Wenham, Suffolk . . . | couplet | 14 | | | |
| *Ringstead, Northamptonshire . . . | lancet | 15 | | | |
| *Hartley, Kent . . . | couplet | 16 | | | |
| *Blakeney, Norfolk . . . | seven lancets | 17 | | | |
| *Lyddington, Berkshire . . . | three | 18 | | | |
| *Felmarsham, Bedfordshire . . . | two | 19 | | | |
| *Belgrave, Leicestershire . . . | two | 20 | | | |
| *Grafton Underwood, Northamptonshire . . . | two | 21 | | | |
| *Cranford St. Andrew's, Northamptonshire . . . | two | 22 | | | |
| *Cranford St. John, Northamptonshire . . . | three | 23 | | | |
| *Doddington, Northamptonshire . . . | three | 24 | | | |
| *Cransley, Northamptonshire . . . | three | 25 | | | |
| *Stoke Albany, Northamptonshire . . . | three | 26 | | | |
| *Little Harrowden, Northamptonshire . . . | four | 27 | | | |
| *Doddington, Northamptonshire . . . | three | 28 | | | |
| *Oundle, Northamptonshire . . . | three | 29 | | | |
| Northfleet, Kent . . . | two | . . . | | I. Decorated . . . | 1 |
| Ditto Ditto . . . | two | . . . | | I. Ditto . . . | 1 |
| Ditto Ditto . . . | three | . . . | | I. Ditto . . . | 2 |
| Chesham Bois, Buckinghamshire . . . | two | . . . | | I. Ditto . . . | 2 |
| Chenies, Buckinghamshire . . . | two | . . . | | I. Ditto . . . | 3 |
| Chesham, Buckinghamshire . . . | two | . . . | | I. Ditto . . . | 3 |
| Waltham Abbey Church . . . | | . . . | | I. Ditto . . . | 3 |
| Ditto Ditto interior . . . | circular | . . . | | I. Ditto . . . | 3 |
| Ditto Ditto . . . | | . . . | | I. Ditto . . . | 4 |
| Ditto Ditto . . . | two | . . . | | I. Ditto . . . | 4 |
| St. Michael's, St. Alban . . . | two | . . . | | I. Ditto . . . | 4 |
| Roydon, Essex . . . | two | . . . | | I. Ditto . . . | 5 |
| Northfleet, Kent . . . | two | . . . | | I. Ditto . . . | 5 |
| Lindfield, Sussex . . . | five | . . . | | I. Ditto . . . | 6 |
| Holbeach, Lincolnshire . . . | four | . . . | | I. Ditto . . . | 7 |
| Capel St. Mary, Suffolk . . . | two | . . . | | I. Ditto . . . | 8 |
| St. Margaret's, Hertfordshire . . . | two | . . . | | I. Ditto . . . | 8 |
| St. Mary's Stratford, Suffolk . . . | four | . . . | | I. Ditto . . . | 9 |
| Holbeach, Lincolnshire . . . | three | . . . | | I. Ditto . . . | 11 |
| Ditto Ditto . . . | three | . . . | | I. Ditto . . . | 12 |
| Roydon, Essex . . . | two | . . . | | I. Ditto . . . | 13 |
| St. Margaret's, Hertfordshire . . . | four | . . . | | I. Ditto . . . | 13 |
| Boughton Aluph, Kent . . . | four | . . . | | I. Ditto . . . | 15 |
| Sleaford, Lincolnshire . . . | four | . . . | | I. Ditto . . . | 18 |
| Herne, Kent . . . | three | . . . | | I. Ditto . . . | 20 |
| Chartham, Kent . . . | two | . . . | | I. Ditto . . . | 22 |
| Sleaford, Lincolnshire . . . | four | . . . | | I. Ditto . . . | 26 |
| Bottisham, Cambridgeshire . . . | three | . . . | | I. Ditto . . . | 27 |
| Trumpington, Cambridgeshire . . . | five | . . . | | I. Ditto . . . | 29 |
| Worstead, Norfolk . . . | | . . . | | I. Ditto . . . | 36 |
| Ditto Ditto . . . | | . . . | | I. Ditto . . . | 36 |
| Paston, Norfolk . . . | | . . . | | I. Ditto . . . | 36 |
| Hingham, Norfolk . . . | | . . . | | I. Ditto . . . | 36 |
| Ditto Ditto . . . | | . . . | | I. Ditto . . . | 36 |
| Ditto Ditto . . . | | . . . | | I. Ditto . . . | 36 |
| Rushden, Northamptonshire . . . | | . . . | | I. Ditto . . . | 36 |
| Fulmodistone, Norfolk . . . | | . . . | | I. Ditto . . . | 36 |
| Badgeworth, Gloucestershire . . . | two | . . . | | I. Ditto . . . | 38 |

| WINDOWS— <i>continued.</i> | NO. OF LIGHTS. | FIGURE | PAGE | SECTION | PLATE |
|--|----------------|--------|------|------------------------|-------|
| Cottingham, Northamptonshire . . . | four | . . . | 27 | | |
| Sawbridgeworth, Hertfordshire . . . | three | . . . | 27 | | |
| Southfleet, Kent . . . | two | . . . | 27 | | |
| Rigstead, Northamptonshire . . . | five | . . . | 27 | | |
| Holton St. Mary, Suffolk . . . | two | . . . | 27 | | |
| St. Alban's Abbey Church . . . | two | . . . | 28 | | |
| Southfleet, Kent . . . | two | . . . | 28 | | |
| Sawbridgeworth, Hertfordshire . . . | three | . . . | 28 | | |
| Wheathampstead, Hertfordshire . . . | four | . . . | 30 | | |
| Rouen, Normandy . . . | three | . . . | 30 | | |
| Tunstead, Norfolk . . . | three | . . . | 31 | | |
| Farndish, Bedfordshire . . . | two | . . . | 33 | | |
| Brandon, Norfolk . . . | five | . . . | 34 | | |
| Bicker, Lincolnshire . . . | two | . . . | 34 | | |
| Southfleet, Kent . . . | two | . . . | 34 | | |
| Keymer, Sussex . . . | two | . . . | 34 | | |
| Cottingham, Northamptonshire . . . | . . . | . . . | 35 | | |
| Meopham, Kent . . . | . . . | . . . | 36 | | |
| Filby, Norfolk . . . | . . . | . . . | 36 | | |
| St. Alban's Abbey Church . . . | lancet | . . . | 39 | | |
| Southfleet, Kent . . . | two | . . . | 41 | | |
| Shorne, Kent . . . | two | . . . | 41 | | |
| Northfleet, Kent . . . | two | . . . | 41 | | |
| St. Nicholas, Colechester . . . | two | . . . | 42 | | |
| Harbledown, Kent . . . | two | . . . | 43 | | |
| Southfleet, Kent . . . | five | . . . | 43 | | |
| *Barnwell, Northamptonshire . . . | two | 30 | | | |
| *Burton, Leicestershire . . . | two | 31 | | | |
| *Ditto Ditto . . . | two | 32 | | | |
| *Ditto Ditto . . . | two | 33 | | | |
| *Fleet, Lincolnshire . . . | three | 34 | | | |
| *Lyddington, Berkshire . . . | two | 35 | | | |
| *Witham, Essex . . . | two | 36 | | | |
| *St. Alban's Abbey Church . . . | two | 37 | | | |
| *Hingham, Norfolk . . . | three | 38 | | | |
| *Exton, Rutlandshire . . . | . . . | 39 | | | |
| *Mickleham, Surrey . . . | three | 40 | | | |
| *Exton, Rutlandshire . . . | . . . | 41 | | | |
| *Tilsworth, Bedfordshire . . . | three | 42 | | | |
| *Cranford St. Andrew's, Northamptonshire . . . | . . . | 43 | | | |
| *Interior of ditto . . . | . . . | 46 | | | |
| *Trunch, Norfolk . . . | . . . | 44 | | | |
| *Gosgrove, Northamptonshire . . . | . . . | 45 | | | |
| *Shiere, Surrey . . . | three | 47 | | | |
| *Wimington, Bedfordshire . . . | five | 48 | | | |
| *Shiere, Surrey . . . | four | 49 | | | |
| *Sutton at Hone, Kent . . . | three | 53 | | | |
| *Ely . . . | . . . | 50 | | | |
| *Ditto, Interior . . . | . . . | 52 | | | |
| *Long Staunton, Cambridgeshire . . . | four | 54 | | | |
| *Little Waltham, Essex . . . | three | 55 | | | |
| *Ashwell, Rutlandshire . . . | three | 62 | | | |
| *Harbledown, Kent . . . | two | 63 | | | |
| *Wimington, Bedfordshire . . . | three | 66 | | | |
| *Ditto Ditto . . . | two | 67 | | | |
| *Cley, Norfolk . . . | three | 68 | | | |
| *Billington, Bedfordshire . . . | two | 69 | | | |
| King's Worthly, Hampshire . . . | two | . . . | | I. Perpendicular . . . | 3 |
| Basingstoke, Hampshire . . . | four | . . . | | I. Ditto . . . | 4 |
| Northfleet, Kent . . . | three | . . . | | I. Ditto . . . | 5 |
| Chalk, Kent . . . | one | . . . | | I. Ditto . . . | 5 |
| Dummer, Hampshire . . . | one | . . . | | I. Ditto . . . | 5 |
| Wilton, Norfolk . . . | one | . . . | | I. Ditto . . . | 10 |
| Uffington, Lincolnshire . . . | three | . . . | | I. Ditto . . . | 13 |
| Lavenham, Suffolk . . . | . . . | . . . | | I. Ditto . . . | 13 |

| WINDOWS— <i>continued.</i> | NO. OF LIGHTS. | FIGURE | PAGE | SECTION | PLATE |
|--------------------------------------|----------------|--------|------|------------------|-------|
| Lavenham, Suffolk, Interior | | | | I. Perpendicular | 13 |
| West Tarring, Sussex | five | | | I. Ditto | 16 |
| Chesham, Buckinghamshire | three | | | I. Ditto | 18 |
| Ristangles, Suffolk | three | | | I. Ditto | 18 |
| Westwick, Norfolk | | | | I. Ditto | 22 |
| St. Lawrence, Norwich | | | | I. Ditto | 22 |
| St. George's, Norwich | | | | I. Ditto | 22 |
| Bradfield, Norfolk | | | | I. Ditto | 22 |
| St. Peter's, Norwich | | | | I. Ditto | 22 |
| Bradfield, Norfolk | | | | I. Ditto | 22 |
| Coltishall, Norfolk | | | | I. Ditto | 22 |
| Little Shelford, Cambridgeshire | five | | | I. Ditto | 23 |
| Churchdown, Gloucestershire | three | | 24 | | |
| Ashby St. Ledger's, Northamptonshire | three | | 32 | | |
| Blakeney, Norfolk | four | | 33 | | |
| Humberstone, Leicestershire | three | | 36 | | |
| Hunworth, Norfolk | | | 38 | | |
| Winterton, Norfolk | | | 39 | | |
| Rushton Lodge | | | 47 | | |
| *Chellington, Bedfordshire | four | 56 | | | |
| *Odell, Bedfordshire | four | 57 | | | |
| *St. John's, Stamford | five | 58 | | | |
| *Cirencester, Gloucestershire | four | 59 | | | |
| *Felmarsham, Bedfordshire | three | 61 | | | |
| *Donington, Lincolnshire | five | 60 | | | |
| *Wootton, Bedfordshire | three | 65 | | | |
| *St. Peter's, Northampton | three | 64 | | | |

MOLDINGS.

| | | | | | |
|--------------------------------|-------------------|--|--|------------------|----|
| Caps, Bases, and Stringcourses | | | | I. Decorated | 30 |
| Caps, Bases, and Stringcourses | | | | I. Ditto | 30 |
| Caps, Bases, and Stringcourses | | | | I. Early English | 24 |
| Worsted, Norfolk | | | | I. Decorated | 35 |
| Tunstead, Norfolk | | | | I. Perpendicular | 26 |
| Deopham, Norfolk | | | | I. Ditto | 25 |
| Kenninghall, Norfolk | | | | I. Ditto | 25 |
| Haslingfield, Cambridgeshire | | | | I. Ditto | 25 |
| *Caldecott, Northants | Basement moldings | | | | |
| *Ringstead, Northants | | | | | |
| *Fen Ditton, Cambridgeshire | | | | | |
| *Heckington, Lincolnshire | | | | | |
| *Wissendine, Rutlandshire | | | | | |
| *Exton, Rutlandshire | String | | | | |
| *Greetham, Rutlandshire | | | | | |
| Gosgrove, Northamptonshire | | | | | |
| St. Martin's, Leicester | Corbel tables | | | | |
| Bicker, Lincolnshire | | | | | |
| Oadby, Leicestershire | | | | | |
| *Cottesmore, Rutlandshire | Spire tables | | | | |
| *Greetham, Rutlandshire | | | | | |
| *Wellingborough, Northants | | | | | |
| *Achurch, Northants | String | | | | |
| Sandridge, Hertfordshire | | | | | |
| Bapechild, Kent | | | | | |
| Skelton, York | | | | | |

DOORWAYS.

| | | | | | |
|---------------------------|--|--|--|-----------|---|
| Nately, Hampshire | | | | I. Norman | 1 |
| Old Shoreham, Sussex | | | | I. Ditto | 2 |
| Wootton, Gloucestershire | | | | I. Ditto | 4 |
| Sempringham, Lincolnshire | | | | I. Ditto | 6 |

| DOORWAYS. | FIGURE | PAGE | SECTION | PLATE |
|--|-----------|-----------|----------------------------|-------|
| Orpington, Kent | | | I. Semi-Norman | 1 |
| Meopham, Kent | | | I. Early English | 3 |
| Holton St. Mary's, Suffolk | | | I. Ditto | 3 |
| Warmington, Northamptonshire | | | I. Ditto | 21 |
| St. Martin's, Leicester | | | I. Ditto | 23 |
| *Barnwell, Northamptonshire | } Plate 7 | | | |
| *Felmarsham, Bedfordshire | | | | |
| *St. Margaret's, Hertfordshire | | | | |
| *Burton, Leicestershire | | | | |
| Sutton at Hone, Kent | | | I. Decorated | 1 |
| Holbeach, Lincolnshire | | | I. Ditto | 10 |
| Brandon, Norfolk | | | I. Ditto | 12 |
| Milton, Kent | | | I. Ditto | 14 |
| Heckington, Lincolnshire | | | I. Ditto | 23 |
| Swatton, Lincolnshire* | | | I. Ditto | 23 |
| North Mimms, Hertfordshire | | | I. Ditto | 25 |
| Cley, Norfolk | | | I. Ditto | 39 |
| Fen Ditton | | 51 | | |
| Ewerby, Lincolnshire | | 68 | | |
| Aldwinkle, Northamptonshire | | 70 | | |
| Leir, Leicestershire | | 74 | | |
| Trunch, Norfolk | | 75 | | |
| Felmarsham, Bedfordshire | | 75 | | |
| Higham Ferrars | | 76 | | |
| Weekley, Northamptonshire | | 76 | | |
| St. Alban's Abbey Church | | | I. Perpendicular | 1 |
| Basingstoke, Hampshire | | | I. Ditto | 3 |
| Lavenham, Suffolk | | | I. Ditto | 6 |
| Ditto Ditto, Interior | | | I. Ditto | 7 |
| Chesham, Buckinghamshire | | | I. Ditto | 17 |
| Coltishall, Norfolk | | | I. Ditto | 20 |
| Toweester, Northamptonshire | | 72 | | |
| Shorne, Kent | | 73 | | |
| Islip, Northamptonshire | | 73 | | |
| Cransley, Northamptonshire | | 74 | | |
| Grundisburgh, Suffolk | | 75 | | |
| Merstham, Surrey | | 75 | | |

PIERS AND ARCHES.

| | | | | |
|---------------------------------------|-----------|-----------|----------------------------|----|
| New Shoreham, Sussex | | | I. Semi-Norman | 2 |
| Ditto Ditto | | | I. Ditto | 3 |
| Ditto Ditto | | | I. Ditto | 4 |
| Codford St. Mary, Wiltshire | | | I. Ditto | 5 |
| *Polstead, Suffolk | | | | |
| St. Mary's Cray, Kent | | | I. Early English | 2 |
| Matehing, Essex | | | I. Ditto | 2 |
| Erith, Kent | | | I. Ditto | 2 |
| Clymping, Sussex | | | I. Ditto | 5 |
| Preston, Sussex | | | I. Ditto | 5 |
| Westminster Abbey Church | | 8 | | |
| Aeton Bunnell, Shropshire | | 77 | | |
| Barnwell, Northamptonshire | | 78 | | |
| Eaton Bray, Bedfordshire | | 80 | | |
| *Boxgrove, Sussex | | | | |
| *St. Martin's, Leicester | | | | |
| Bottisham, Cambridgeshire | | | I. Decorated | 16 |
| Brookworth, Gloucestershire | | | I. Ditto | 21 |
| Boughton Aluph, Kent | | | I. Ditto | 21 |
| Morton, Lincolnshire | | | I. Ditto | 21 |
| Trumpington, Cambridgeshire | | | I. Ditto | 21 |
| Lindfield, Sussex | | | I. Perpendicular | 14 |

| PIERS AND ARCHES— <i>continued.</i> | | | | | FIGURE | PAGE | SECTION | PLATE |
|--|---|---|---|---|--------|------|----------------------------|-------|
| Lavenham, Suffolk | . | . | . | . | . | . | I. Ditto | 14 |
| Westminster Abbey Church | . | . | . | . | . | 8 | | |
| Ditto Ditto | . | . | . | . | . | 7 | | |
| PANELS. | | | | | | | | |
| Lavenham, Suffolk | . | . | . | . | . | . | I. Perpendicular | 8 |
| St. Mary's, Stratford, Suffolk | . | . | . | . | . | . | I. Ditto | 19 |
| Eye, Suffolk | . | . | . | . | . | . | I. Ditto | 19 |
| DIAPERS. | | | | | | | | |
| Westminster Abbey Church | . | . | . | . | . | . | I. Early English | 19 |
| Hatfield Broad Oaks, Essex | . | . | . | . | . | . | I. Ditto | 19 |
| St. Alban's Abbey Church | . | . | . | . | . | . | I. Decorated | 24 |
| Westminster Abbey Church | . | . | . | . | . | . | I. Ditto | 24 |
| BUTTRESSES. | | | | | | | | |
| Raydon, Suffolk | . | . | . | . | . | . | I. Early English | 14 |
| Little Wenham, Suffolk | . | . | . | . | . | . | I. Ditto | 14 |
| Holbeach, Lincolnshire | . | . | . | . | . | . | I. Decorated | 17 |
| Fen Ditton, Cambridgeshire | . | . | . | . | . | . | I. Ditto | 17 |
| Debenham, Suffolk | . | . | . | . | . | . | I. Ditto | 19 |
| Bottisham, Cambridgeshire | . | . | . | . | . | . | I. Ditto | 19 |
| Achurch, Northamptonshire | . | . | . | . | . | . | I. Early English | 22 |
| St. Margaret's, Leicester | . | . | . | . | . | 82 | | |
| Redgrave, Suffolk | . | . | . | . | . | 83 | | |
| Pythley, Northamptonshire | . | . | . | . | . | 83 | | |
| Besthorpe, Norfolk | . | . | . | . | . | 84 | | |
| Blakeney, Norfolk | . | . | . | . | . | 84 | | |
| St. Mary's, Stratford, Suffolk | . | . | . | . | . | . | I. Perpendicular | 11 |
| Lavenham, Suffolk | . | . | . | . | . | . | I. Ditto | 12 |
| Ryall, Rutlandshire | . | . | . | . | . | . | I. Ditto | 24 |
| New Walsingham, Norfolk | . | . | . | . | . | . | I. Ditto | 24 |
| PARAPETS. | | | | | | | | |
| Heckington, Lincolnshire | . | . | . | . | . | . | I. Decorated | 37 |
| Ditto Ditto | . | . | . | . | . | . | I. Ditto | 37 |
| Evington, Leicestershire | . | . | . | . | . | . | I. Ditto | 37 |
| Lavenham, Suffolk | . | . | . | . | . | . | I. Perpendicular | 12 |
| St. Mary's, Stratford, Suffolk | . | . | . | . | . | . | I. Ditto | 11 |
| CROSSES. | | | | | | | | |
| Barnack, Northamptonshire | . | . | . | . | . | 87 | | |
| Witchford, Wiltshire | . | . | . | . | . | . | I. Early English | 16 |
| Edith, Weston, Rutlandshire | . | . | . | . | . | . | I. Ditto | 16 |
| Helpringham, Lincolnshire | . | . | . | . | . | . | I. Ditto | 16 |
| St. Mary's, Stamford | . | . | . | . | . | . | I. Ditto | 16 |
| Little Casterton, Rutlandshire | . | . | . | . | . | . | I. Ditto | 16 |
| Barnwell, Northamptonshire | . | . | . | . | . | . | I. Ditto | 25 |
| St. Patrick's, Dublin | . | . | . | . | . | . | I. Ditto | 25 |
| Tinwell, Rutlandshire | . | . | . | . | . | . | I. Decorated | 28 |
| Ewerby, Lincolnshire | . | . | . | . | . | . | I. Ditto | 28 |
| Peterborough, Northamptonshire | . | . | . | . | . | . | I. Ditto | 28 |
| Peakirk, Northamptonshire | . | . | . | . | . | . | I. Ditto | 28 |
| Methwold, Norfolk | . | . | . | . | . | . | I. Ditto | 28 |
| St. Mary's, Norwich | . | . | . | . | . | . | I. Ditto | 33 |


| CROSSES— <i>continued.</i> | | | | | FIGURE | PAGE | SECTION | PLATE |
|---------------------------------|---|---|---|---|--------|------|------------------|-------|
| Ludham, Norfolk | . | . | . | . | . | . | I. Decorated | 33 |
| Ditto Ditto | . | . | . | . | . | . | I. Ditto | 33 |
| Hingham, Norfolk | . | . | . | . | . | . | I. Ditto | 33 |
| Haslingfield, Cambridgeshire | . | . | . | . | . | . | I. Ditto | 33 |
| Stoke Ferry, Norfolk | . | . | . | . | . | . | I. Perpendicular | 15 |
| Morton, Lincolnshire | . | . | . | . | . | . | I. Ditto | 15 |
| Brandon, Norfolk | . | . | . | . | . | . | I. Ditto | 15 |
| Billingborough, Lincolnshire | . | . | . | . | . | . | I. Ditto | 15 |
| West Lynn, Norfolk | . | . | . | . | . | . | I. Ditto | 15 |
| Gunthorpe, Norfolk | . | . | . | . | . | . | I. Ditto | 21 |
| Trunch, Norfolk | . | . | . | . | . | . | I. Ditto | 21 |
| Oakham, Rutlandshire | . | . | . | . | . | . | I. Ditto | 21 |
| Ditto Ditto | . | . | . | . | . | . | I. Ditto | 21 |
| Stody, Norfolk | . | . | . | . | . | . | I. Ditto | 21 |
| FONTS. | | | | | | | | |
| Weston, Lincolnshire | . | . | . | . | . | . | I. Early English | 27 |
| Redgrave, Suffolk | . | . | . | . | . | . | I. Decorated | 32 |
| Clymping, Sussex | . | . | . | . | . | . | I. Perpendicular | 28 |
| SEDILIA. | | | | | | | | |
| *Great Wenham, Suffolk | . | . | . | . | 14 | . | | |
| Preston, Sussex | . | . | . | . | . | . | I. Early English | 6 |
| Cobham, Kent | . | . | . | . | . | . | I. Perpendicular | 9 |
| PISCINA. | | | | | | | | |
| Widelsfield, Sussex | . | . | . | . | . | . | I. Early English | 6 |
| CHAMFER TERMINATIONS. | | | | | | | | |
| Twenty Specimens | . | . | . | . | . | . | I. Early English | 26 |
| Ten Specimens | . | . | . | . | . | . | I. Decorated | 34 |
| GABLETS. | | | | | | | | |
| Capel St. Mary, Suffolk | . | . | . | . | . | . | I. Decorated | 31 |
| Swafeld, Norfolk | . | . | . | . | . | . | I. Ditto | 31 |
| Trunch, Norfolk | . | . | . | . | . | . | I. Ditto | 31 |
| Little Shelford, Cambridgeshire | . | . | . | . | . | . | I. Ditto | 31 |
| Ditto Ditto | . | . | . | . | . | . | I. Ditto | 31 |
| Stapleford, Cambridgeshire | . | . | . | . | . | . | I. Ditto | 31 |
| Coltishall, Norfolk | . | . | . | . | . | . | I. Ditto | 31 |
| Tunstead, Norfolk | . | . | . | . | . | . | I. Ditto | 31 |
| DRIPSTONE TERMINATIONS. | | | | | | | | |
| Swafton, Lincolnshire | . | . | . | . | . | . | I. Early English | 18 |
| St. Margaret's, Hertfordshire | . | . | . | . | . | . | I. Ditto | 18 |
| Debenham, Suffolk | . | . | . | . | . | . | I. Ditto | 18 |
| Little Wenham, Suffolk | . | . | . | . | . | . | I. Ditto | 18 |
| St. Cross, Hampshire | . | . | . | . | . | . | I. Ditto | 18 |
| Westminster Abbey Church | . | . | . | . | . | . | I. Ditto | 18 |
| Four Specimens | . | . | . | . | . | . | I. Decorated | 34 |
| Twelve Specimens | . | . | . | . | . | . | I. Perpendicular | 27 |

| ROOFS. | | FIGURE | PAGE | SECTION | PLATE |
|-----------------------------|--|--------|------|------------------|------------|
| Wymondham, Norfolk | | | | II. Woodwork | 17, 18, 19 |
| Capel St. Mary, Suffolk | | | | II. Ditto | 22, 23 |
| Stuston, Suffolk | | | | II. Ditto | 24 |
| Grundisburgh, Suffolk | | | | II. Ditto | 26, 27 |
| SEATS. | | | | | |
| Great Waltham | | | | II. Woodwork | 1 |
| Bentley, Suffolk | | | | II. Ditto | 5 |
| Comberton, Cambridgeshire | | | | II. Ditto | 29 |
| FINIALS. | | | | | |
| Bentley, Suffolk | | | | II. Woodwork | 6 |
| Great Wenham, Suffolk | | | | II. Ditto | 6 |
| Brandon, Norfolk | | | | II. Ditto | 6 |
| Chesham Bois, Hertfordshire | | | | II. Ditto | 6 |
| Nantwich, Cheshire | | | | II. Ditto | 16 |
| Stoke, Suffolk | | | | II. Ditto | 16 |
| Stoke, Suffolk | | | | II. Ditto | 16 |
| Howell, Lincolnshire | | | | II. Ditto | 16 |
| St. Mary Stratton, Norfolk | | | | II. Ditto | 20 |
| Ditto Ditto | | | | II. Ditto | 20 |
| Great Wenham, Suffolk | | | | II. Ditto | 20 |
| A Church in Norfolk | | | | II. Ditto | 20 |
| Debenham, Suffolk | | | | II. Ditto | 30 |
| PORCHES. | | | | | |
| Aldham, Essex | | | | II. Woodwork | 12, 13 |
| SCREENS. | | | | | |
| Waltham Abbey Church | | | | II. Woodwork | 7 |
| Barton, Cambridgeshire | | | | II. Ditto | 10 |
| SPANDRELS. | | | | | |
| Barton, Cambridgeshire | | | | II. Woodwork | 11 |
| Bottisham, Cambridgeshire | | | | II. Ditto | 14 |
| Doneaster, Yorkshire | | | | II. Ditto | 25 |
| Stoke, Suffolk | | | | II. Ditto | 25 |
| DOORS. | | | | | |
| St. Alban's Abbey Church | | | | II. Woodwork | 4 |
| Wells Cathedral | | | | II. Ditto | 8 |
| Stoke, Suffolk | | | | II. Ditto | 15 |
| Holbeach, Lincolnshire | | | | I. Decorated | 10 |
| Milton, Kent | | | | I. Ditto | 14 |
| North Minns, Hertfordshire | | | | I. Ditto | 25 |
| Lavenham, Suffolk | | | | I. Perpendicular | 6, 7 |
| Chesham, Buckinghamshire | | | | I. Ditto | 17 |
| Coltishall, Norfolk | | | | I. Ditto | 20 |
| PANELS. | | | | | |
| Great Waltham, Essex | | | | II. Woodwork | 2 |

| PANELS— <i>continued.</i> | FIGURE | PAGE | SECTION | PLATE |
|--|-----------|-----------|-------------------------|-------|
| Great Waltham, Essex | | | II. Woodwork | 3 |
| Cirencester, Gloucestershire | | | II. Ditto | 14 |
| Bottisham, Cambridgeshire | | | II. Ditto | 14 |
| Chester Cathedral | | | II. Ditto | 21 |
| Crowcombe, Somersetshire | | | II. Ditto | 31 |
| Bishop's Lydeard, Somersetshire | | | II. Ditto | 31 |
| Little Shelford, Cambridgeshire | | | II. Ditto | 31 |
| Worstead, Norfolk | | | II. Ditto | 31 |
| BOSSSES. | | | | |
| Brockworth, Gloucestershire | | | II. Woodwork | 9 |
| Brockworth, Gloucestershire | | | II. Ditto | 28 |
| Diss, Norfolk | | | II. Ditto | 28 |
| Haslingfield, Cambridgeshire | | | II. Ditto | 28 |
| STRINGS. | | | | |
| Cirencester, Gloucestershire | | | II. Woodwork | 9 |
| Brockworth, Gloucestershire | | | II. Ditto | 9 |
| Trunch, Norfolk | | | II. Ditto | 28 |
| Rushden, Northamptonshire | | | II. Ditto | 30 |
| Martham, Norfolk | | | II. Ditto | 30 |
| CUSP TERMINATIONS. | | | | |
| Barton, Cambridgeshire | | | II. Woodwork | 11 |
| Higham Ferrars, Northamptonshire | | | II. Ditto | 10 |
| CLOSING RINGS. | | | | |
| St. Alban's Abbey Church | | | II. Metalwork | 2 |
| St. Mary's, Stratford | | | II. Ditto | 2 |
| Westminster Abbey Church | | | II. Ditto | 2 |
| Cirencester, Gloucestershire | | | II. Ditto | 3 |
| Barton, Cambridgeshire | | | II. Ditto | 3 |
| Brockworth, Gloucestershire | | | II. Ditto | 3 |
| Eyre, Suffolk | | | II. Ditto | 5 |
| Aldham, Essex | | | II. Ditto | 5 |
| Colly Weston, Northamptonshire | | | II. Ditto | 7 |
| Diss, Norfolk | | | II. Ditto | 7 |
| Bapchild, Kent | | | II. Ditto | 7 |
| Hythe, Kent | | | II. Ditto | 7 |
| Haconby, Lincolnshire | | | II. Ditto | 7 |
| Westminster Abbey Church | | | II. Ditto | 7 |
| St. Mary's, Norwich | | | II. Ditto | 8 |
| Floore, Northamptonshire | | | II. Ditto | 9 |
| Eaton Bray, Bedfordshire | | | II. Ditto | 11 |
| Ashby St. Ledger, Northamptonshire | | | II. Ditto | 12 |
| Exton, Rutlandshire | | | II. Ditto | 12 |
| St. Nicholas, Gloucester | | | II. Ditto | 12 |
| Martham, Norfolk | | | II. Ditto | 12 |
| Filby, Norfolk | | | II. Ditto | 13 |
| HINGES. | | | | |
| Erith, Kent | | | II. Metalwork | 1 |
| Westminster Abbey Church | | | II. Ditto | 1 |
| St. Margaret Roding, Essex | | | II. Ditto | 1 |
| St. Peter's, Colchester | | | II. Ditto | 1 |

| HINGES— <i>continued.</i> | | | | | FIGURE | PAGE | SECTION | PLATE |
|---------------------------------|---|---|---|---|--------|------|---------------|-------|
| Northfleet, Kent | . | . | . | . | . | . | II. Metalwork | 1 |
| St. Alban's Abbey Church | . | . | . | . | . | . | II. Ditto | 1 |
| Stanstead Church, Hertfordshire | . | . | . | . | . | . | II. Ditto | 1 |
| Hartley, Kent | . | . | . | . | . | . | II. Ditto | 2 |
| Gloucester Cathedral | . | . | . | . | . | . | II. Ditto | 3 |
| Horton Kirby, Kent | . | . | . | . | . | . | II. Ditto | 3 |
| Spalding, Lincolnshire | . | . | . | . | . | . | II. Ditto | 3 |
| Brockworth, Gloucestershire | . | . | . | . | . | . | II. Ditto | 3 |
| Sempringham, Lincolnshire | . | . | . | . | . | . | II. Ditto | 5 |
| Tinwell, Rutlandshire | . | . | . | . | . | . | II. Ditto | 5 |
| St. Mary's, Norwich | . | . | . | . | . | . | II. Ditto | 8 |
| Market Deeping, Lincolnshire | . | . | . | . | . | . | II. Ditto | 9 |
| St. Alban's Abbey Church | . | . | . | . | . | . | II. Ditto | 9 |
| Eaton Bray, Bedfordshire | . | . | . | . | . | . | II. Ditto | 11 |
| Wootton, Bedfordshire | . | . | . | . | . | . | II. Ditto | 13 |
| Sutton at Hone, Kent | . | . | . | . | . | . | II. Ditto | 13 |
| Oundle, Northamptonshire | . | . | . | . | . | . | II. Ditto | 13 |
| STIFFENERS. | | | | | | | | |
| Chester Cathedral | . | . | . | . | . | . | II. Metalwork | 4 |
| York Minster | . | . | . | . | . | . | II. Ditto | 6 |
| Great Casterton, Rutlandshire | . | . | . | . | . | . | II. Ditto | 9 |
| Tunstead, Norfolk | . | . | . | . | . | . | II. Ditto | 9 |
| KEY PLATES. | | | | | | | | |
| Westminster Abbey Church | . | . | . | . | . | . | II. Metalwork | 2 |
| Diss, Norfolk | . | . | . | . | . | . | II. Ditto | 7 |
| Uffington, Lincolnshire | . | . | . | . | . | . | II. Ditto | 7 |
| Tunstead, Norfolk | . | . | . | . | . | . | II. Ditto | 9 |
| Martham, Norfolk | . | . | . | . | . | . | II. Ditto | 13 |











Panel heads from open seats (St. Wultham Ch. Essex)




Centres of Tracery $\frac{1}{16}$ full size








Panel heads from open seats. Gt Waltham Ch Essex.



Centres of tracery.




SCALE OF 0 1 2 3 4 5 6 INCHES





Door from St Alban's Abbey Church, Hertfordshire.


Section on line A.B.
 $\frac{1}{2}$ full size






Open Seats from Bentley Ch. Suffolk.

SCALE OF 1 0 3 6 9 12 FEET




Section at F. 2 in scale.

Section at B. 1/2 full size.






Finial from Bunting Church, Suffolk.



Finial from Great Wingham Church, Suffolk.



B


Finial from Draxton Church, Suffolk.



Finial from Chessham Bois Church, Bucks.

SCALE OF 0 1 2 3 4 5 6 7 INCHES

Parclose from Waltham Abbey Ch. House.




Section of beam




Section of sill





Section of mullion



Section on line AB.



A — B



Centres of circles


SCALE OF 12 9 6 3 0 3 6 9 12 FEET






12 6 0 1 2
SCALE OF FEET.

B




Centres of Tracery.

Lower panels of Door, from Wells Cathedral.



From roof of North Aisle Brockworth Church, Gloucestershire.



From South Chapel Brockworth Ch. Gloucestershire.



From Cirencester Church, Gloucestershire.



From Cirencester Church, Gloucestershire.

B

SECTION II.



Rood screen, from Barton Ch. Cambridgehire.

Details of screen. $\frac{1}{16}$ full size.
Section of beam.




Section A.B.

Section B.C.







SCALE OF FEET 1 2 3 4 5




*Crocket from Roodscreen of
Barton Church, Cambridgeshire.*

1/2 full size



*Commencement
of Crocket*




*Spandrels and termination of tracings, from
Roodscreen of
Barton Church, Cambridgeshire. 1/2 full size.*

B

Woodwork

Section D. E.



Rafters $5 \times 4\frac{1}{2}$

Curved braces $2 \times 3\frac{1}{2}$

Collars $4\frac{1}{2} \times 3\frac{1}{2}$

The section of details are drawn full size

Section E. F.




Section B. C.



Section A. B.




Section C. D.




South Porch Aldham Ch. Essex.

SCALE OF FEET.


South Porch, Aldham Church, Essex.



Section A.B. $\frac{1}{2}$ full size.




Chamfer at C.



Tracery to Porch. 1st scale.



Tracery to W. side of Porch. Bradwell Ch. Essex. $\frac{1}{4}$ scale.




Tracery to E. side of Porch. Bradwell Ch. Essex.

Section looking West.



Centre line.




Plan of Aldham Porch


SCALE OF 0 1 2 3 4 5 6 7 FEET.








Spandrel from Bottisham Church, Cambridgeshire. 2" Scale



From Bottisham Church, Cambridgeshire.



From Cirencester Church, Gloucestershire



*From Bottisham Church, Cambridgeshire.
1½ Scale.*

B

*S. Door of Stoke Church, Suffolk.**drawn to a Scale of $\frac{7}{8}$ of an inch to a foot.**Section C.D.
2nd $\frac{5}{8}$ scale**Section A.B.
2nd $\frac{5}{8}$ scale*




From Nantwich Church Cheshire



From Stoke Church Suffolk.




From Stoke Church, Suffolk.



From Howell Ch. Lincolnshire.

B

SCALE OF 1 2 3 4 5 6 INCHES



Roof over North Side, Wyndham Church, Norfolk.

B

Roof over North Aisle, Wymondham Ch. Norfolk.

Transverse Section.

Purlin, 2ⁱⁿ scale

Section of Cornice
2ⁱⁿ scale.

Hammer beam, 2ⁱⁿ scale.


Ornament in Cornice 1/2 full size.

Longitudinal Section.

SCALE OF 1 2 3 4 5 6 7 8 9 10 FEET

B


Spandrels from roof of Wymondham Ch. Suffolk.



Scale of 1 1/2 in. to a foot.



From St Mary Stratten Church, Norfolk






From Great Wenham Church Suffolk

From a Church in Norfolk




SCALE OF 1 2 3 4 5 FEET



*Panels From Chester Cathedral**1/2nd Scale*



*Roof over Nave of Chapel S^t Mary Church Suffolk
with details 2nd Scale*











B

Roof over Nave of Chapel St. Mary's Church Suffolk

Roof over porch Stutton Church, Suffolk.*Longitudinal section*


Scale of  feet

B

Spandrels from Doncaster Church, Yorkshire*Spandrel from
Stoke Church,
Suffolk**Spandrel from
Stoke Church,
Suffolk**Spandrels from Doncaster Church, Yorkshire**Spandrel from
Stoke Church,
Suffolk**Spandrel from
Stoke Church,
Suffolk*

B




Scale of 0 1 2 3 4 5 6 Inches



Roof over the Nave of Grandisburgh Church, Suffolk.

B


Ornaments in Cornice 2nd Scale.




Section on line C.D.




Roof over the Altar of Grimsbury Ch. Suffolk
with
SCALE OF 0 1 2 3 4 5 6 7 8 9 10 FEET
details 1/2 in Scale



From Aisle roofs Hastingfield Ch. Cambridgeshire




From Rood screen Trunch Church Norfolk.





B.


From roof of north porch Diss Church Norfolk



From roof of North Aisle Brockworth Church Gloucestershire










Section of Seat and Backboard




Elevation of Seat



All half, full size*From Screen in Rushden Church Northamptonshire.**B From South Door of Martham Church Norfolk.**Cusp terminations**from
Higham Ferrers Church Northamptonshire.**Finial from Debenham Church Suffolk.*




Bench ends from Crowcombe Church, Somersetshire.




From Worstead Church, Norfolk.



From Little Shelford Ch. Cambridgeshire.




From Worstead Church, Norfolk.




B From Crowcombe Ch. Somersetshire



From Bishop's Lydeard Church, Somersetshire.






Hinges


- A. From Erith Church, Kent
 B. From Westminster Abbey Church, Middlesex
 C. From Margaret Roding Church, Essex
 D. From St. Peter's Church, Colchester, Essex
 E. From Northfleet Church, Kent
 F. From St. Albans Abbey Church, Hertfordshire
 G. From Stanstead Abbots Church, Hertfordshire

Scale of 18 9 6 3 0 1 12 feet









Scutcheon from St. Albans Abbey Church Hertfordshire




Scutcheon from St. Mary's Stratford, Suffolk



Key plates from Westminster Abbey




From Westminster Abbey



SCALE OF 0 1 2 3 4 5 6 7 8 9 FEET

From South door of Hartley Church Kent


Section on line A. B.



Section C.D. full size.




Cirencester Ch. Gloucestershire 1/2 full size.




Gloucester Cathedral.


Brockworth Ch. Gloucestershire.




Horton Kirby Ch. Kent.




Spalding Ch. Lincolnshire.



SCALE OF 1 2 3 INCHES.




Barton Ch. Cambridgeshire full size.



Brockworth Ch. Gloucestershire. 1/2 full size.














Iron scroll-work from doors in Chester Cathedral and details one half full size.

SCALE OF FEET







*Closing Ring from Aldham Ch. Essex.**1½th scale.**Closing Ring from Eye Church, Suffolk.**½ full size.**with details full size.**Part of ironwork from doors of Sempringham Ch.**1½th scale**Hinge from Tinwill Ch. Rutland 1½th scale.*

*Metalwork from Doors of
Chapter House, York Minster*

1 1/2" Scale


Details one half full size



B











五

五




五

五

*From St Marys Norwich
with details full size.*



Scale of $\frac{1}{2}$ 6 9 1 2 Feet




A. *Tunstead Ch. Norfolk*



B. *Great Casterton Ch. Rutland*

C. *S^t Albans Abbey Church.*

D. *Market Deeping Ch. Lincolnshire*




F.




E.

E. *Floore Church, Northamptonshire.*

F. *Tunstead Church, Norfolk.*



D.







C.

SCALE OF 12 10 8 6 4 2 1 0 FEET








From Westminster Abbey Church





*From South Door of
Eaton Bray Church,
Bedfordshire.*



R




SCALE OF

FEET




Closing Rings from

Eaton Church Rutlandshire.



St. Nicholas Church
Gloucester.Ashby St. Ledger Church,
NorthamptonshireAshby St. Ledger Church,
Northamptonshire.

and Marcham Church, Norfolk.





B









From Woolton Church Bedfordshire.





From Sutton at Hone Church Kent.




From Oundle Church, Northamptonshire.



From




- A. *Potterspury Church, Northampton^{co}.*
 B. *Raunds Church, Northamptonshire.*
 C. *S^t Albans Abbey Church, Herts.*
 D. *Rothley Church, Leicestershire.*
 E. *Trull Church, Somersetshire.*
 F. *Rushden Church, Northamptonshire.*
 G. *Filby Church, Norfolk.*
 H. *Ashby S^t Ledger Church, Northants.*




From Martham Church, Norfolk.








Section



Inside Elevation



Section on line A.B.




Plan

Scale of 10 20 30 40 50 60 70 feet






















Norman Stringcourses.





Specimens of Dogtooth.




Specimens of mullions
1/2 full size




Tower basement mouldings 3/4 to 1 foot




Patstead, Suffolk.





Boxgrove, Sussex.




Boxgrove, Sussex.




S^t. Martin's, Leicester.



Cottismore, Rutlandshire.



Greatham, Rutlandshire.




Wellingborough, Northamptonshire.

Specimens of Spire Tables



Achurch, Northamptonshire.



G/C
L/B
N



GETTY RESEARCH INSTITUTE



3 3125 01499 1463

